

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
353	(12&13)WRS-4	WILL	608	41
STA.		TO STA.		
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				

STATION	TEMPORARY FENCE (FOOT)	TREE TRUNK PROTECTION (EACH)	TREE ROOT PRUNING (EACH)	TOPSOIL FURNISH AND PLACE, 4" (SQYD)	TOPSOIL FURNISH AND PLACE, 8" (SQYD)	TOPSOIL FURNISH AND PLACE, 24" (SQYD)	COMPOST FURNISH AND PLACE, 4" (SQYD)	SELECTIVE MOWING STAKES (EACH)	SEEDING, CLASS 2A (ACRES)	SEEDING, CLASS 4 (ACRES)	SEEDING, CLASS 5A (ACRES)	SEEDING, CLASS 4B (MODIFIED) (ACRES)	MULCH, METHOD 2 (ACRES)	EROSION CONTROL BLANKET (SQYD)	SODDING, SALT TOLERANT (SQYD)
	20101000	20101100	20101200	21101615	21101630	21101685	21101815	25000775	25000210	25000310	25000322	X2502024	25100115	25100630	25200110
U.S. ROUTE 30 410+00 TO 423+00	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
423+00 TO 435+00	370	2	2	2,658	2,127	39	3,274	23	0.3	0.7	0	0	0	27,636	2,767
435+00 TO 450+00	247	8	8	2,909	7,555	1,964	9,921	44	0.9	1.7	0	0.3	3.0	46,476	2,987
450+00 TO 465+00	0	0	0	4,849	4,058	1,531	8,472	32	1.0	1.8	0	0	0	52,876	2,380
465+00 TO 480+00	244	15	15	3,420	4,972	1,338	4,362	39	1.3	0.9	0.2	0	0	40,108	2,024
480+00 TO 495+00	487	22	22	4,273	9,030	993	9,923	20	0.8	1.3	0.1	0.8	2.1	41,264	1,597
495+00 TO 510+00	1,534	70	70	5,753	5,150	1,061	2,636	18	1.9	0.5	0.1	0	0	44,908	1,280
510+00 TO 525+00	790	47	47	4,685	4,529	930	1,852	24	1.7	0.3	0.1	0	0	66,855	2,117
525+00 TO 539+00	187	8	8	3,314	3,223	391	685	11	1.0	0.2	0.1	0	0	33,404	1,956
539+00 TO 554+00	160	4	4	1,682	7,254	1,166	50	2	1.7	0.1	0	0	0	41,788	1,590
554+00 TO 569+00	93	5	5	2,762	6,479	2,011	1,494	29	1.9	0.3	0	0	0	47,540	1,987
569+00 TO 584+00	0	0	0	3,664	5,996	510	596	11	1.6	0.1	0	0	0	32,874	2,502
584+00 TO 591+10.14	0	0	0	1,559	3,426	1,930	0	0	1.3	0	0	0	0	20,056	777
94TH AVE 525+72 TO 529+00	0	0	0	1,073	0	0	0	0	0.1	0	0	0	0	2,568	444
93RD AVE 546+65 TO 549+00	30	1	1	0	0	0	2,797	10	0	0.6	0	0	0.9	4,234	0
PFEIFFER RD 593+50 TO 598+00	160	4	4	1,711	0	0	0	0	0.3	0	0	0	0	5,014	428
84TH AVE 701+15 TO 703+67.22	54	2	2	1,366	0	0	323	2	0.2	0.1	0.1	0	0	5,396	599
HILLSIDE RD 745+30 TO 749+00	40	1	1	1,924	0	0	390	5	0.3	0.1	0	0	0	5,934	297
80TH AVE 794+89.46 TO 804+25.34	0	0	0	3,405	0	0	0	0	0.5	0	0	0	0	8,624	774
HUNTER WOODS/ FRANKFORT SQ. 896+32.18 TO 903+86	0	0	0	560	0	0	0	0	0.1	0	0	0	0	484	220
HARLEM AVENUE 981+31.38 TO 989+00	0	0	0	3,425	0	0	2,337	32	0.5	0.5	0	0	0	15,304	983
989+00 TO 998+00	130	0	0	5,111	0	0	1,887	33	0.8	0.4	0	0	0	48,362	1,367
1002+00 TO 1011+84.62	0	0	0	1,270	4,485	1,841	2,359	38	1.3	0.5	0	0	0	21,482	1,135
STAGE 3 REPLACEMENT	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
TOTALS	4,526	185	185	61,373	68,284	15,705	53,358	373	19.5	10.1	0.7	1.1	6.0	613,157	30,211
								ROUNDED	19.50	10.25	0.75	1.25	6.00		

LOCATION	STONE RIPRAP, CLASS A3 (SQYD)
	28100105
FOR USE AT CURB AND GUTTER TRANSITIONS (AS SHOWN ON DETAIL SHEET NO. 442)	
82ND AVE, LT	1.8
82ND AVE, RT	6.2
79TH AVE, LT	3.6
79TH AVE, RT	3.6
78TH AVE, LT	3.6
78TH AVE, RT	3.6
PFEIFFER RD, LT	3.6
PFEIFFER RD, RT	3.6
84TH AVE, LT	3.6
84TH AVE, RT	3.6
80TH AVE, LT	5.3
80TH AVE, RT	5.3
HARLEM AVE, LT	8.9
HARLEM AVE, RT	8.9
HARLEM AVE, LT	12.7
HARLEM AVE, RT	12.7
FOR USE DURING STAGE 1 CONSTRUCTION (AS SHOWN ON SHEET NO. 92)	
STA. 520+00, RT	26.3
TOTAL	117

STATION	REMOVE SUBDIVISION MONUMENT SIGN (EACH)	REMOVE DECORATIVE ARBOR (EACH)
	X0327029	X0327030
U.S. ROUTE 30 488+54, RT	1	
489+93, RT	1	
488+89, RT		1
489+61, RT		1
TOTAL	2	2

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

U.S. ROUTE 30
SCHEDULE OF QUANTITIES

SCALE: VERT. DRAWN BY DJK
 HORIZ. CHECKED BY JRV
 DATE 6/11/2010