

PAY ITEM #	DESCRIPTION	UNIT	TOTAL QUANTITY	URBAN			OVER SIZED STORM SEWER												
				ROADWAY 80% FEDERAL 20% STATE	SPECIAL BRIDGE 80% FEDERAL 20% STATE	0003	0040	0040	0040										
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	7448	7448															
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	2050	2050															
20101000	TEMPORARY FENCE	FOOT	200	200															
* 20101100	TREE TRUNK PROTECTION	EACH	2	2															
* 20101200	TREE ROOT PRUNING	EACH	2	2															
20200100	EARTH EXCAVATION	CU YD	148602	148602															
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	82156	82156															
20400800	FURNISHED EXCAVATION	CU YD	49371	49371															
20800150	TRENCH BACKFILL	CU YD	30356	18112			3669	8575											
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	2608	2608															
* 21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	97889	97889															
* 21101630	TOPSOIL FURNISH AND PLACE, 8"	SQ YD	64056	64056															
* 21101685	TOPSOIL FURNISH AND PLACE, 24"	SQ YD	14671	14671															
* 21101815	COMPOST FURNISH AND PLACE, 4"	SQ YD	42311	42311															
* 25000100	SEEDING, CLASS 1	ACRE	2.25	2.25															
* 25000210	SEEDING, CLASS 2A	ACRE	11	11															
* 25000310	SEEDING, CLASS 4	ACRE	20.75	20.75															
* 25000314	SEEDING, CLASS 4B	ACRE	0.25	0.25															
* 25000322	SEEDING, CLASS 5A	ACRE	8.75	8.75															
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	1860	1860															
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	1860	1860															
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	1860	1860															
* 25100630	EROSION CONTROL BLANKET	SQ YD	513425	513425															
* 25200110	SODDING, SALT TOLERANT	SQ YD	55483	55483															
* 25200200	SUPPLEMENTAL WATERING	UNIT	1440	1440															
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	7415	7415															
28000305	TEMPORARY DITCH CHECKS	FOOT	6220	6220															
28000400	PERIMETER EROSION BARRIER	FOOT	21351	21351															
28000510	INLET FILTERS	EACH	900	900															
28100105	STONE RIPRAP, CLASS A3	SQ YD	551	551															
28100113	STONE RIPRAP, CLASS A7	SQ YD	269	269															
28100205	STONE RIPRAP, CLASS A3	TON	90		90														

*SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SUMMARY OF QUANTITIES
 U.S. RTE. 30 (LINCOLN HIGHWAY)
 SCALE : 1" = 50'
 DATE : / /
 DRAWN BY : BAE
 CHECKED BY : CB