

CONTRACT NO. 62479

PAY ITEM #	DESCRIPTION	UNIT	TOTAL QUANTITY	URBAN			SIDEWALK				BIKE PATH					ROADWAY 100% FRANKFORT (CEDAR RD)
				ROADWAY 80% FEDERAL 20% STATE	BRIDGE 80% FEDERAL 20% STATE	SPECIAL BRIDGE 80% FEDERAL 20% STATE	SAFETY 80% STATE 20% NEW LENOX	SAFETY 80% STATE 20% MOKENA	SAFETY 80% STATE 20% FRANKFORT	SAFETY 80% FEDERAL 20% STATE	SAFETY 80% STATE 20% NEW LENOX	SAFETY 80% STATE 20% MOKENA	SAFETY 80% STATE 20% FRANKFORT	SAFETY 80% STATE 20% FPDWC	SAFETY 80% FEDERAL 20% STATE	
28100207	STONE RIPRAP, CLASS A4	TON	390	0003	0010	0040	0021	0021	0021	0021	0021	0021	0021	0021	0021	0004
28100209	STONE RIPRAP, CLASS A5	TON	465		295	95										
28100211	STONE RIPRAP, CLASS A6	TON	250			250										
28200200	FILTER FABRIC	SQ YD	1654	269	410	975										
31101200	SUBBASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	306	306												
31101400	SUBBASE GRANULAR MATERIAL, TYPE B 6"	SQ YD	834	834												
31200502	STABILIZED SUBBASE - HOT-MIX ASPHALT, 4 1/2"	SQ YD	223079	223079												
35101500	AGGREGATE BASE COURSE, TYPE B	CU YD	775	775												
35101800	AGGREGATE BASE COURSE, TYPE B 6"	SQ YD	22459								8621	2198	1366	2679	7595	
35501308	HOT-MIX ASPHALT BASE COURSE, 6"	SQ YD	3277	2758												519
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQ YD	5169	5169												
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	106	46							18	5	3	6	16	12
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	18	18												
40600895	CONSTRUCTING TEST STRIP	EACH	1	1												
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	53	53												
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	117	117												
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	771	165												606
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	5631	1262							1448	369	229	450	1276	597
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	1010	1010												
40701861	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 9"	SQ YD	8951	8951												
40701956	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 13 3/4"	SQ YD	499	499												
40800030	AGGREGATE (PRIME COAT)	TON	30	25												5
42000416	PORTLAND CEMENT CONCRETE PAVEMENT 9 3/4" (JOINTED)	SQ YD	193039	193039												
42001300	PROTECTIVE COAT	SQ YD	229336	229311												25
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	90	90												
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	115670				27410	19379	12426	17082	18619	298	4660	1470	14141	185
42400800	DETECTABLE WARNINGS	SQ FT	2089				152	75	132	469	563	41	105	40	482	30
44000100	PAVEMENT REMOVAL	SQ YD	211649	207177												4472
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	16740	16221												519
44000300	CURB REMOVAL	FOOT	2040	2040												
44000400	GUTTER REMOVAL	FOOT	128	128												
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	20750	20628												122

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**SUMMARY OF QUANTITIES**  
 U.S. RTE. 30 (LINCOLN HIGHWAY)

SCALE : 1" = 50'  
 DATE : / /

DRAWN BY : BAE  
 CHECKED BY : GB