

ROADWAY SCHEDULE

LOCATION	40603335	42300400	42400200	42400800	48101500	60107600	60600095	60605000	60600605	60603800	60618300	60619200	60620000	60620200	60624600	60619600	Z0073345	X6062100	Z0001050
	HMA SC "D" N50 (1 1/2")	PCC DRIVEWAY PAVT 8	PC CONC SIDEWALK 5	DETECTABLE WARNINGS	AGGREGATE SHLDS B 6	PIPE UNDER DRAINS 4"	CLASS S1 CONC OUTLET	COMB CC&G TB6. 24	CONC CURB TB	COMB CC&G TB6. 12	CONC MEDIAN SURF 4	CONC MED TSB6. 06	CONC MED TSB6. 24	CONC MED TSB6. 24 MOD	CORRUGATED MED	CONC MED TSB6. 12	SLEEPER SLAB	STAB MED SURF 12	AGG SUBGRADE 12
	TON	SQ YD	SQ FT	SQ FT	SQ YD	FOOT	CU YD	FOOT	FOOT	FOOT	SQ FT	SQ FT	SQ FT	SQ FT	SQ FT	FOOT	FOOT	SQ YD	SQ YD
STA 133+00 TO STA 146+00	0	0	5422	40	0	252	0	2160	337	0	0	0	0	0	0	0	0	0	107
STA 146+00 TO STA 161+00	0	0	10475	204	0	312	12	3582	326	0	0	0	0	0	0	0	0	0	674
STA 161+00 TO STA 174+00	0	0	7922	63	3	240	6	2990	268	0	0	0	0	0	0	0	0	0	594
STA 174+00 TO STA 189+00	0	0	8420	87	27	479	3	3341	124	0	0	0	0	0	0	0	0	0	757
STA 189+00 TO STA 202+00	0	0	7252	160	0	354	6	3831	448	0	0	0	0	3743	2432	0	0	0	757
STA 202+00 TO STA 215+00	0	0	168	0	0	287	0	5200	0	0	0	0	0	0	0	0	0	0	309
STA 215+00 TO STA 230+00	0	0	2581	80	0	515	6	3707	494	0	3077	0	0	7199	0	0	188	0	158
STA 230+00 TO STA 245+00	0	0	5373	97	0	411	12	3970	265	0	2119	0	0	6785	0	0	0	0	254
STA 245+00 TO STA 260+00	0	0	2837	122	0	435	13	4507	0	0	0	0	97	4754	0	293	0	0	640
STA 260+00 TO STA 275+00	0	0	3082	137	0	370	0	4945	0	0	0	0	96	3525	0	417	0	0	197
STA 275+00 TO STA 290+00	0	0	17305	132	0	306	0	4824	31	0	0	0	0	3496	0	0	0	0	180
STA 290+00 TO STA 303+00	0	0	3481	0	0	55	0	1167	31	0	0	0	0	5661	0	0	0	0	744
STA 303+00 TO STA 318+00	0	0	676	0	0	70	0	1153	75	0	0	0	0	3423	0	0	0	0	0
STA 318+00 TO STA 331+00	0	0	7258	105	0	304	0	4149	68	0	0	0	96	3021	0	0	0	0	94
STA 331+00 TO STA 346+00	0	0	2014	66	21	358	6	5084	141	0	0	0	97	3106	0	0	0	0	216
STA 346+00 TO STA 361+00	0	0	1727	105	0	349	0	5334	69	0	0	0	96	2083	0	0	0	0	158
STA 361+00 TO STA 374+00	0	0	6820	234	0	345	0	3361	0	0	0	0	97	5063	0	0	0	0	71
STA 374+00 TO STA 389+00	0	0	1193	22	0	382	0	4341	124	120	0	0	97	5384	0	0	0	0	0
STA 389+00 TO STA 404+00	0	0	9662	305	7	348	9	4065	144	0	0	0	0	6483	0	0	0	0	627
STA 404+00 TO STA 411+20	0	0	6750	51	0	192	0	3088	314	0	0	108	96	635	0	0	0	834	0
ELSNER	0	0	0	0	0	0	0	100	0	0	0	0	0	0	0	0	0	0	0
BROOKSIDE AND HACKBERRY	0	0	117	11	0	0	3	678	0	0	0	0	0	0	0	0	0	0	1313
LOCUST ST.	0	0	2415	0	74	0	6	249	0	0	0	0	0	0	0	0	0	0	1505
MARLEY RD.	0	0	152	0	0	0	0	0	0	353	0	0	0	0	0	0	0	0	596
SCHOOHOUSE ROAD	200	0	603	0	0	0	0	408	48	0	0	0	0	0	0	0	0	0	0
TALL GRASS DR.	0	0	1396	20	0	0	0	280	0	0	0	0	0	0	0	0	0	0	496
WEST CIRCLE DR.	0	0	0	0	0	0	6	134	0	0	0	0	0	0	0	0	0	0	869
OWENS RD & RIDGEMORE RD	0	90	385	19	0	0	0	412	68	0	0	0	0	0	0	0	0	0	1374
CEDAR RD	0.0	0	185	30	1690	0	3.1	0	0	161.0	0	0.0	0.0	0	0	0.0	0.0	0.0	4809
TOTALS	200	90	115670	2089	1822	6364	93	77056	3373	634	5196	108	771	69269	2432	710	576	834	16741

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION SCHEDULE OF QUANTITIES U.S. RTE. 30 (LINCOLN HIGHWAY) SCALE : 1" = 50' DATE : 10/12/10 DRAWN BY : BAE CHECKED BY : CB
NAME	DATE	