

PAVEMENT MARKING SCHEDULE

LOCATION	78000100	78000200	78000400	78000600	78000650	78008300	78008310	78008330	78008350	78008370	78100100	78100300
	THERMOPLASTIC PAVEMENT MARKING					POLYUREA PAVEMENT MARKING TYPE II					RAISED REFL	REPLACEMENT
	LTY & SYM	LINE 4	LINE 6	LINE 12	LINE 24	LTY & SYM	LINE 4	LINE 6	LINE 12	LINE 24	PAVT MKR	REFLECTOR
SQ FT	FOOT	FOOT	FOOT	FOOT	SQ FT	FOOT	FOOT	FOOT	FOOT	EACH	EACH	
STA 118+00 TO STA 133+00	104.0	2220	205	40	0	0.0	0	0	28	66	0	
STA 133+00 TO STA 146+00	67.6	833	149	40	0	130	3085	390	395	120	0	
STA 146+00 TO STA 161+00	0.0	140	0	0	0	244.4	4017	1245	416	144	0	
STA 161+00 TO STA 174+00	0.0	183	0	0	0	171.6	3828	584	409	48	129	
STA 174+00 TO STA 189+00	0.0	141	71	0	0	182.0	2158	1813	916	111	124	
STA 189+00 TO STA 202+00	0.0	58	0	0	0	145.6	634	1476	969	119	92	
STA 202+00 TO STA 215+00	0.0	0	0	0	0	36.4	640	338	7	0	69	
STA 215+00 TO STA 230+00	0.0	0	0	0	0	535.6	1483	3690	742	214	118	
STA 230+00 TO STA 245+00	0.0	0	0	0	0	254.8	862	2245	815	144	114	
STA 245+00 TO STA 260+00	0.0	39	0	0	0	182.0	756	1865	1126	85	105	
STA 260+00 TO STA 275+00	0.0	0	0	0	0	109.2	838	1091	654	72	94	
STA 275+00 TO STA 290+00	0.0	0	0	0	0	145.6	680	1353	133	82	94	
STA 290+00 TO STA 303+00	145.6	485	1914	257	0	0.0	110	25	0	0	46	
STA 303+00 TO STA 318+00	254.8	525	2372	923	134	57.2	100	423	61	0	34	
STA 318+00 TO STA 331+00	0.0	50	0	0	0	124.8	688	1412	623	65	82	
STA 331+00 TO STA 346+00	0.0	0	0	0	0	109.2	818	968	91	52	94	
STA 346+00 TO STA 361+00	0.0	50	0	0	0	72.8	816	779	588	43	86	
STA 361+00 TO STA 374+00	0.0	0	0	0	0	182.0	540	1626	638	79	94	
STA 374+00 TO STA 389+00	0.0	0	0	0	0	145.6	750	1486	169	26	104	
STA 389+00 TO STA 404+00	0.0	72	0	0	0	254.8	773	2274	1703	135	114	
STA 404+00 TO STA 419+00	145.6	260	635	0	49	36.4	398	455	371	29	70	
SUBTOTAL	717.6	5056	5346	1260	183	3120.0	23974	25538	10826	1542	1993	
MARLEY RD (S)	41.6	1175	114	122	0	0.0	403	385	521	38	26	
MARLEY RD (N)	20.8	2055	19	58	0	15.6	437	287	0	40	35	
SUBTOTAL	62.4	3230	133	180	0	15.6	840	672	521	78	61	
SCHOOLHOUSE (S)	72.8	1549	475	28	0	72.8	151	321	437	53	40	
SCHOOLHOUSE (N)	36.4	2144	212	44	0	36.4	196	94	255	46	44	
SUBTOTAL	109.2	3693	687	72	0	109.2	347	415	692	99	84	
JOLIET HWY (S)	36	117	59	0	0	0	113	56	0	29	6	
W CIRCLE DR (N)	36	106	53	0	0	0	127	184	298	28	9	
SUBTOTAL	72.8	223	112	0	0	0.0	240	240	298	57	15	
OWENS (S)	73	1407	193	0	0	0	99	241	0	38	28	
RIDGEMORE (N)	36	129	64	0	0	0	97	168	296	25	9	
SUBTOTAL	109.2	1536	257	0	0	0.0	196	409	296	63	37	
ELSNER RD (S)	73	132	66	0	0	0	220	250	0	29	15	
SUBTOTAL	73	132	66	0	0	0	220	250	0	29	15	
BROOKSIDE COMMONS (S)	0	0	0	0	0	0	77	250	45	47	0	
HACKBERRY RD (N)	0	270	0	0	0	0	86	196	494	40	0	
SUBTOTAL	0.0	270	0	0	0	0.0	163	446	539	87	0	
LOCUST (S)	0	0	0	0	0	36	682	270	19	34	16	
LOCUST (N)	21	584	53	0	0	16	200	254	397	33	18	
SUBTOTAL	20.8	584	53	0	0	52.0	882	524	416	67	34	
SIDE ROAD SUBTOTAL	447.2	9668	1308	252	0	176.8	2888	2956	2762	480	246	
TOTAL	1164.8	14724	6654	1512	183	3296.8	26862	28494	13588	2022	2239	

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES
 U.S. RTE. 30 (LINCOLN HIGHWAY)

SCALE : 1" = 50'
 DATE : 10/12/10

DRAWN BY : BAE
 CHECKED BY : GB