

DRAINAGE REMOVAL SCHEDULE

LOCATION	56400100	60250200	60251520	60255500	60257900	60260050	60260100	60261320	60265700	60500040	60500050	60500060	X6026050	X6025300	X6026620
	FIRE HYDNPTS TO BE MVD	CB ADJUST	CB ADJ NEW T11V F&G	MAN ADJUST	MAN RECONST	SAN MAN RECONST	INLETS ADJUST	INLET ADJ NEW T11VF&G	VV ADJUST	REMOV MANHOLES	REMOV CATCH BAS	REMOV INLETS	SANITARY MANHOLE ADJ	CB ADJUST SPL	INLETS ADJUST SPL
	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH
STA 118+00 TO STA 133+00	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
STA 133+00 TO STA 146+00	1	0	0	8	0	1	0	0	2	1	7	0	4	0	0
STA 146+00 TO STA 161+00	5	1	0	3	0	0	0	0	5	0	8	0	6	0	0
STA 161+00 TO STA 174+00	2	0	0	0	0	0	0	0	2	1	6	0	4	0	0
STA 174+00 TO STA 189+00	3	0	0	0	0	0	0	0	1	1	5	0	6	0	0
STA 189+00 TO STA 202+00	5	0	0	0	0	0	0	0	0	0	4	0	1	0	0
STA 202+00 TO STA 215+00	0	0	0	0	0	0	0	0	1	0	4	0	1	0	0
STA 215+00 TO STA 230+00	1	3	0	1	0	0	0	0	0	2	18	2	0	0	0
STA 230+00 TO STA 245+00	3	0	0	1	0	0	0	0	0	1	5	2	0	0	0
STA 245+00 TO STA 260+00	0	0	0	0	0	0	0	0	0	1	5	0	0	0	0
STA 260+00 TO STA 275+00	1	0	0	0	0	0	0	0	0	1	0	0	0	0	0
STA 275+00 TO STA 290+00	5	0	0	3	1	1	0	0	2	0	4	2	2	0	0
STA 290+00 TO STA 303+00	1	0	1	0	1	0	0	8	0	0	2	2	2	0	0
STA 303+00 TO STA 318+00	1	1	1	2	0	0	0	2	1	1	2	1	1	0	0
STA 318+00 TO STA 331+00	4	2	0	4	0	0	0	0	4	0	3	2	6	0	0
STA 331+00 TO STA 346+00	4	0	0	1	0	0	0	0	2	2	1	0	5	0	0
STA 346+00 TO STA 361+00	1	0	0	0	0	0	0	0	0	4	0	0	0	0	0
STA 361+00 TO STA 374+00	6	2	0	0	1	0	0	0	7	1	7	0	6	0	0
STA 374+00 TO STA 389+00	2	0	0	0	1	0	0	0	2	0	4	0	0	0	0
STA 389+00 TO STA 404+00	5	0	0	0	0	0	0	0	5	1	2	1	0	0	0
STA 404+00 TO STA 434+00	3	3	0	1	0	0	0	0	3	7	12	1	0	0	0
SUBTOTAL	53	12	2	24	4	2	0	10	37	24	99	14	44	0	0
MARLEY (S)	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
MARLEY (N)	1	2	0	0	0	0	0	0	1	0	0	0	0	0	0
SUBTOTAL	1	2	0	0	0	0	0	0	1	0	0	0	0	0	0
SCHOOLHOUSE (S)	1	0	0	0	0	0	0	0	0	0	0	0	0	0	0
SCHOOLHOUSE (N)	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
SUBTOTAL	1	0	0	0	0	0	0	0	0	0	0	0	0	0	0
JOLIET HWY (S)	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
W CIRCLE DR (N)	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
SUBTOTAL	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
OWENS (S)	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
RIDGEMORE (N)	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
SUBTOTAL	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
ELSNER RD (S)	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
SUBTOTAL	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
CEDAR LANE (400+00 TO 410+00)	0	7	0	2	0	0	1	0	0	0	0	0	0	0	0
CEDAR LANE (410+00 TO 420+00)	0	1	0	0	0	0	0	0	0	0	0	0	3	0	0
SUBTOTAL	0	8	0	2	0	0	1	0	0	0	0	0	3	0	0
BROOKSIDE COMMONS (S)	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
HACKBERRYRD (N)	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
SUBTOTAL	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
LOCUST (S)	1	2	0	1	0	0	0	0	0	1	0	0	0	0	0
LOCUST (N)	1	0	0	0	0	0	0	0	0	0	0	0	0	0	0
SUBTOTAL	2	2	0	1	0	0	0	0	0	1	0	0	0	0	0
SIDE ROAD SUBTOTAL	4	12	0	3	0	0	1	0	1	1	0	0	3	0	0
TEMPORARY STRUCTURES REMOVAL		3		3						11	40	0	5	10	
TOTALS	57	27	2	30	4	2	1	10	38	36	139	15	47	5	10

15

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		<p align="center">SCHEDULE OF QUANTITIES</p> <p align="center">U.S. RTE. 30 (LINCOLN HIGHWAY)</p> <p>SCALE : 1" = 50' DRAWN BY : BAE</p> <p>DATE : 10/12/10 CHECKED BY :GB</p>