

**DRAINAGE REMOVAL SCHEDULE**

LOCATION	50105220						55100500	55100700	55100900	55101200	55101400	55101600	55101900
	PIPE CULVERT REMOVAL						STORM SEWER	STORM SEWER	STORM SEWER	STORM SEWER	STORM SEWER	STORM SEWER	STORM SEWER
	12" DIA FOOT	15" DIA FOOT	18" DIA FOOT	24" DIA FOOT	30" DIA FOOT	36" DIA FOOT	REM 12 FOOT	REM 15 FOOT	REM 18 FOOT	REM 24 FOOT	REM 30 FOOT	REM 36 FOOT	REM 48 FOOT
STA 118+00 TO STA 133+00	0	0	0	0	0	0	0	0	0	0	0	0	
STA 133+00 TO STA 146+00	0	37	0	0	107	0	350	0	157	0	0	0	
STA 146+00 TO STA 161+00	118	0	0	0	0	0	71	147	0	250	0	0	
STA 161+00 TO STA 174+00	86	0	0	0	72	0	279	269	48	66	0	0	
STA 174+00 TO STA 189+00	0	69	0	0	0	0	322	203	0	0	119	0	
STA 189+00 TO STA 202+00	0	54	146	0	0	0	6	469	147	0	0	0	
STA 202+00 TO STA 215+00	17	0	0	0	0	58	81	16	33	54	0	0	
STA 215+00 TO STA 230+00	25	20	0	0	0	0	848	249	0	0	0	0	
STA 230+00 TO STA 245+00	0	58	0	0	0	0	63	122	325	287	0	0	
STA 245+00 TO STA 260+00	0	106	45	0	0	0	0	153	0	134	24	0	
STA 260+00 TO STA 275+00	0	97	0	0	0	0	0	0	3	0	0	0	
STA 275+00 TO STA 290+00	0	0	126	153	0	0	206	0	208	0	0	0	
STA 290+00 TO STA 303+00	0	0	0	0	0	0	184	0	0	107	108	0	
STA 303+00 TO STA 318+00	0	0	0	0	0	0	76	0	0	0	0	0	
STA 318+00 TO STA 331+00	0	0	185	0	0	73	439	29	0	84	0	0	
STA 331+00 TO STA 346+00	57	25	20	0	0	0	28	15	0	431	0	0	
STA 346+00 TO STA 361+00	0	234	0	0	0	0	86	725	258	300	0	0	
STA 361+00 TO STA 374+00	110	123	0	0	0	0	160	272	270	161	0	0	
STA 374+00 TO STA 389+00	117	0	23	0	0	0	21	0	0	111	0	0	
STA 389+00 TO STA 404+00	0	165	219	58	0	0	268	0	0	0	0	0	
STA 404+00 TO STA 434+00	0	0	0	0	0	0	808	134	89	0	0	0	
SUBTOTAL	530	988	764	211	179	131	4296	2803	1720	2142	132	119	
MARLEY (S)	0	0	0	0	0	0	0	0	0	0	0	0	
MARLEY (N)	0	0	0	0	0	0	0	0	0	0	0	0	
SUBTOTAL	0	0	0	0	0	0	0	0	0	0	0	0	
SCHOOLHOUSE (S)	0	0	0	0	0	0	0	0	0	0	0	0	
SCHOOLHOUSE (N)	0	0	0	0	0	0	0	0	0	0	0	0	
SUBTOTAL	0	0	0	0	0	0	0	0	0	0	0	0	
JOLIET HWY (S)	0	0	0	0	0	0	0	0	0	0	0	0	
W CIRCLE DR (N)	0	0	0	0	0	0	0	0	0	0	0	0	
SUBTOTAL	0	0	0	0	0	0	0	0	0	0	0	0	
OWENS (S)	0	0	0	0	0	0	0	0	0	0	0	0	
RIDGEMORE (N)	0	0	0	0	0	0	0	0	0	0	0	0	
SUBTOTAL	0	0	0	0	0	0	0	0	0	0	0	0	
ELSNER RD (S)	0	0	0	0	0	0	0	0	0	0	0	0	
SUBTOTAL	0	0	0	0	0	0	0	0	0	0	0	0	
CEDAR LANE (400+00 TO 410+00)	0	0	0	0	0	0	0	0	0	0	0	0	
CEDAR LANE (410+00 TO 420+00)	0	0	0	0	0	0	0	0	0	0	0	0	
SUBTOTAL	0	0	0	0	0	0	0	0	0	0	0	0	
BROOKSIDE COMMONS (S)	0	0	0	0	0	0	0	0	0	0	0	0	
HACKBERRY RD (N)	0	0	0	0	0	0	0	0	0	0	0	0	
SUBTOTAL	0	0	0	0	0	0	0	0	0	0	0	0	
LOCUST (S)	0	11	0	0	0	0	11	0	0	0	0	0	
LOCUST (N)	32	0	0	0	0	0	0	0	0	0	0	0	
SUBTOTAL	32	11	0	0	0	0	11	0	0	0	0	0	
SIDE ROAD SUBTOTAL	32	11	0	0	0	0	11	0	0	0	0	0	
TEMPORARY STRUCTURES REMOVAL		114	107	44	5	58	188	125	158	376	35	35	
TOTALS	562	1113	871	255	184	189	4495	2928	1878	2518	167	119	35

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		<p align="center"><b>SCHEDULE OF QUANTITIES</b></p> <p align="center">U.S. RTE. 30 (LINCOLN HIGHWAY)</p> <p>SCALE : 1" = 50'      DRAWN BY : BAE</p> <p>DATE : 10/12/10      CHECKED BY : GB</p>