F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
353	(12&13)WRS-3	WILL	1235	50
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

EARTHWORK SCHEDULE

LOCATION		EARTH EXCAVATION CU YD					TOPSOIL EXCAVATION CU YD					EMBANKMENT CU YD					UNDERCUT CU YD					PGES CU YD					STRUCTURE EXCAVATION CU YD					EXCAVATION USED IN EMBANKMENT ADJUSTED OR SHRINKAGE CU YD					EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) CU YD				
STA	STA	PSTG 1	STG 1	STG 2	STG 3	STG 4	PSTG 1	STG 1	STG 2	STG 3	STG 4	PSTG 1	STG 1	STG 2	STG 3	STG 4	PSTG 1	STG 1	STG 2	STG 3	STG 4	PSTG 1	STG 1	STG 2	STG 3	STG 4	PSTG 1	STG 1	STG 2	STG 3	STG 4	PSTG 1	STG 1	STG 2	STG 3	STG 4	PSTG 1	STG 1	STG 2	STG 3	STG 4
261+00	262+00	121	236	603	94	0	117	208	89	0	0	23	41	2	12	12	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	103	201	513	80	0	80	160	511	68	-12
262+00	263+00	128	140	384	67	0	123	203	64	0	0	41	108	23	13	13	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	108	119	327	57	0	67	11	304	44	-13
263+00	264+00	87	84	215	129	0	129	198	30	0	0	51	225	21	26	26	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	74	72	183	109	0	23	-154	161	83	-26
264+00	265+00	239	74	143	124	0	186	221	0	0	0	57	455	0	27	27	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	203	62	122	105	0	146	-393	122	78	-27
265+00	266+00	495	111	408	123	0	211	252	37	0	0	32	492	29	27	27	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	421	94	347	105	0	389	-398	318	77	-27
266+00	267+00	811	151	694	123	0	205	243	69	0	0	4	312	37	27	27	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	690	129	589	105	0	686	-183	553	77	-27
267+00	268+00	907	148	710	123	0	218	236	71	0	0	5	322	21	26	26	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	771	126	604	104	0	766	-196	583	78	-26
268+00	269+00	533	124	565	132	15	179	236	71	0	0	5	454	31	35	35	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	453	106	480	112	13	449	-348	448	78	-22
269+00	270+00	199	74	276	140	24	167	217	32	0	0	4	597	54	44	44	0	47	77	0	0	0	76	77	0	0	0	0	0	0	0	169	63	235	119	20	165	-534	181	75	-23
270+00	271+00	88	21	58	95	9	182	206	0	0	0	100	704	86	45	45	0	76	137	0	0	0	153	154	0	0	0	0	0	0	0	74	18	49	81	8	-26	-686	-36	35	-38
271+00	272+00	47	25	26	26	0	124	219	65	0	0	135	733	203	28	28	0	38	73	0	0	0	154	154	0	0	0	0	0	0	0	40	21	22	22	0	-95	-711	-181	-6	-28
272+00	273+00	6	25	38	0	0	62	190	127	0	0	70	637	259	4	4	0	8	12	0	0	0	155	154	0	0	0	0	0	0	0	5	21	33	0	0	-65	-616	-226	-4	-4
273+00	274+00	24	0	13	0	0	80	191	102	0	0	69	681	334	7	7	0	0	0	0	0	0	78	77	0	0	0	0	0	0	0	20	0	11	0	0	-49	-681	-324	-7	-7
274+00	275+00	18	0	0	36	0	95	234	83	0	0	158	635	354	25	25	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	15	0	0	31	0	-142	-635	-354	6	-25
275+00	276+00	0	45	60	90	0	83	242	89	0	0	173	374	159	27	27	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	38	51	77	0	-173	-335	-108	49	-27
276+00	277+00	231	212	359	121	0	112	229	66	0	0	51	140	33	17	12	1	0	0	0	0	1	0	0	0	0	0	0	0	0	0	196	181	306	103	0	145	41	272	85	-12
277+00	278+00	456	497	669	67	82	146	212	36	0	0	2	12	0	8	3	1	0	0	0	0	1	0	0	0	0	0	0	0	0	0	388	423	569	57	70	386	410	569	49	66
278+00	279+00	454	677	789	82	164	147	214	41	0	0	2	6	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	386	576	671	70	139	384	570	671	70	139
279+00	280+00	396	659	708	144	82	160	108	32	0	0	3	3	0	0	29	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	336	560	602	122	70	333	558	602	122	40
280+00	281+00	187	376	383	121		159	90	7	0		84	150	0	0		0	0	0	0		0	0	0	0		0	0	0	0		159	320	325	103		75	170	325	103	
281+00	282+00	27	71	109	89		97	194	61	0		109	468	36	5		0	0	0	0		0	0	0	0		0	0	0	0		23	60	93	75		-86	-407	57	71	
282+00	283+00	35	7	35	62		81	175	61	0		38	843	340	5		0	0	0	0		0	0	0	0		0	0	0	0		29	6	30	53		-9	-837	-310	48	
283+00	284+00	94	10	40	74		119	143	0	0		19	1123	741	0		0	0	0	0		0	0	0	0		0	0	0	0		80	8	34	62		61	-1115	-707	62	
284+00	285+00	152	10	46	81		126	145	0	0		14	1161	890	2		0	0	0	0		0	0	0	0		0	0	0	0		130	8	39	69		115	-1153	-851	67	
285+00	286+00	107	0	55	76		130	137	0	0		51	1089	865	5		0	0	0	0		0	0	0	0		0	0	0	0		91	0	47	65		40	-1089	-818	60	
286+00	287+00	21	0	28	36		64	65	0	0		43	687	560	3		0	0	0	0		0	0	0	0		0	0	0	0		18	0	24	31		-25	-687	-536	28	
287+00	288+00	209	0	52	48		61	52	0	0		14	578	492	0		0	0	0	0		0	0	0	0		0	0	0	0		178	0	44	41		164	-578	-448	41	
288+00	289+00	493	0	139	97		120	52	0	0		23	698	606	0		0	0	0	0		0	0	0	0		0	0	0	0		419	0	118	82		396	-698	-487	82	
289+00	290+00	479	0	153	90		154	0	0	0		45	414	421	0		0	0	0	0		0	0	0	0		0	0	0	0		407	0	130	77		362	-414	-291	77	
290+00	291+00	324	18	144	101		196	0	0	0		99	177	230	0		0	0	0	0		0	0	0	0		0	0	0	0		276	16	122	86		177	-161	-108	86	
291+00	292+00	221	18	179	110		209	0	0	0		152	62	179	0		0	0	0	0		0	0	0	0		0	0	0	0		188	16	153	93		36	-47	-26	93	
292+00	293+00	92	0	101	49		109	0	0	0		89	18	108	0		0	0	0	0		0	0	0	0		0	0	0	0		78	0	86	42		-11	-18	-22	42	
293+00	294+00				0					0					0					0					0					0					0					0	
294+00	295+00				0					0					0					0					0					0					0					0	
295+00	296+00				0					0					0					0					0					0					0					0	
296+00	297+00				0					0					0					0					0					0					0					0	
297+00	298+00				0					0					0					0					0					0					0					0	
298+00	299+00				0					0					0					0					0					0					0					0	
299+00	300+00				0					0					0					0					0					0					0					0	
300+00	301+00				0					0					0					0					0					0					0					0	
301+00	302+00				0					0					0					0					0					0					0					0	
302+00	303+00				0					0					0					0					0					0					0					0	
303+00	304+00																																								
304+00	305+00																																								
305+00	306+00																																								
306+00	307+00																																								
307+00	308+00																																								
308+00	309+00																																								
309+00	310+00					0					0					0					0					0					0					0					0
310+00	311+00					0					0					0					0					0					0					0					0
311+00	312+00					0					0					0					0					0					0					0					0
312+00	313+00					0					0					0					0					0					0					0					0
313+00	314+00					0					0					0					0					0					0					0					0
314+00	315+00					0					0					0					0					0					0					0					0
315+00	316+00		27		49	45		30		16	0		29		11	0		0		0	0		0		0	0		0		0	0		23		41	39		-6		30	39
316+00	317+00		27		63	78		68		17	0		100		56	8		0		0	0		0		0	0		0		0	0		23		54	66		-77		-2	58
317+00	318+00		18		19	52		138		2	25		107		147	16		0		0	0		0		0	0		0		0	0		15		16	44		-92		-131	28
318+00	319+00		111		98	20		100		0	25		167		233	8		0		0	0		0		0	0		0		0	0		94		83	17		-72		-150	9
319+00	320+00		102		97	23		96		101	0		260		314	17		0		0	0		0		0	0		0		0	0		87		83	20		-173		-231	3
320+00	321+00		75		6	46		195		260	0		161		306	34		0		0	0		0		0	0		0		0	0		64		5	39		-97		-301	5
321+00	322+00		334		1	46		233		159	0		72		297	36		0		0	0		0		0	0		0		0	0		284		1	39		212		-296	3
322+00	323+00		595		0	47		240		32	22		43		447	35		0		0	0		0		0	0		0		0	0		506		0	40		463		-447	5

A SHRINKAGE FACTOR OF 15% WAS USED FOR EARTH EXCAVATION ADJUSTMENT

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

U.S. RTE. 30 (LINCOLN HIGHWAY)

SCALE : 1" = 50'
DATE : 10/12/10

DRAWN BY : BAE
CHECKED BY : GB

DLZ ENGINEERS • ARCHITECTS • SCIENTISTS • PLANNERS • SURVEYORS
65 W. ALGONQUIN ROAD, SUITE 220 ARLINGTON HEIGHTS, IL 60005 TEL: (847) 640-0840

$FILE$ $DATE$ $TIME$