

EARTHWORK SCHEDULE

LOCATION		EARTH EXCAVATION				TOPSOIL EXCAVATION				EMBANKMENT				UNDERCUT				PGES				STRUCTURE EXCAVATION				EXCAVATION USED IN EMBANKMENT ADJUSTED OR SHRINKAGE				EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)																						
		CU YD				CU YD				CU YD				CU YD				CU YD				CU YD				CU YD																										
STA	STA	PSTG 1	STG 1	STG 2	STG 3	STG 4	PSTG 1	STG 1	STG 2	STG 3	STG 4	PSTG 1	STG 1	STG 2	STG 3	STG 4	PSTG 1	STG 1	STG 2	STG 3	STG 4	PSTG 1	STG 1	STG 2	STG 3	STG 4	PSTG 1	STG 1	STG 2	STG 3	STG 4	PSTG 1	STG 1	STG 2	STG 3	STG 4																
TALL GRASS DR.																																																				
274+50	275+00											94					0						0						0						0						0						-94					
275+00	276+00		0				27					220					0						0						0						0						26						-194					
276+00	277+00		0				71					31					0						0						0						26						-6											
OWENS/RIDGEMORE																																																				
100+00	101+00			98				15				6					0						0						0						0						83						77					
101+00	102+00			98				30				29					0						0						0						83						54											
106+00	107+00		48					20				9					0						0						0						41						32											
107+00	108+00		10					6				3					0						0						0						8						6											
ELSNER																																																				
397+00	398+00			170				78				22					0						0						0						145						123											
398+00	399+00			578				193				32					0						0						0						491						459											
HACKBERRY ROAD																																																				
447+81	448+00			29				13				2					0						0						0						24						22											
448+00	449+00			435				142				16					0						0						0						369						353											
451+00	452+00		122					195				67					0						0						0						103						37											
452+00	452+35		77					33				11					0						0						0						65						55											
LOCUST STREET																																																				
496+00	497+00			216				26				6					0						0						0						184						178											
497+00	498+00			624				130				14					0						0						0						530						516											
498+00	499+00			982				231				13					0						0						0						835						822											
501+00	502+00		217					136				53					0						0						0						185						132											
502+00	503+00		179					113				61					0						0						0						152						92											
503+00	504+00		120					45				21					0						0						0						102						81											

A SHRINKAGE FACTOR OF 15% WAS USED FOR EARTH EXCAVATION ADJUSTMENT

REVISIONS		DATE
NAME		

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES
 U.S. RTE. 30 (LINCOLN HIGHWAY)

SCALE : 1" = 50'
 DATE : 10/12/10

DRAWN BY : BAE
 CHECKED BY : GB