



VINE PLANTING DETAIL

NOTES:

- See Landscape Plans for specific locations of vines.
- Compost/Topsoil shall be thoroughly rototilled into exist ground to a depth of 6" prior to planting.
- Mulch bed shall be placed over rototilled compost/topsoil as shown in vine planting detail and according to IDOT Standard Specification 253.11 except that no weed barrier fabric is required. Cost of mulch cover is included with payment for "Vine-Parthenocissus quinquefolia (Virginia Creeper), 1-Gallon Pot"
- Pre-emergent Granular Herbicide shall be placed in mulched beds according to the Special Provision.

ORNAMENTAL PERENNIAL PLANT CARE SCHEDULE

Activity	Time
Plant Perennials as per Plan	May 1 - June 15 August 15 - September 15
Mulch Perennial Beds	24 Hours After Planting
Install Selective Mow Stakes as per Plan or Direction of RE	Prior to Period of Establishment Inspection
Perennial Plant Period of Establishment - Water Once Every 7 Days for 4 Weeks	Within 30 Days After Planting
Replace Dead Plants	After Period of Establishment Inspection
Perennial Plant Care (First Cycle)	30 Days After Period of Establishment Inspection
Perennial Plant Care (Second Cycle)	60 Days After Period of Establishment Inspection
Perennial Plant Care (Third Cycle)	90 Days After Period of Establishment Inspection
Supplemental Watering	Use After Period of Est. Insp. As Directed by Resident Engineer

SCHEDULE OF PERENNIAL PLANTS, WETLAND TYPE

WETLAND TYPE, 2" DIAMETER X 4" DEEP PLUG-34.08 UNITS TOTAL

WETLAND #1 (WET MEADOW)-1.92 UNIT (2 LOCATIONS)

CALAMOGROSTIS CANADENSIS	BLUE JOINT GRASS	96 EACH
CAREX STRICTA	TUSSOCK SEDGE	96 EACH

WETLAND #2 (WET MEADOW)-3.04 UNIT

ASCLEPIAS INCARNATA	SWAMP MILKWEED	112 EACH
EUPATORIUM RUGOSUM	WHITE SNAKEROOT	96 EACH
PHLOX DIVARICATA	WILD BLUE PHLOX	96 EACH

WETLAND #4 EASTBOUND (FLOODPLAIN FOREST)-12.16 UNIT

ASTER PUNICEUS	SWAMP ASTER	152 EACH
IRIS VIRGINICA VAR.SHREVEI	BLUE FLAG IRIS	152 EACH
LYCOPUS AMERICANUS	WATER HOREHOUND	152 EACH
PHLOX DIVARICATA	WILD BLUE PHLOX	456 EACH
RUDBECKIA LACINIATA	WILD GOLDEN GLOW	152 EACH
SOLIDAGO PATULA	SWAMP GOLDENROD	152 EACH

WETLAND #4 WESTBOUND (FLOODPLAIN FOREST)-12.16 UNIT

ASTER PUNICEUS	SWAMP ASTER	152 EACH
IRIS VIRGINICA VAR.SHREVEI	BLUE FLAG IRIS	152 EACH
LYCOPUS AMERICANUS	WATER HOREHOUND	152 EACH
PHLOX DIVARICATA	WILD BLUE PHLOX	456 EACH
RUDBECKIA LACINIATA	WILD GOLDEN GLOW	152 EACH
SOLIDAGO PATULA	SWAMP GOLDENROD	152 EACH

BUFFER TO HICKORY CREEK TRIBUTARY #1 AT TERMINUS OF CEDAR LANE-4.80 UNIT

ELYMUS VIRGINIANA	VIRGINIA WILD RYE	96 EACH
IRIS VIRGINICA VAR.SHREVEI	BLUE FLAG IRIS	96 EACH
LYCOPUS AMERICANUS	WATER HOREHOUND	96 EACH
POLYGONUM VIRGINIANUM	WOODLAND KNOTWEED	96 EACH
SOLIDAGO PATULA	SWAMP GOLDENROD	96 EACH

WOODLAND TYPE, QUART POT-1.60 UNITS

BUFFER TO HICKORY CREEK TRIBUTARY #1 AT TERMINUS OF CEDAR LANE

CALTHA PALUSTRIS	MARSH MARIGOLD	160 EACH
------------------	----------------	----------

NOTE: ALL WETLAND PLANTS SHALL BE SPACED 12" APART AND STAGGERED UNLESS OTHERWISE NOTED.

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION LANDSCAPING PLANS DETAILS
NAME	DATE	

SCALE : 1" = 20'
DATE : 10/12/2010
DRAWN BY : BAE
CHECKED BY : GB