F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
353	(12&13)WRS-3	WILL	1235	523
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 62479

TRAFFIC SIGNAL SUMMARY OF QUANTITIES (CONT.)

ITEM	UNIT	TOTAL QUANTITY	NEW LENOX					MOKENA	FRANKFORT		FIRE PROTECTION DISTRICT		INTERCONNECT	
			MARLEY	SCHOOL-HOUSE	VANCINA	JOLIET	FLASHING BEACON	OWENS	ELSNER	LOCUST	NEW LENOX	FRANKFORT	LOCATION 1	LOCATION 2
RE-OPTIMIZE TRAFFIC SIGNAL SYSTEM LEVEL 2	EACH	2											1	1
PREFORMED DETECTOR LOOP	FOOT	6395	982	1315	874	824		971	473	956				
ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C	FOOT	25177											11497	13680
TEMPORARY TRAFFIC SIGNAL TIMING	EACH	4	1	1	1				1					
FLASHING BEACON, POST MOUNTED, SOLAR POWERED INSTALLATION	EACH	1					1							
FULL-ACTUATED CONTROLLER AND CABINET (SPECIAL)	EACH	7	1	1	1	1		1	1	1				
SERVICE INSTALLATION - POLE MOUNTED	EACH	7	1	1	1	1		1	1	1				
UNINTERRUPTIBLE POWER SUPPLY	EACH	7	1	1	1	1		1	1	1				
FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM12F SM12F	FOOT	25338											11589	13749
ELECTRIC CABLE IN CONDUIT, GROUNDING, NO. 6 1C	FOOT	5602	753	905	852	653		858	858	723				
ELECTRIC CABLE IN CONDUIT NO. 20 3/C, TWISTED, SHIELDED	FOOT	3019									1916	1103		
STEEL MAST ARM ASSEMBLY AND POLE WITH DUAL MAST ARMS, 14 FT. AND 52 FT.	EACH	1				1								
STEEL MAST ARM ASSEMBLY AND POLE WITH DUAL MAST ARMS, 22 FT. AND 60 FT.	EACH	1	1											

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

TRAFFIC SIGNAL
SUMMARY OF QUANTITIES

US RTE. 30 (LINCOLN HIGHWAY)

SCALE : 1" = NTS
DATE : 10/12/2010

DRAWN BY : RG
DESIGNED BY : GB
CHECKED BY : ZH

DLZ ENGINEERS • ARCHITECTS • SCIENTISTS • PLANNERS • SURVEYORS
85 W. ALGONQUIN ROAD, SUITE 220 ARLINGTON HEIGHTS, IL 60005 TEL: (847) 640-0840