

SUMMARY OF QUANTITIES			TOTAL QUANTITY	CONSTRUCTION TYPE CODE			
				ROADWAY	US RTE 20@ PLANK/COMBS	US RTE 20@ NESTLER RD	INTERCONNECT
CODE NO.	ITEM DESCRIPTION	UNIT	1000-2A QUANTITY	Y031-1F QUANTITY	Y031-1F QUANTITY	Y031-1F QUANTITY	
20101000	TEMPORARY FENCE	FOOT	4384	4384	-	-	-
20101400	NITROGEN FERTILIZER NUTRIENT	POUND	162	162	-	-	-
20101500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	162	162	-	-	-
20101600	POTASSIUM FERTILIZER NUTRIENT	POUND	162	162	-	-	-
20200100	EARTH EXCAVATION	CU YD	631	631	-	-	-
20201006	GRADING AND SHAPING SHOULDERS	UNIT	73.1	73.1	-	-	-
20800150	TRENCH BACKFILL	CU YD	46.2	46.2	-	-	-
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	8627	8627	-	-	-
25000210	SEEDING, CLASS 2A	ACRE	1.8	1.8	-	-	-
25100630	EROSION CONTROL BLANKET	SQ YD	8626	8626	-	-	-
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	540	540	-	-	-
28000305	TEMPORARY DITCH CHECKS	FOOT	374	374	-	-	-
28000400	PERIMETER EROSION BARRIER	FOOT	1084	1084	-	-	-
28000500	INLET AND PIPE PROTECTION	EACH	6	6	-	-	-
28001000	AGGREGATE (EROSION CONTROL)	TON	104	104	-	-	-
28200200	FILTER FABRIC	SQ YD	155	155	-	-	-
35501308	HOT-MIX ASPHALT BASE COURSE, 6"	SQ YD	105	105	-	-	-
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQ YD	32	32	-	-	-
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	74	74	-	-	-
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	14.7	14.7	-	-	-
40600300	AGGREGATE (PRIME COAT)	TON	72.8	72.8	-	-	-
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	55	55	-	-	-
X4060826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	1607	1607	-	-	-
40600895	CONSTRUCTING TEST STRIP	EACH	2	2	-	-	-
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	258.9	258.9	-	-	-
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	1090	1090	-	-	-
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	15.7	15.7	-	-	-
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	3750	3750	-	-	-
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	36389	36389	-	-	-
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	184	184	-	-	-
Z0004562	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	200	200	-	-	-
44004250	PAVED SHOULDER REMOVAL	SQ YD	1586	1586	-	-	-

SUMMARY OF QUANTITIES			TOTAL QUANTITY	CONSTRUCTION TYPE CODE			
				ROADWAY	US RTE 20@ PLANK/COMBS	US RTE 20@ NESTLER RD	INTERCONNECT
CODE NO.	ITEM DESCRIPTION	UNIT	1000-2A QUANTITY	Y031-1F QUANTITY	Y031-1F QUANTITY	Y031-1F QUANTITY	
44201811	CLASS D PATCHES, TYPE I, 14 INCH	SQ YD	50	50	-	-	-
44201815	CLASS D PATCHES, TYPE II, 14 INCH	SQ YD	200	200	-	-	-
44201819	CLASS D PATCHES, TYPE III, 14 INCH	SQ YD	200	200	-	-	-
44201821	CLASS D PATCHES, TYPE IV, 14 INCH	SQ YD	280	280	-	-	-
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	1441	1441	-	-	-
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	292.3	292.3	-	-	-
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	1702	1702	-	-	-
50105220	PIPE CULVERT REMOVAL	FOOT	116	116	-	-	-
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	9	9	-	-	-
54214731	PRECAST REINFORCED CONCRETE FLARED END SECTIONS-ELLIPTICAL, EQUIVALENT ROUND-SIZE 36"	EACH	6	6	-	-	-
54247170	GRATING FOR CONCRETE FLARED END SECTION 36"	EACH	6	6	-	-	-
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	2	2	-	-	-
63200310	GUARDRAIL REMOVAL	FOOT	366	366	-	-	-
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	7	7	-	-	-
67100100	MOBILIZATION	L SUM	1	1	-	-	-
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1	-	-	-
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1	-	-	-
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1	-	-	-
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1	-	-	-
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	5	5	-	-	-
70300100	SHORT TERM PAVEMENT MARKING	FOOT	3657	3657	-	-	-
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	2420	2420	-	-	-
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	68832	68832	-	-	-
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	9301	9301	-	-	-
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	1250	1250	-	-	-
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	309	309	-	-	-
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	610	610	-	-	-
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	1092	1092	-	-	-
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	34416	34416	-	-	-
78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	4651	4651	-	-	-
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	625	625	-	-	-

* SPECIALTY ITEM

FILE NAME = P:\2009\VE2\9886_Ver-Var-Ph1\CADD\W05_US20\Shets\83-500\ht-ht-US20.dgn
 PLOT SCALE = 1:1000 / IN.
 USER NAME = Millennium Professional Services



200 22ND Street, Suite 216, Lombard, IL 60148
 630.785.9119 voice, 630.859.2566 fax
 WWW.MPS-IL.COM

MILLENNIA PROFESSIONAL SERVICES

DESIGNED - TVN	REVISED -
DRAWN - TVN	REVISED -
CHECKED - RPD	REVISED -
DATE - 11/2/2010	REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

U.S. ROUTE 20
 EAST OF PLANK ROAD TO WELD ROAD

SUMMARY OF QUANTITIES

F.A.P. RTE. 345	SECTION 8WRS-2	COUNTY KANE	TOTAL SHEETS 72	SHEET NO. 3
CONTRACT NO. 62529			FED. ROAD DIST. NO. 1 (ILLINOIS) FED. AID PROJECT	