

**INDEX OF SHEETS**

NO.	SHEET TITLE
1	COVER SHEET
2	INDEX OF SHEETS, STANDARDS & GENERAL NOTES
3-4	SUMMARY OF QUANTITIES
5	TYPICAL SECTIONS
6-7	SCHEDULE OF QUANTITIES
8	ALIGNMENT & TIES / EXISTING ROADWAY & REMOVALS
9	ROADWAY PLAN & PROFILE
10	DETOUR ROUTE & SIGNAGE
11	EROSION & SEDIMENT CONTROL PLAN
12-13	EROSION & SEDIMENT CONTROL DETAILS
14	LANDSCAPING PLAN
15	DISTRICT ONE TYPICAL PAVEMENT MARKINGS
16	GENERAL PLAN & ELEVATION
17	BILL OF MATERIAL & GENERAL NOTES
18-19	DECK BEAM DETAILS
20-21	APPROACH SLAB DETAILS
22	RAILING ELEVATION & CONCRETE OVERLAY DETAILS
23	RAILING DETAILS
24	ABUTMENT DETAILS
25	SE MSE WALL PLAN & PROFILE
26	NE MSE WALL PLAN & PROFILE
27-28	MSE WALL DETAILS
29	METAL SHELL PILES
30	BAR SPLICER ASSEMBLY DETAILS
31-38	CROSS SECTIONS -- 88TH AVENUE
39-43	CROSS SECTIONS -- FORKED CREEK

**STATE STANDARDS**

NO.	TITLE
000001-06	STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS
001006	DECIMAL OF AN INCH AND OF A FOOT
280001-05	TEMPORARY EROSION CONTROL SYSTEMS
420401-08	BRIDGE APPROACH PAVEMENT CONNECTOR
482001-02	HMA SHOULDER ADJACENT TO FLEXIBLE PAVEMENT
515001-03	NAME PLATE FOR BRIDGES
630001-09	STEEL PLATE BEAM GUARDRAIL
630301-05	SHOULDER WIDENING FOR TYPE 1 (SPECIAL) GUARDRAIL TERMINALS
631032-06	TRAFFIC BARRIER TERMINAL, TYPE 6A
635001-01	DELINEATORS
635006-03	REFLECTOR AND TERMINAL MARKER PLACEMENT
635011-02	REFLECTOR MARKER AND MOUNTING DETAILS
666001-01	RIGHT-OF-WAY MARKERS
701901-01	TRAFFIC CONTROL DEVICES
720001-01	SIGN PANEL MOUNTING DETAILS
720006-02	SIGN PANEL ERECTION DETAILS
728001-01	TELESCOPING STEEL SIGN SUPPORT
780001-02	TYPICAL PAVEMENT MARKINGS

**DISTRICT ONE DETAILS**

NO.	TITLE
TC 13	DISTRICT ONE TYPICAL PAVEMENT MARKINGS

**GENERAL NOTES**

- | NO. | NOTE  |
|-----|---|
| 1.  | ANY REFERENCE TO THE "STANDARD SPECIFICATIONS" THROUGHOUT THE PLANS OR SPECIAL PROVISIONS SHALL BE INTERPRETED TO BE THE ILLINOIS DEPARTMENT OF TRANSPORTATION (IDOT) STANDARD SPECIFICATIONS, ADOPTED JANUARY 1, 2007 AND THE LATEST EDITION OF THE IDOT SUPPLEMENTAL SPECIFICATIONS AND RECURRING SPECIAL PROVISIONS. |
| 2.  | BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL "J.U.L.I.E." AT 1-800-892-0123 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE AND GAS FACILITIES. FORTY-EIGHT (48) HOURS OF NOTIFICATION IS REQUIRED.  |
| 3.  | THE CONTRACTOR SHALL COORDINATE CONSTRUCTION ACTIVITIES WITH UTILITY COMPANIES, THE ILLINOIS DEPARTMENT OF TRANSPORTATION, GREEN GARDEN TOWNSHIP AND THE WILL COUNTY DIVISION OF HIGHWAYS.  |
| 4.  | THE CONTRACTOR WILL NOT BE ALLOWED TO SET UP A YARD OR FIELD OFFICE ON TOWNSHIP PROPERTY WITHOUT WRITTEN PERMISSION FROM THE TOWNSHIP.  |
| 5.  | TEN (10) FOOT TRANSITIONS SHALL BE USED TO MATCH PROPOSED ITEMS OF WORK TO EXISTING ITEMS IN THE FIELD, UNLESS OTHERWISE SHOWN. THE TRANSITIONS SHALL BE PAID FOR AT THE CONTRACT UNIT PRICE FOR THE PROPOSED ITEM OF WORK SPECIFIED.   |
| 6.  | THE ENGINEER SHALL BE THE SOLE JUDGE CONCERNING CURING TIME FOR THE VARIOUS HOT MIX ASPHALT (HMA) LIFTS.  |
| 7.  | BASIS OF DESIGN AND QUANTITY CALCULATIONS FOR HOT-MIX ASPHALT MIXTURES IS 112 LBS/SY/IN.  |
| 8.  | INSTALLATION, OPERATION AND MAINTENANCE OF EROSION AND SEDIMENT CONTROL DETAILS SHALL BE IN ACCORDANCE WITH THE STANDARD SPECIFICATIONS, IDOT STATE STANDARD DETAILS AND THE ILLINOIS URBAN MANUAL BY THE USDA NATURAL RESOURCE CONSERVATION SERVICE.   |

**COMMITMENTS**

- | NO. | COMMITMENT   | NO. | COMMITMENT  |
|-----|--|-----|---|
| 1.  | THE CONTRACTOR IS REQUIRED TO NOTIFY THE SHERIFF'S OFFICE AS TO THE START OF CONSTRUCTION, CHANGES TO THE CONSTRUCTION SCHEDULE OF CHANGES TO THE DETOUR.<br><br>SHERIFF PAUL J. KAUPAS<br>WILL COUNTY SHERIFF<br>14. W. JEFFERSON ST.<br>JOLIET, IL 60432<br>(815) 727-8895   | 3.  | THE CONTRACTOR SHALL COMPLETE THE SOIL EROSION AND SEDIMENT CONTROL INFORMATION FORM AND RETURN IT TO THE U.S. ARMY CORPS OF ENGINEERS (USACE) -- CHICAGO REGIONAL OFFICE PRIOR TO STARTING CONSTRUCTION. |
| 2.  | THE CONTRACTOR IS REQUIRED TO NOTIFY THE MONEE FIRE DEPARTMENT AS TO THE START OF CONSTRUCTION, CHANGES TO THE CONSTRUCTION SCHEDULE OF CHANGES TO THE DETOUR.<br><br>CHIEF CARL NIELAND<br>MONEE FIRE DEPARTMENT<br>25707 S. HARLEM AVE.<br>MONEE, IL 60449<br>(708) 235-0471 | 4.  | THE CONTRACTOR SHALL COMPLETE AND RETURN THE FIELD INSPECTION CHECKLIST TO THE USACE -- CHICAGO REGIONAL OFFICE ON A WEEKLY BASIS DURING CONSTRUCTION.  |