

PAY ITEM NUMBER	PAY ITEM NAME	UNIT	TOTAL	RECONSTRUCTION, NO	BRIDGE REPLACEMENT,
				CAPACITY ADDED 0004	NO CAPACITY ADDED 0011
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	82	82	
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	42	42	
20200100	EARTH EXCAVATION	CU YD	1547	1547	
20300100	CHANNEL EXCAVATION	CU YD	1011		1011
20400800	FURNISHED EXCAVATION	CU YD	747	747	
* 21101505	TOPSOIL EXCAVATION AND PLACEMENT	CU YD	583	583	
* 25000210	SEEDING, CLASS 2A	ACRE	0.6	0.6	
* 25000300	SEEDING, CLASS 3	ACRE	0.1	0.1	
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	63	63	
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	63	63	
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	63	63	
* 25100115	MULCH, METHOD 2	ACRE	0.7	0.7	
* 28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	70	70	
28000305	TEMPORARY DITCH CHECKS	FOOT	120	120	
28000400	PERIMETER EROSION BARRIER	FOOT	2261	2261	
28100107	STONE RIPRAP, CLASS A4	SQ YD	347		347
28200200	FILTER FABRIC	SQ YD	347		347
40300100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	5748	5748	
40600895	CONSTRUCTING TEST STRIP	EACH	1	1	
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	994	994	
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	191	191	
42001300	PROTECTIVE COAT	SQ YD	495		495
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	533	533	
44000100	PAVEMENT REMOVAL	SQ YD	1949	1949	
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	305	305	
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQ YD	789	789	
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1		1
50105220	PIPE CULVERT REMOVAL	FOOT	20	20	
50200100	STRUCTURE EXCAVATION	CU YD	595		595
50300225	CONCRETE STRUCTURES	CU YD	50.2		50.2
50300255	CONCRETE SUPERSTRUCTURE	CU YD	307.5		307.5
50300260	BRIDGE DECK GROOVING	SQ YD	465		465
50400605	PRECAST PRESTRESSED CONCRETE DECK BEAMS (33" DEPTH)	SQ FT	2542		2542
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	43510		43510
50800515	BAR SPLICERS	EACH	64		64
* 50901050	STEEL RAILING, TYPE SM	FOOT	661		661
51200956	FURNISHING METAL SHELL PILES 12" X 0.179"	FOOT	910		910

* SPECIALTY ITEM

FILE NAME =	USER NAME = *USER*	DESIGNED - PFR	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION GREEN GARDEN TOWNSHIP 88TH AVENUE (PEOTONE ROAD)	SUMMARY OF QUANTITIES (SHEET 1 OF 2)				F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
#FILE#		DRAWN - PFR	REVISED -		N/A	03-07118-00-BR	WILL	43	3				
TENG TENG & ASSOCIATES, INC. ENGINEERS/ARCHITECTS/PLANNERS CHICAGO, ILLINOIS	PLOT SCALE = *SCALE*	CHECKED - KPS	REVISED -		CONTRACT NO. 63156								
	PLOT DATE = 10-26-2010	DATE - 10/27/10	REVISED -		SCALE: N.T.S.	FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT					