

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

CONSTRUCTION TYPE CODE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE		
				STP ROADWAY 0003	CMAQ SIGNALS & LIGHTING 0021	ITEP LANDSCAPING 0031
28000400	PERIMETER EROSION BARRIER	FOOT	4,532	4,532		
28000500	INLET AND PIPE PROTECTION	EACH	101	101		
35101400	AGGREGATE BASE COURSE, TYPE B	TON	310	310		
35600712	HOT-MIX ASPHALT BASE COURSE WIDENING, 9"	SQ YD	1,124	1,124		
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	61	61		
40600895	CONSTRUCTING TEST STRIP	EACH	1	1		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	222	222		
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	2,595	2,595		
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	1,040	1,040		
40701901	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 11"	SQ YD	23,883	23,883		
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	102	102		
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	99	99		
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	644	644		
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	27,977	27,977		
42400800	DETECTABLE WARNINGS	SQ FT	427	427		
44000100	PAVEMENT REMOVAL	SQ YD	22,323	22,323		
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	2,152	2,152		
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	13,904	13,904		
44000600	SIDEWALK REMOVAL	SQ FT	9,284	9,284		

> DENOTE "SPECIALTY ITEM"

FILE NAME = G:\S\9021\CADD_Sheets\9021500.dgn	USER NAME = JE Consultants	DESIGNED -	REVISED - 11/08/2010	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.U.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
PLOT SCALE = 10.0000' / IN.	DRAWN -	REVISED -	1578			06-00046-01-PV	WILL	244	5	
PLOT DATE = 11/16/2010	CHECKED -	REVISED -	CONTRACT NO. 63503							
	DATE -	REVISED -	ILLINOIS FED. AID PROJECT							
					SCALE:	SHEET NO. OF SHEETS		STA.	TO STA.	