

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

CONSTRUCTION TYPE CODE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE		
				STP ROADWAY 0003	CMAQ SIGNALS & LIGHTING 0021	ITEP LANDSCAPING 0031
44003100	MEDIAN REMOVAL	SQ FT	423	423		
X4403800	MEDIAN SURFACE REMOVAL	SQ FT	4,823	4,823		
44200180	PAVEMENT PATCHING, TYPE II, 15 INCH	SQ YD	60	60		
44200184	PAVEMENT PATCHING, TYPE III, 15 INCH	SQ YD	113	113		
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	4,200	4,200		
45100200	CRACK FILLING	POUND	500	500		
50300225	CONCRETE STRUCTURES	CU YD	2.1	2.1		
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	280	280		
51500100	NAME PLATES	EACH	1	1		
54213675	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30"	EACH	1	1		
54213681	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36"	EACH	2	2		
54213687	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 42"	EACH	1	1		
54215985	REINFORCED CONCRETE PIPE ELBOW 30"	EACH	1	1		
54247150	GRATING FOR CONCRETE FLARED END SECTION 30"	EACH	1	1		
54247170	GRATING FOR CONCRETE FLARED END SECTION 36"	EACH	2	2		
54247180	GRATING FOR CONCRETE FLARED END SECTION 42"	EACH	1	1		
550A2320	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 12"	FOOT	614	614		
550A2340	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 18"	FOOT	58	58		
550A2350	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 21"	FOOT	98	98		

> DENOTE "SPECIALTY ITEM"

FILE NAME = G:\S09021\CA00_Sheets\9021S00.dgn	USER NAME = JE Consultants	DESIGNED -	REVISED - 11/08/2010	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.U.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
PLOT SCALE = 10.0000' / IN.	DRAWN -	CHECKED -	REVISED -			1578	06-00046-01-PV	WILL	244	6	
PLOT DATE = 12/2/2010	DATE -	REVISED -				CONTRACT NO. 63503		ILLINOIS FED. AID PROJECT			
SCALE:		SHEET NO. OF SHEETS				STA. TO STA.					