

**ILLINOIS DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES**

CONSTRUCTION TYPE CODE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	STP	CMAQ	ITEP
				ROADWAY 0003	SIGNALS & LIGHTING 0021	LANDSCAPING 0031
55101200	STORM SEWER REMOVAL 24"	FOOT	181	181		
55101300	STORM SEWER REMOVAL 27"	FOOT	230	230		
55101600	STORM SEWER REMOVAL 36"	FOOT	44	44		
60107600	PIPE UNDERDRAINS 4"	FOOT	924	924		
60211600	CATCH BASINS, TYPE D, 3'-DIAMETER, TYPE 15 FRAME AND LID	EACH	1	1		
60212800	CATCH BASINS, TYPE D, 4'-DIAMETER, TYPE 15 FRAME AND LID	EACH	6	6		
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2	2		
60223800	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1		
60235700	INLETS, TYPE A, TYPE 3 FRAME AND GRATE	EACH	5	5		
60236200	INLETS, TYPE A, TYPE 8 GRATE	EACH	4	4		
60236800	INLETS, TYPE A, TYPE 11 FRAME AND GRATE	EACH	2	2		
60237000	INLETS, TYPE A, TYPE 15 FRAME AND LID	EACH	1	1		
60250500	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	1	1		
60255500	MANHOLES TO BE ADJUSTED	EACH	29	29		
60255800	MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	3	3		
60260100	INLETS TO BE ADJUSTED	EACH	1	1		
60266600	VALVE BOXES TO BE ADJUSTED	EACH	5	5		
60500040	REMOVING MANHOLES	EACH	14	14		
60500060	REMOVING INLETS	EACH	33	33		

> DENOTE "SPECIALTY ITEM"

FILE NAME = G:\S09021\CADD_Sheets\9021500.dgn	USER NAME = IE Consultants	DESIGNED -	REVISED - 11/08/2010	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>				F.A.U.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
PLOT SCALE = 10.0000' / IN.	CHECKED -	REVISOR -	SCALE:						SHEET NO.	OF	SHEETS	STA.	TO STA.	1578
PLOT DATE = 12/1/2010	DATE -	REVISOR -	CONTRACT NO. 63503											
											ILLINOIS FED. AID PROJECT			