

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

CONSTRUCTION TYPE CODE

STP CMAQ ITEP

ROADWAY SIGNALS & LIGHTING LANDSCAPING  
0003 0021 0031

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY	SIGNALS & LIGHTING	LANDSCAPING
> 81028080	CONDUIT, BORED AND PULLED, COLLAPSE NON-METALLIC CONDUIT, 3"	FOOT	76		76	
> 81400100	HANDHOLE	EACH	2		2	
> X8140115	HANDHOLE TO BE ADJUSTED	EACH	2		2	
> 81400700	HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	3		3	
> 81400720	DOUBLE HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	1		1	
> 81603025	UNIT DUCT, 600V, 2-1C NO. 4, 1/C NO. 4 GROUND, (XLP-TYPE USE), 1" DIA. POLYETHYLENE	FOOT	2,700		2,700	
> 81603035	UNIT DUCT, 600V, 2-1C NO. 6, 1/C NO. 6 GROUND, (XLP-TYPE USE), 1" DIA. POLYETHYLENE	FOOT	2,590		2,590	
> 81603060	UNIT DUCT, 600V, 3-1C NO. 8, 1/C NO. 10 GROUND, (XLP-TYPE USE), 1" DIA. POLYETHYLENE	FOOT	4,800		4,800	
> 81702415	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 3-1/C NO. 6	FOOT	697		697	
> 81702440	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 3-1/C NO. 1/0	FOOT	150		150	
> 81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	4,554		4,554	
> 82102250	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 250 WATT	EACH	52		52	
> X8250505	LIGHTING CONTROLLER, SPECIAL	EACH	3		3	
> 83007400	LIGHT POLE, ALUMINUM, 35 FT. M.H., 10 FT. MAST ARM	EACH	27		27	
> 83007600	LIGHT POLE, ALUMINUM, 35 FT. M.H., 15 FT. MAST ARM	EACH	1		1	
> 83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	606		606	
> 83600215	LIGHT POLE FOUNDATION, 24" DIAMETER, OFFSET	FOOT	36		36	
> 83800105	BREAKAWAY DEVICE, TRANSFORMER BASE, 11.5 INCH BOLT CIRCLE	EACH	38		38	
> 84200500	REMOVAL OF LIGHTING UNIT, SALVAGE	EACH	15		15	
> X0324901	REMOVE EXISTING STREET LIGHTING FOUNDATION	EACH	15		15	

> DENOTE "SPECIALTY ITEM"

FILE NAME = G:\S09021\CADD_Sheets\9021500.dgn	USER NAME = IE Consultants	DESIGNED -	REVISED - 11/08/2010	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>	F.A.U.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
PLOT SCALE = 1/8" = 1' IN.	DRAWN -	REVISED -	1578			06-00046-01-PV	WILL	244	11	
PLOT DATE = 12/2/2010	CHECKED -	REVISED -	CONTRACT NO. 63503							
DATE -	REVISED -	ILLINOIS FED. AID PROJECT								
SCALE:		SHEET NO. OF SHEETS		STA. TO STA.						