

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

CONSTRUCTION TYPE CODE

STP CMAQ ITEP

ROADWAY SIGNALS & LIGHTING LANDSCAPING
0003 0021 0031

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY	SIGNALS & LIGHTING	LANDSCAPING
> 85000300	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	L SUM	1		1	
> 85700300	FULL-ACTUATED CONTROLLER AND TYPE V CABINET	EACH	1		1	
> 87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	1,266		1,266	
> 87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	2,460		2,460	
> 87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	1,577		1,577	
> 87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	1,267		1,267	
> 87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C	FOOT	133		133	
> 87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL 16 FT.	EACH	4		4	
> 87700180	STEEL MAST ARM ASSEMBLY AND POLE, 28 FT.	EACH	1		1	
> 87702830	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 20 FT.	EACH	2		2	
> 87702840	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 22 FT.	EACH	3		3	
> 87702880	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 30 FT.	EACH	1		1	
> 87702890	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 32 FT.	EACH	1		1	
> 87800100	CONCRETE FOUNDATION, TYPE A	FOOT	16		16	
> 87800150	CONCRETE FOUNDATION, TYPE C	FOOT	4		4	
> 87800200	CONCRETE FOUNDATION, TYPE D	FOOT	4		4	
> 87800400	CONCRETE FOUNDATION, TYPE E 30-INCH DIAMETER	FOOT	68		68	
> 88040090	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	8		8	
> 88040160	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, MAST ARM MOUNTED	EACH	4		4	
> 88040260	SIGNAL HEAD, POLYCARBONATE, LED, 2-FACE, 1-3-SECTION, 1-5-SECTION, BRACKET MOUNTED	EACH	4		4	

> DENOTE "SPECIALTY ITEM"