

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

CONSTRUCTION TYPE CODE

STP CMAQ ITEP

ROADWAY SIGNALS & LIGHTING LANDSCAPING  
0003 0021 0031

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY	SIGNALS & LIGHTING	LANDSCAPING
> 88102717	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	2		2	
> 88102820	PEDESTRIAN SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 2-SECTION BRACKET MOUNTED	EACH	8		8	
> 88200100	TRAFFIC SIGNAL BACKPLATE	EACH	8		8	
> 88700200	LIGHT DETECTOR	EACH	4		4	
> 88700300	LIGHT DETECTOR AMPLIFIER	EACH	1		1	
> 88800100	PEDESTRIAN PUSH-BUTTON	EACH	10		10	
> 89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	2		2	
> A2004620	TREE, GLEDITSIA TRIACANTHOS INERMIS (THORNLESS COMMON HONEYLOCUST), 2 1/2" CALIPER, BALLED AND BURLAPPED	EACH	29			29
> A2004514	TREE, GINKGO BILOBA AUTUMN GOLD (AUTUMN GOLD GINKGO), 2 1/2" CALIPER, BALLED AND BURLAPPED	EACH	53			53
> A2006420	TREE, QUERCUS ALBA (WHITE OAK), 2 1/2" CALIPER, BALLED AND BURLAPPED	EACH	46			46
> A2008722	TREE, ULMUS PATRIOT (PATRIOT ELM), 2" CALIPER, BALLED AND BURLAPPED	EACH	29			29
> K0026610	TRANSPLANTED SALVAGED TREES	EACH	40			40
X0301834	STORM SEWER TO BE FILLED	FOOT	1,075	1,075		
> X0323553	ORNAMENTAL FENCE, WROUGHT IRON	FOOT	33	33		
> X0323713	RADIO INTERCONNECT SYSTEM COMPLETE, LOCAL	EACH	1		1	
X0326911	TRANSVERSE DRAINS COMPLETE	EACH	16	16		
X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	31	31		
X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	9	9		
X4401198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	8,161	8,161		

> DENOTE "SPECIALTY ITEM"

FILE NAME = G:\S09021\CADD_Sheets\9021500.dgn	USER NAME = IE Consultants	DESIGNED -	REVISED - 11/08/2010	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>	F.A.U.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
		DRAWN -	REVISED -			1578	06-00046-01-PV	WILL	244	13	
		CHECKED -	REVISED -			CONTRACT NO. 63503					
		DATE -	REVISED -			ILLINOIS FED. AID PROJECT					
		PLOT SCALE = 10.0000' / IN.		SCALE:		SHEET NO. OF SHEETS		STA. TO STA.			
		PLOT DATE = 11/16/2010									