

MANHOLE SCHEDULE							
ID	STA	OFFSET	60218400 MANHOLES, TYPE A, 4' DIA., TY 1 FRAME, CLOSED LID	60223800 MANHOLES, TYPE A, 6' DIA., TY 1 FRAME, CLOSED LID	60221100 MH, 5' DIA., TY A, TY 1 FRAME, CLOSED LID	60255800 MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	X6020090 MANHOLES, WITH RESTRICTOR PLATE
			(EACH)	(EACH)	(EACH)	(EACH)	(EACH)
N-1.01	25+47.81	28.00				1	
N-1.04	27+34.84	35.44				1	
N-1.09	29+00.00	32.60			1 (a)		
N-2.02	30+20.00	27.50					1
N-2.11	35+50.00	27.50					1
N-2.27	43+05.00	32.00					1
N-2.28	45+85.00	32.00		1			
N-3.25	75+23.00	-22.00	1				
N-3.26	74+92.00	43.00	1				
N-3.31	74+80.00	43.00			1 (a)		
N-3.32	73+95.00	43.00			1 (a)		
N-3.34	65+23.87	-11.95				1	
N-4.05	76+10.00	37.00			1 (a)		
N-4.14	79+93.50	28.23					1
TOTALS			2	1	4	3	4

(a) REQUIRES FLAT SLAB TOP

UNDERDRAIN SCHEDULE		
STATION	60107600 PIPE UNDERDRAINS 4"	X0326911 TRANSVERSE DRAINS COMPLETE
	(FOOT)	(EACH)
26+55	58	1
27+83	58	1
31+50	56	1
35+60	75	1
40+45	56	1
47+28	56	1
51+85	75	1
55+32	60	1
58+87	48	1
63+60	46	1
66+65	50	1
70+40	50	1
74+22	56	1
76+69	56	1
78+94	56	1
82+14	68	1
TOTAL	924	16

PATCHING SCHEDULE			
STA	EX AREA FROM CAD	44200180 PAVEMENT PATCHING TY II, 15"	44200184 PAVEMENT PATCHING TY III, 15"
	(SQ FT)	(SQ YD)	(SQ YD)
29+00.00	160.6		17.9
32+50.00	134.4		15.0
38+70.00	131.9	14.7	
42+20.00	132.3	14.7	
48+05.00	133.7	14.9	
53+00.00	139.2		15.5
55+32.50	137.5		15.3
70+40.00	134.2		15.0
74+45.00	151.7		16.9
76+90.00	149.7		16.7
79+20.00	132.6	14.8	
TOTAL		59.1	112.3
USE		60	113

FILE NAME =	USER NAME = IE Consultants	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES				F.A.U.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
G:\S09021\CADD_Sheets\9021Schedule01.dgn		DRAWN -	REVISED -		1578	06-00046-01-PV	WILL	244	20				
PLOT SCALE = 10.0000' / IN.		CHECKED -	REVISED -		CONTRACT NO. 63503								
PLOT DATE = 12/1/2010		DATE -	REVISED -		SCALE:	SHEET NO. OF SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT				