

### CURB AND GUTTER SCHEDULE

STA.	TO	STA.	LOCATION	44000500	44003100	X4403800	60600605	60603500	60603800	60604400	60605900	60606800	60620800
				COMBINATION CURB & GUTTER REMOVAL	MEDIAN REMOVAL	MEDIAN SURFACE REMOVAL	CURB, TYPE B	COMBINATION CONCRETE CURB & GUTTER, TYPE B-6.06	COMBINATION CONCRETE CURB & GUTTER, TYPE B-6.12	COMBINATION CONCRETE CURB & GUTTER, TYPE B-6.18	COMBINATION CONCRETE CURB & GUTTER, TYPE B-9.12	COMBINATION CONCRETE CURB & GUTTER, TYPE B-9.18	CONCRETE MEDIAN, TYPE SB-9.12
				(FOOT)	(SQ FT)	(SQ FT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(SQ FT)
<b>LILY CACHE</b>													
23+96		26+51	LT	264								264	
26+51		27+27	LT	76									
24+37		44+74	RT	2,032								2,032	
27+27		44+74	LT	1,742								1,742	
27+18		27+26	MED		56								
27+26		28+61	MED	272		1,682							
28+61		28+73	MED	24		154							71
28+73		31+55	MED	564		2,926				564			
31+55		31+65	MED	20		29							97
31+65		31+79	MED	28		32							
31+79		32+68	MED		367								
32+45		32+55	MED										97
32+55		34+83	MED							456			
34+83		34+93	MED										97
35+73		35+83	MED										97
35+83		39+32	MED							698			
39+32		39+42	MED										97
40+22		40+32	MED										97
40+32		42+36	MED							408			
42+36		42+48	MED										71
45+74		48+86	LT	312								312	
45+74		65+05	RT	1,931								1,931	
48+86		65+15	LT	1,629					1,643				
47+98		48+10	MED										71
48+10		49+75	MED							330			
49+75		49+85	MED										97
50+67		50+77	MED										97
50+77		52+93	MED							438			
52+99		53+96	MED							199			
53+96		54+06	MED										97
65+81		75+31	LT	961					961				
65+88		75+24	RT	936								936	
76+06		82+35	LT	629								629	
76+06		82+35	RT	651								629	
78+36		78+48	MED										71
78+48		80+87	MED									478	
80+87		80+99	MED										71
PICARDY LN				26+85	LT	113			90				
LINDSEY LN				45+24	LT	132				114			
LINDSEY LN				45+24	RT	120				106			
PLAINVIEW DR				65+48	LT	105			106				
PLAINVIEW DR				65+48	RT	86			75				
ORCHARD DR				75+65	LT	158			155				
ORCHARD DR				75+65	RT	543			452				
CE				25+35	LT	20		39					
CE				26+84	RT	66		45					
CE				32+04	RT	71			41				
CE				32+06	LT	122			62				
CE				35+33	LT	69			57				
CE				39+82	RT	73	33						
CE				50+25	RT	58			33				
CE				51+62	RT	70			35				
CE				53+24	RT	71	47						
<b>TOTALS</b>				<b>13,948</b>	<b>423</b>	<b>4,823</b>	<b>80</b>	<b>84</b>	<b>1,106</b>	<b>2,824</b>	<b>3,093</b>	<b>8,953</b>	<b>1,228</b>