

SIDEWALK SCHEDULE								
STA.	TO	STA.	LT / RT	42400200 PC CONC SIDEWALK, 5" (AREA CALC'D. IN CADD)		42400800 DETECTABLE WARNINGS	44000600 SIDEWALK REMOVAL	
				8' SHARED USE PATH (SQ FT)	SIDEWALK (SQ FT)	(SQ FT)	(SQ FT)	
24+11.00		24+18.00	LT		41	11	28	
25+10.00		25+17.00	LT		40	10	36	
25+54.00		25+61.00	LT		33	9	26	
26+64.00		26+72.00	LT		39	10	49	
27+02.00		27+10.00	LT		32	10	22	
28+92.00		31+84.00	LT		1,317			
31+84.00		31+91.00	LT		35	9		
32+20.00		32+28.00	LT		35	9		
32+28.00		33+63.00	LT		611			
35+13.00		35+19.00	LT		35	9	32	
35+46.00		35+53.00	LT		35	9	33	
44+89.00		45+01.00	LT		60	10	75	
45+56.00		45+62.00	LT		62	11		
45+46.00		45+55.00	LT	68		17	44	
45+55.00		53+66.00	LT	2,538				
45+56.00		45+65.00	RT		78	11		
45+65.00		49+01.00	RT		1,478		68	
49+67.00		50+04.00	RT		167		144	
50+04.00		50+11.00	RT		36	10		
50+39.00		50+46.00	RT		35	9		
50+46.00		51+42.00	RT		430			
51+42.00		51+49.00	RT		36	10		
51+77.00		51+83.00	RT		36	10		
51+83.00		53+01.00	RT		532			
52+93.00		52+99.00	RT		61	10		
53+01.00		53+08.00	RT		36	10	155	
53+39.00		53+46.00	RT		36	10	26	
53+46.00		54+00.00	RT		245		233	
52+89.00		53+04.00	LT		121	9	134	
53+66.00		65+21.00	LT	9,250			1,673	
65+07.00		65+13.00	LT		71	10		
65+16.00		65+20.00	LT		50			
65+21.00		65+30.00	LT	70		17		
65+07.00		65+13.00	RT		87	10	82	
65+12.00		65+28.00	RT		75	10	86	
65+66.00		65+81.00	RT		74	10	79	
65+81.00		65+86.00	RT		84	10	95	
65+66.00		65+75.00	LT	70		17	43	
65+75.00		65+79.00	LT		49			
65+81.00		65+86.00	LT		67	10		
65+75.00		75+29.00	LT	7,710			4,270	
75+29.00		75+40.00	LT	286		48	167	
75+33.00		75+37.00	LT		47		173	
75+86.00		76+03.00	LT	159		24	132	
75+92.00		75+97.00	LT		49		88	
73+75.00		75+27.00	RT		684		684	
75+31.00		75+42.00	RT	152		25	379	
75+27.00		75+31.00	RT		21		18	
75+87.00		76+03.00	RT		112	23	210	
76+03.00		76+86.00	LT	502				
TOTALS					20,805	7,172	427	9,284
USE					27,977		427	9,284

UTILITY ADJUSTMENT & REMOVAL SCHEDULE						
STATION	OFFSET	LT / RT	60255500 MANHOLES TO BE ADJUSTED	60266600 VALVE BOXES TO BE ADJUSTED	81400115 HANDHOLE TO BE ADJUSTED	X8950810 REMOVE AND RE-ERECT FLASHING BEACON
			(EACH)	(EACH)	(EACH)	(EACH)
			(FEET)			
24+36	5	LT	1			
26+01	23	RT				
26+72	46	LT				
27+03	2	LT	1			
27+19	31	LT	1			
27+90	26	RT				
29+21	33	LT	1			
31+87	49	LT	1			
32+31	50	LT	1			
34+10	50	LT	1			
34+60	34	LT	1			
34+68	34	LT	1			
36+18	43	LT	1			
38+95	42	LT	1			
43+36	34	LT	1			
44+56	35	RT	1			
44+75	38	RT			1	
44+92	28	RT	1			
44+93	43	LT	1			
45+52	33	RT		1		
45+60	29	LT				
45+70	38	RT			1	
48+94	37	RT	1			
46+26	19	RT				1
51+16	33	LT	1			
51+79	37	RT		1		
52+95	45	LT	1			
53+69	31	RT		1		
53+90	38	LT	1			
54+54	47	LT	1			
55+08	20	RT				
56+39	24	LT				1
58+16	46	LT	1			
58+31	20	RT				
58+92	32	LT	1			
59+78	39	LT	1			
65+06	20	LT		1		
65+06	39	LT	1			
65+16	26	LT				
65+23	56	RT				
66+85	34	LT	1			
68+26	23	RT				
69+14	46	LT	1			
72+48	24	RT				1
72+59	46	LT	1			
75+14	37	LT	1			
75+38	29	LT				
75+48	40	RT				
75+87	26	RT		1		
75+93	50	LT	1			
78+65	29	LT				1
TOTAL			29	5	2	4