



NOTE:
 ALL NEW SIGNS AND EXISTING SIGNS SHOWN TO BE RELOCATED SHALL BE PLACED IN THEIR PERMANENT LOCATIONS AS DIRECTED BY THE ENGINEER.

- LANDSCAPING LEGEND**
- INDICATES PROPOSED SODDING AREAS
 - PROPOSED TREES
SEE "GENERAL NOTES FOR TREE PLANTING AND LANDSCAPING" FOR APPROVED TREES AND INSTRUCTIONS.
 - EXISTING TREES
INDICATES TEMPORARY FENCE (SEE TREE SCHEDULE FOR ADDITIONAL WORK)
 - INDICATES TRANSPLANTED SALVAGED TREES
 - INDICATES TREE REMOVAL

- PAVEMENT MARKING LEGEND**
- ① THERMOPLASTIC PAVEMENT MARKING - LINE 4", SOLID WHITE
 - ② THERMOPLASTIC PAVEMENT MARKING - LINE 4", SOLID YELLOW
 - ③ THERMOPLASTIC PAVEMENT MARKING - LINE 4", WHITE SKIP-DASH (10' LINE - 30' SKIP) (TYP)
 - ④ THERMOPLASTIC PAVEMENT MARKING - LINE 4", YELLOW SKIP-DASH (10' LINE - 30' SKIP) (TYP)
 - ⑤ THERMOPLASTIC PAVEMENT MARKING - LINE 4", DOUBLE SOLID YELLOW
 - ⑥ THERMOPLASTIC PAVEMENT MARKING - LINE 6", SOLID WHITE
 - ⑦ THERMOPLASTIC PAVEMENT MARKING - LINE 6", WHITE DOTTED (2' LINE - 6' SKIP) (TYP)
 - ⑧ THERMOPLASTIC PAVEMENT MARKING - LINE 12", SOLID WHITE
 - ⑨ THERMOPLASTIC PAVEMENT MARKING - LINE 12", SOLID YELLOW
 - ⑩ THERMOPLASTIC PAVEMENT MARKING - LINE 24", SOLID WHITE
 - ⑪ THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS (8' TYP)

FILE NAME = G:\S09021\CADD_Sheets\9021FS04.dgn	USER NAME = IE Consultants	DESIGNED -	REVISIONS -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	LILY CACHE LANE SIGNING, PAVEMENT MARKING & LANDSCAPING PLAN			F.A.U.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN -	REVISIONS -		SCALE:	SHEET NO. OF SHEETS	STA. 38+00 TO STA. 43+00	1578	06-00046-01-PV	WILL	244	183
		CHECKED -	REVISIONS -		CONTRACT NO. 63503							
		DATE -	REVISIONS -		ILLINOIS FED. AID PROJECT							