

CODED PAY ITEM NO.	ITEM	UNIT	TOTAL QUANTITY	0004	0005	0021	0021	0021	0031	0043
				RECONSTRUCTION, NO CAPACITY ADDED	SYSTEM PRESERVATION, RESURFACING	SAFETY (TRAFFIC SIGNALS)	SAFETY (LIGHTING)	SAFETY (SIDEWALKS)	LANDSCAPING AND OTHER SCENIC BEAUTIFICATION	NON-PARTICIPATING
● 84400105	RELOCATE EXISTING LIGHTING UNIT	EACH	2				2			
● 85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	1			1				
● 85700205	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET, SPECIAL	EACH	1			1				
● 86400100	TRANSCIEVER - FIBER OPTIC	EACH	1			1				
● 87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	1554			1554				
● 87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	2275			2275				
● 87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	2385			2385				
● 87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	2842			2842				
● 87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	4253			4253				
● 87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2C	FOOT	112			112				
● 87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL 16 FT.	EACH	2			2				
● 87700170	STEEL MAST ARM ASSEMBLY AND POLE, 26 FT.	EACH	1			1				
● 87700200	STEEL MAST ARM ASSEMBLY AND POLE, 32 FT.	EACH	1			1				
● 87700250	STEEL MAST ARM ASSEMBLY AND POLE, 42 FT.	EACH	1			1				
● 87700290	STEEL MAST ARM ASSEMBLY AND POLE, 50 FT.	EACH	1			1				
● 87700300	STEEL MAST ARM ASSEMBLY AND POLE, 52 FT.	EACH	1			1				
● 87700400	STEEL MAST ARM ASSEMBLY AND POLE, 60 FT.	EACH	1			1				
● 87800100	CONCRETE FOUNDATION, TYPE A	FOOT	8			8				
● 87800150	CONCRETE FOUNDATION, TYPE C	FOOT	4			4				
● 87800400	CONCRETE FOUNDATION, TYPE E 30-INCH DIAMETER	FOOT	30			30				
● 87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	45			45				
● 87800420	CONCRETE FOUNDATION, TYPE E 42-INCH DIAMETER	FOOT	21			21				
● 87900200	DRILL EXISTING HANDHOLE	EACH	2			2				
● 88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	8			8				
● 88030110	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST-ARM MOUNTED	EACH	10			10				
● 88030240	SIGNAL HEAD, LED, 2-FACE, 1-3 SECTION, 1-5 SECTION, BRACKET MOUNTED	EACH	2			2				
● 88102747	PEDESTRIAN SIGNAL HEAD, LED, 2-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	4			4				
● 88200210	TRAFFIC SIGNAL BACKPLATE, LOUVERED, ALUMINUM	EACH	18			18				
● 88500100	INDUCTIVE LOOP DETECTOR	EACH	15			15				
● 88600100	DETECTOR LOOP, TYPE I	FOOT	652			652				
● 88700200	LIGHT DETECTOR	EACH	3							3
● 88700300	LIGHT DETECTOR AMPLIFIER	EACH	1							1
● 88800100	PEDESTRIAN PUSH-BUTTON	EACH	8			8				
● 89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	1			1				
● 89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	3513			1923	1590			

● SPECIALTY ITEM

FILE NAME = ...load\sheet\2363_Sum_Quant.dgn

USER NAME = blg

DESIGNED - BLG

REVISED -

DRAWN - BLG

REVISED -

PLOT SCALE = 50.0000 / IN.

CHECKED - DJK

REVISED -

PLOT DATE = 11/3/2010

DATE - 10-22-10

REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SHEET NO. 5 OF 7 SHEETS

F.A.P. RTE. 334

SECTION 09-00057-00-CH

COUNTY COOK

TOTAL SHEETS 103

SHEET NO. 8

CONTRACT NO. 63523

FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT M-9003660