

EARTHWORK SCHEDULE - GREENLEAF AVENUE				
ITEM	UNIT	STAGE 1	STAGE 2	STAGE 3
EARTH EXCAVATION	C.Y.	457	540	646
EARTH EXCAVATION ADJUSTED FOR SHRINKAGE	C.Y.	389	459	549
EMBANKMENT REQUIRED	C.Y.	246	785	9
EARTHWORK BALANCE				
WASTE (+) OR SHORTAGE (-)	C.Y.	+143	-326	+540

EARTHWORK SCHEDULE - IL ROUTE 83 (BUSSE ROAD)				
ITEM	UNIT	STAGE 1	STAGE 2	STAGE 3
EARTH EXCAVATION	C.Y.	-	-	905
EARTH EXCAVATION ADJUSTED FOR SHRINKAGE	C.Y.	-	-	769
EMBANKMENT REQUIRED	C.Y.	-	-	69
EARTHWORK BALANCE				
WASTE (+) OR SHORTAGE (-)	C.Y.	-	-	+700

SHRINKAGE CALCULATED USING 15% SHRINKAGE FACTOR

A PAY ITEM FOR "FURNISHED EXCAVATION" HAS BEEN INCLUDED ON THE ASSUMPTION THAT, DUE TO LIMITED WORKING SPACE, ALL EMBANKMENT MAY HAVE TO BE BROUGHT IN FROM OUTSIDE THE PROJECT LIMITS.

SCHEDULE OF DRIVEWAY PAVEMENT REMOVAL & REPLACEMENT		
STATION	DRIVEWAY PAVEMENT REMOVAL	PCC DW, 8", SPECIAL
402+12, LT	103 SY	106 SY
402+19, RT	112 SY	176 SY
402+87, RT*	38 SY	0 SY
403+50, RT	62 SY	64 SY
404+66, LT	75 SY	75 SY
405+08, RT	112 SY	113 SY
406+70, RT	109 SY	120 SY
407+65, RT	31 SY	34 SY
410+95, LT	127 SY	109 SY
412+15, RT	52 SY	61 SY
413+25, LT	117 SY	113 SY
413+38, RT	58 SY	65 SY
415+05, RT	103 SY	115 SY
415+34, LT	141 SY	128 SY

* PROPOSED DRIVEWAY AREA COMBINED WITH DRIVEWAY AT 402+19, RT