SUMMARY OF QUANTITIES

CODE NO.	ITEMS	UNIT	QUANTITY (0005)
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	17
25200110	SODDING, SALT TOLERANT	SQ YD	17
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	3,810
40600300	AGGREGATE (PRIME COAT)	TON	76
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	1334
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	715
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	2134
44000162	HOT-MIX ASPHALT SURFACE REMOVAL, 3 1/4"	SQ YD	19,052
44201737	CLASS D PATCHES, TYPE I, 8 INCH	SQ YD	476
44201741	CLASS D PATCHES, TYPE II, 8 INCH	SQ YD	476
44201745	CLASS D PATCHES, TYPE III, 8 INCH	SQ YD	476
44201747	CLASS D PATCHES, TYPE IV, 8 INCH	SQ YD	476
44300100	AREA REFLECTIVE CRACK CONTROL TREATMENT	SQ YD	19052
X6030310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	83
67100100	MOBILIZATION	L SUM	1
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1,290
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	252
Z0004562	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	100
XX003453	PCC DRIVEWAY REMOVAL AND REPLACEMENT	SQ YD	10

* SPECIALTY ITEMS

FILE NAME = p:\f0142560_franklin park - pavement resurfacing\plans\sheets\f0142560qtbx0001.dgn	USER NAME = $USER$	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 20.0000 ' / IN.	CHECKED -	REVISED -
	PLOT DATE = 10/28/2010	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

HAWTHORNE ELDER EMERSON AVENUE
SUMMARY OF QUANTITIES

SCALE: N/A | SHEET NO. 1 OF 1 SHEETS | STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	10-00077-00-RS	COOK	16	3

CONTRACT NO. 63526

ILLINOIS | FED. AID PROJECT