

CODED PAY ITEM NO.	ITEM	UNIT	TOTAL QUANTITY	0004	0005	0021	0021	0021	0031	0043
				RECONSTRUCTION, NO CAPACITY ADDED	SYSTEM PRESERVATION, RESURFACING	SAFETY (TRAFFIC SIGNALS)	SAFETY (LIGHTING)	SAFETY (SIDEWALKS)	LANDSCAPING AND OTHER SCENIC BEAUTIFICATION	NON-PARTICIPATING
56201100	WATER SERVICE LINE 3"	FOOT	27							27
56300100	ADJUSTING SANITARY SEWERS, 8-INCH DIAMETER OR LESS	FOOT	150							150
56400810	FIRE HYDRANT EXTENSION	FOOT	6							6
56400820	FIRE HYDRANT WITH AUXILIARY VALVE AND VALVE BOX	EACH	6							6
56500800	DOMESTIC WATER SERVICE BOXES	EACH	4							4
60109510	PIPE UNDERDRAINS, FABRIC LINED TRENCH 4"	FOOT	500	500						
60201340	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	12	12						
60205040	CATCH BASINS, TYPE A, 5'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	3	3						
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	3	3						
60219540	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	1	1						
60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1						
60223800	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1						
60224039	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	1	1						
60224446	MANHOLES, TYPE A, 7'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1						
X602281 0	MANHOLES, SANITARY, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1							1
X60228 20	MANHOLES, SANITARY, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2							2
60234200	INLETS, TYPE A, TYPE 1 FRAME, OPEN LID	EACH	1		1					
60237470	INLETS, TYPE A, TYPE 24 FRAME AND GRATE	EACH	12	12						
60255500	MANHOLES TO BE ADJUSTED	EACH	5	5						
X60260 51	SANITARY MANHOLES TO BE RECONSTRUCTED	EACH	1	1						
60260100	INLETS TO BE ADJUSTED	EACH	1	1						
60266600	VALVE BOXES TO BE ADJUSTED	EACH	1							1
X6026632	VALVE BOXES TO BE REMOVED	EACH	2							2
60500040	REMOVING MANHOLES	EACH	4	4						
60500050	REMOVING CATCH BASINS	EACH	10	10						
60500060	REMOVING INLETS	EACH	14	13	1					
60600605	CONCRETE CURB, TYPE B	FOOT	72	72						
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	515	515						
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	2688	2633	55					
60605400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24 (SPECIAL)	FOOT	1069	1069						
60605900	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-9.12	FOOT	2057		2057					
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	628	100	528					
X60619 00	CONCRETE MEDIAN, TYPE SB-6.12 (SPECIAL)	SQ FT	1389	1389						
60620800	CONCRETE MEDIAN, TYPE SB-9.12	SQ FT	178		178					
60624600	CORRUGATED MEDIAN	SQ FT	47	47						
66900205	SPECIAL WASTE DISPOSAL	CU YD	160	160						
66900450	SPECIAL WASTE PLANS AND REPORT	L SUM	1	1						
66900530	SOIL DISPOSAL ANALYSIS	EACH	1	1						

● SPECIALTY ITEM

FILE NAME =
...oad\sheet\2362_Sum_Quant.dgn

USER NAME = blg	DESIGNED - BLG	REVISED -
PLOT SCALE = 50.0000' / IN.	DRAWN - BLG	REVISED -
PLOT DATE = 11/3/2010	CHECKED - DJK	REVISED -
	DATE - 10-22-10	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SHEET NO. 3 OF 7 SHEETS

F.A.P. RTE. 334	SECTION 09-00056-00-CH	COUNTY COOK	TOTAL SHEETS 111	SHEET NO. 6
CONTRACT NO. 63527				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT M-90031659				