

CODED PAY ITEM NO.	ITEM	UNIT	TOTAL QUANTITY	0004	0005	0021	0021	0021	0031	0043
				RECONSTRUCTION, NO CAPACITY ADDED	SYSTEM PRESERVATION, RESURFACING	SAFETY (TRAFFIC SIGNALS)	SAFETY (LIGHTING)	SAFETY (SIDEWALKS)	LANDSCAPING AND OTHER SCENIC BEAUTIFICATION	NON-PARTICIPATING
66900565	PNAS SOIL ANALYSIS	EACH	1	1						
66900590	RCRA METALS TCLP SOIL ANALYSIS	EACH	1	1						
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	9	9						
67100100	MOBILIZATION	L SUM	1	1						
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1						
XX008438	TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR	EACH	1	1						
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	36	36						
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	6886	1755	5131					
70300210	TEMPORARY PAVEMENT MARKING- LETTERS AND SYMBOLS	SQ FT	218	73	145					
70300220	TEMPORARY PAVEMENT MARKING- LINE 4"	FOOT	14162	10793	3369					
70300240	TEMPORARY PAVEMENT MARKING- LINE 6"	FOOT	725	525	200					
70300260	TEMPORARY PAVEMENT MARKING- LINE 12"	FOOT	106	106						
70300280	TEMPORARY PAVEMENT MARKING- LINE 24"	FOOT	175	45	130					
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	13605	11895	1710					
72000100	SIGN PANEL - TYPE 1	SQ FT	257	102	123	32				
72000200	SIGN PANEL - TYPE 2	SQ FT	25			25				
72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	29	16	13					
72400200	REMOVE SIGN PANEL ASSEMBLY - TYPE B	EACH	5	2	3					
72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	567	375	192					
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	219		219					
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	3100		3100					
78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1431		1431					
78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	132		132					
78008200	POLYUREA PAVEMENT MARKING TYPE I - LETTERS AND SYMBOLS	SQ FT	146	146						
78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	5412	5412						
78008230	POLYUREA PAVEMENT MARKING TYPE I - LINE 6"	FOOT	913	913						
78008250	POLYUREA PAVEMENT MARKING TYPE I - LINE 12"	FOOT	663	663						
78008270	POLYUREA PAVEMENT MARKING TYPE I - LINE 24"	FOOT	79	79						
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	136		136					
78300100	PAVEMENT MARKING REMOVAL	SQ FT	2310	215	2095					
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	136		136					
81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	851			851				
81000700	CONDUIT IN TRENCH, 2 1/2" DIA., GALVANIZED STEEL	FOOT	302			302				
81000800	CONDUIT IN TRENCH, 3" DIA., GALVANIZED STEEL	FOOT	106			106				
81001000	CONDUIT IN TRENCH, 4" DIA., GALVANIZED STEEL	FOOT	112			112				
81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	450			450				
81018600	CONDUIT PUSHED, 2 1/2" DIA., GALVANIZED STEEL	FOOT	75			75				
81018900	CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL	FOOT	566			566				

● SPECIALTY ITEM

FILE NAME = ...road\sheet\2362_Sum_Quant.dgn

USER NAME = blg	DESIGNED - BLG	REVISED -
PLOT SCALE = 52.0000 1/ IN.	DRAWN - BLG	REVISED -
PLOT DATE = 11/3/2010	CHECKED - DJK	REVISED -
	DATE - 10-22-10	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SHEET NO. 4 OF 7 SHEETS

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
334	09-00056-00-CH	COOK	111	7
CONTRACT NO. 63527				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT M-9003659				