

CODED PAY ITEM NO.	ITEM	UNIT	TOTAL QUANTITY	0004	0005	0021	0021	0021	0031	0043
				RECONSTRUCTION, NO CAPACITY ADDED	SYSTEM PRESERVATION, RESURFACING	SAFETY (TRAFFIC SIGNALS)	SAFETY (LIGHTING)	SAFETY (SIDEWALKS)	LANDSCAPING AND OTHER SCENIC BEAUTIFICATION	NON-PARTICIPATING
81400100	HANDHOLE	EACH	4			4				
81400200	HEAVY-DUTY HANDHOLE	EACH	4			4				
81400300	DOUBLE HANDHOLE	EACH	3			3				
81603055	UNIT DUCT, 600V, 3-1C NO.8, 1/C NO.8 GROUND, (XLP-TYPE USE), 1" DIA. POLYETHYLENE	FOOT	385				385			
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	1315			1315				
81900302	TRENCH AND BACKFILL WITH SCREENINGS OR SAND	FOOT	361				361			
83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	20				20			
85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	2			2				
85700205	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET, SPECIAL	EACH	1			1				
86400100	TRANSCEIVER - FIBER OPTIC	EACH	1			1				
87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	1543			1543				
87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	2334			2334				
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	2311			2311				
87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	2800			2800				
87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	3841			3841				
87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2C	FOOT	44			44				
87502440	TRAFFIC SIGNAL POST, GALVANIZED STEEL 10 FT.	EACH	3			3				
87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL 16 FT.	EACH	2			2				
87502520	TRAFFIC SIGNAL POST, GALVANIZED STEEL 18 FT.	EACH	1			1				
87700180	STEEL MAST ARM ASSEMBLY AND POLE, 28 FT.	EACH	1			1				
87700220	STEEL MAST ARM ASSEMBLY AND POLE, 36 FT.	EACH	1			1				
87700250	STEEL MAST ARM ASSEMBLY AND POLE, 42 FT.	EACH	1			1				
87700270	STEEL MAST ARM ASSEMBLY AND POLE, 46 FT.	EACH	1			1				
87700330	STEEL MAST ARM ASSEMBLY AND POLE, 56 FT.	EACH	2			2				
87800100	CONCRETE FOUNDATION, TYPE A	FOOT	24			24				
87800150	CONCRETE FOUNDATION, TYPE C	FOOT	4			4				
87800400	CONCRETE FOUNDATION, TYPE E 30-INCH DIAMETER	FOOT	30			30				
87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	30			30				
87800420	CONCRETE FOUNDATION, TYPE E 42-INCH DIAMETER	FOOT	42			42				
87900200	DRILL EXISTING HANDHOLE	EACH	2			2				
88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	8			8				
88030110	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST-ARM MOUNTED	EACH	10			10				
88030240	SIGNAL HEAD, LED, 2-FACE, 1-3 SECTION, 1-5 SECTION, BRACKET MOUNTED	EACH	2			2				
88102717	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	4			4				
88102747	PEDESTRIAN SIGNAL HEAD, LED, 2-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	2			2				
88200210	TRAFFIC SIGNAL BACKPLATE, LOUVERED, ALUMINUM	EACH	18			18				
88500100	INDUCTIVE LOOP DETECTOR	EACH	14			14				
88600100	DETECTOR LOOP, TYPE I	FOOT	617			617				

● SPECIALTY ITEM

FILE NAME = ...sheet\2362_Sum_Quant.dgn

USER NAME = blg
 PLOT SCALE = 50.0000' / IN.
 PLOT DATE = 11/3/2010

DESIGNED - BLG
 DRAWN - BLG
 CHECKED - DJK
 DATE - 10-22-10

REVISED -
 REVISED -
 REVISED -
 REVISED -

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SHEET NO. 5 OF 7 SHEETS

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
334	09-00056-00-CH	COOK	111	8
CONTRACT NO. 63527				
<small>FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT M-9003659</small>				