

NOTES:

- 1. USE BLACK LETTERING ON ORANGE BACKGROUND.
- 2. ERECT SIGNS IN ADVANCE OF THE LOCATION FOR THE "ROAD CONSTRUCTION AHEAD" SIGN AT LOCATIONS AS DIRECTED BY THE ENGINEER.
- 3. ERECT SIGN (1) WITH INSTALLED PANEL (2) ONE WEEK PRIOR TO THE START OF CONSTRUCTION.
- 4. REMOVE PANEL 2 SOON AFTER THE START OF CONSTRUCTION.
- 5. SEE SPECIAL PROVISION FOR "TEMPORARY INFORMATION SIGNING" FOR ADDITIONAL INFORMATION.
- 6. ONE SIGN ASSEMBLY EQUALS 25.70 SQ. FT. (2.3 SQ. M.)
- 7. SHALL BE PAID FOR AS TEMPORARY INFORMATION SIGNING.

ALL DIMENSIONS ARE IN INCHES (MILLIMETERS)
UNLESS OTHERWISE SHOWN.

	FILE NAME =	USER NAME = gaglianobt	DESIGNED -	REVISED - R. MIRS 09-15-97	***************************************
- 1	W:\diststd\22x34\tc22.dgn		DRAWN -	REVISED - R. MIRS 12-11-97	
		PLOT SCALE = 50.000 '/ IN.	CHECKED -	REVISED -T. RAMMACHER 02-02-99	DEPA
		PLOT DATE = 1/4/2008	DATE -	REVISED - C. JUCIUS 01-31-07	

STATI	E 01	ILLINOIS
DEPARTMENT	0F	TRANSPORTATION

-	ARTERIAL ROAD	F.A.P. RTE.	SEC
	INFORMATION SIGN	344	09-0005
			TC-22
SCALE: NONE	SHEET NO. 1 OF 1 SHEETS STA. TO STA.	FED. R	OAD DIST. NO. 1

F.A.P. SECTION					COUNT	Y	TOTAL	SHEET NO.	
344	344 09-00056-00-CH				COOK	(111	83	
TC-22					C	ONTR	ACT	NO. 6	3527
FED.	ROAD DIST.	NO. 1	ILLINOIS	FED.	AID P	ROJECT	M-9	003(659)