

SUMMARY OF QUANTITIES

SPECIALITY ITEMS	SPECIAL PROVISIONS	CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE 0014
		20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	55	55
	•	20200100	EARTH EXCAVATION	CU YD	117	117
	•	20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	138	138
		20400800	FURNISHED EXCAVATION	CU YD	36	36
	•	21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	802	802
		25000210	SEEDING, CLASS 2A	ACRE	0.17	0.17
		25000400	NITROGEN FERTILIZER NUTRIENT	POUND	15	15
		25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	15	15
		28000500	INLET AND PIPE PROTECTION	EACH	2	2
		31101200	SUBBASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	239	239
		35101600	AGGREGATE BASE COURSE, TYPE B 4"	SQ YD	242	242
		40300100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	39	39
		40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	24	24
		40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	92	92
		42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	1,998	1,998
		44000100	PAVEMENT REMOVAL	SQ YD	296	296
		44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	564	564
		44000600	SIDEWALK REMOVAL	SQ FT	2,091	2,091
		50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	1	1
		50102400	CONCRETE REMOVAL	CU YD	9.7	9.7
		50300225	CONCRETE STRUCTURES	CU YD	19.5	19.5
		50300255	CONCRETE SUPERSTRUCTURE	CU YD	102.1	102.1
	•	50300300	PROTECTIVE COAT	SQ YD	206	206
		50400305	PRECAST PRESTRESSED CONCRETE DECK BEAMS (17" DEPTH)	SQ FT	1,853	1,853
		50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	27,140	27,140
S		50901720	BICYCLE RAILING	FOOT	59	59

SUMMARY OF QUANTITIES

SPECIALITY ITEMS	SPECIAL PROVISIONS	CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE 0014
S		50901750	PARAPET RAILING	FOOT	102	102
		59000200	EPOXY CRACK INJECTION	FOOT	50	50
		60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	1	1
		60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	334	334
		60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	170	170
S		63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	1	1
S		63100070	TRAFFIC BARRIER TERMINAL, TYPE 5	EACH	1	1
S		63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	1	1
S	•	63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	1	1
		63200310	GUARDRAIL REMOVAL	FOOT	238	238
		67100100	MOBILIZATION	L SUM	1	1
	•	X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1
		70300320	PAVEMENT MARKING TAPE, TYPE I 4"	FOOT	1,336	1,336
		70300330	PAVEMENT MARKING TAPE, TYPE I 5"	FOOT	989	989
		70400100	TEMPORARY CONCRETE BARRIER	FOOT	504	504
		72400710	RELOCATE SIGN PANEL - TYPE 1	SQ FT	6	6
S		78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	225	225
S		78000300	THERMOPLASTIC PAVEMENT MARKING - LINE 5"	FOOT	180	180
S		78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	930	930
S		78008220	POLYUREA PAVEMENT MARKING TYPE I - LINE 5"	FOOT	777	777
S		78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	20	20
S	•	78200450	MONODIRECTIONAL GUARD RAIL REFLECTORS	EACH	4	4
S		78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	1	1
		78300100	PAVEMENT MARKING REMOVAL	SQ FT	63	63
S		78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	20	20
	•	Z0004552	APPROACH SLAB REMOVAL	SQ YD	130	130

FILE NAME = LC0907-sh1-S00-1.dgn

USER NAME = 320200907

DESIGNED - TC

REVISED -

DRAWN - PWL

REVISED -

PLOT SCALE = 100.0000' / IN.

CHECKED - MRH

REVISED -

PLOT DATE = 11/2/2010

DATE - 11/2/2010

REVISED -

REVISED -

REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

F.A.U. RTE. 2626

SECTION 05-00193-04-BR

COUNTY LAKE

TOTAL SHEETS 36

SHEET NO. 3

CONTRACT NO. 63531

SCALE: NTS SHEET NO. 1 OF 2 SHEETS STA. N/A TO STA. N/A

FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT