



Drill 3-1/4" ϕ Holes in new wearing surface only for 1" ϕ x 11" dowel bars. Traffic side only. Cost included with Temporary Concrete Barrier.

NEW DECK BEAM

EXISTING DECK BEAM

*** Drilling into PPC deck beam is prohibited.
Embedment of 2 3/4" Dowel Bar into HMA wearing surface only.

NOTES

Any hole drilled into the wearing surface shall be repaired upon removal of the Temporary Concrete Barrier. Cost shall be included in the pay item Temporary Concrete Barrier.

For quantities and payment of Temporary Concrete Barrier see Roadway Plans.

SECTIONS THRU OR DECK BEAM



FILE NAME = 0493040-63531-009-TempBarrier.dgn	USER NAME = 320200907	DESIGNED - KO	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	TEMPORARY CONCRETE BARRIER FOR STAGE CONSTRUCTION STRUCTURE NO. 049-3040 (NB)	F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLLOT SCALE = 2.0000' / IN.	CHECKED - WPM	REVISED -			2626	05-00193-04-BR	LAKE	36	20
	PLLOT DATE = 10/25/2010	DRAWN - KO	REVISED -			CONTRACT NO. 63531				
	CHECKED - WPM	REVISED -		SHEET NO. 9 OF 15 SHEETS		ILLINOIS FED. AID PROJECT				