

SUMMARY OF QUANTITIES

URBAN

CODE	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE 90% FEDERAL / 10% STATE				
				ROADWAY	I-74 SN	S.B. RAMP 081-0115	I-74 N.B. RAMP SN 081-0116	SAFETY
				0004		0014	0014	0021
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SO YD	63	63				
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SO FT	1,160	1,160				
44000100	PAVEMENT REMOVAL	SO YD	36	36				
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	145	145				
44000600	SIDEWALK REMOVAL	SO FT	1,160	1,160				
50102400	CONCRETE REMOVAL	CU YD	44.6		25.6	19.0		
50157300	PROTECTIVE SHIELD	SO YD	2,560		1,705	855		
50300225	CONCRETE STRUCTURES	CU YD	66.8		32.8	34.0		
50300255	CONCRETE SUPERSTRUCTURE	CU YD	1,236.5		771.3	465.2		
50300260	BRIDGE DECK GROOVING	SO YD	3,660		2,365	1,295		
50300300	PROTECTIVE COAT	SO YD	4,600		2,930	1,670		
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1			1		
50500505	STUD SHEAR CONNECTORS	EACH	5,700		3,144	2,556		
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	325,370		199,570	125,800		
50800515	BAR SPLICERS	EACH	81		35	46		
51500100	NAME PLATES	EACH	2		1	1		
52000110	PREFORMED JOINT STRIP SEAL	FOOT	230		132	98		
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	270	270				
550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	130	130				
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	145	145				
* 63100070	TRAFFIC BARRIER TERMINAL, TYPE 5	EACH	3		1	2		
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	3		2	1		
63200310	GUARDRAIL REMOVAL	FOOT	175		102	73		
63500105	DELINEATORS	EACH	12		6	6		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	9		4.5	4.5		
67100100	MOBILIZATION	L SUM	1		0.50	0.50		

\* SPECIALTY ITEMS

S00-1

**JACOBS**

FILE NAME = F:\_2009\C9494102\Cadd\Task1\Civil\Sheet	USER NAME = agensch Files\S0001.dgn	DESIGNED - AEG DRAWN - MJP	REVISOR REVISOR REVISOR	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	SCALE: NONE	SHEET NO. OF SHEETS STA. TO STA.	F.A.I. RTE. 74	SECTION (81-1)BID	COUNTY ROCK ISLAND	TOTAL SHEETS 78	SHEET NO. 3	CONTRACT NO. 64D95
PLT SCALE = #IMS_PLT_SCALE	PLT DATE = 10/29/2010	CHECKED - TAI DATE = 10/29/10	REVISOR					FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT				