

SUMMARY OF QUANTITIES

URBAN

CODE	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE 90% FEDERAL / 10% STATE				
				ROADWAY	I-74 SN 081-0115	S.B. RAMP SN 081-0115	I-74 N.B. RAMP SN 081-0116	SAFETY
				0004		0014	0014	0021
* 70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L SUM	1	1				
* 70100820	TRAFFIC CONTROL AND PROTECTION, STANDARD 701451	L SUM	1	1				
* X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1				
* 70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1				
* 70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1				
* 70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1				
* 70106800	CHANGEABLE MESSAGE SIGN	CAL MO	12	12				
* 70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	2,327	2,327				
* 70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	790	790				
* 70400100	TEMPORARY CONCRETE BARRIER	FOOT	300				300	
78200410	GUARDRAIL MARKERS, TYPE A	EACH	10	10				
78200520	BARRIER WALL MARKERS, TYPE B	EACH	60			34	26	
* 78300100	PAVEMENT MARKING REMOVAL	SQ FT	747	747				
* 81012600	CONDUIT IN TRENCH, 2" DIA., PVC	FOOT	108					108
* 81022100	CONDUIT ENCASED IN CONCRETE, 2" DIA., PVC	FOOT	4					4
* 81100600	CONDUIT ATTACHED TO STRUCTURE, 2" DIA., GALVANIZED STEEL	FOOT	872					872
* 81200230	CONDUIT EMBEDDED IN STRUCTURE, 2" DIA., PVC	FOOT	700					700
* 81300530	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 12" X 10" X 6"	EACH	2					2
* 81702415	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 3-1/C NO. 6	FOOT	1,964					1,964
* 81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	108					108
* 82102400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT	EACH	3					3
* 82107300	UNDERPASS LUMINAIRE, 150 WATT, HIGH PRESSURE SODIUM VAPOR	EACH	8					8
* 84200500	REMOVAL OF LIGHTING UNIT, SALVAGE	EACH	11					11
* X0322011	LIGHT POLE REMOVE AND RE-ERECT	EACH	3					3
* X0323160	VIDEO INSPECTION OF STORM SEWER	FOOT	400	400				

* SPECIALTY ITEMS

NON-PARTICIPATING
100% STATE

S00-2

JACOBS

FILE NAME *	USER NAME * egensch	DESIGNED - AEG	REVISED
Files\50002.dgn		DRAWN - MJP	REVISED
PLOT SCALE * (SMS.PLT.SCALE)		CHECKED - TAI	REVISED
PLOT DATE * 11/8/2010		DATE - 10/29/10	REVISED

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: NONE SHEET NO. OF SHEETS STA. TO STA.

F.A.I. RTE. 74	SECTION (81-1HB)D	COUNTY ROCK ISLAND	TOTAL SHEETS 78	SHEET NO. 4
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
CONTRACT NO. 64D95				