

SCHEDULE OF QUANTITIES

42001430 BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)						
SQ YD	LOCATION					REMARKS
27.0	RAMPS	91+16	TO	91+26		SN 081-0115
18.0	RAMPS	87+81	TO	87+91		SN 081-0116
18.0	RAMPS	93+06	TO	93+16		SN 081-0116
TOTAL						

42400200 PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH						
SQ FT	LOCATION					REMARKS
1,160.0	19TH ST	205+62	TO	207+07		
TOTAL						

44000100 PAVEMENT REMOVAL						
SQ YD	LOCATION					REMARKS
36.0	RAMPS	87+81	TO	88+01		SN 081-0116
TOTAL						

44000500 COMBINATION CURB AND GUTTER REMOVAL						
FOOT	LOCATION					REMARKS
145.0	19TH ST	205+62	TO	207+07		
TOTAL						

44000600 SIDEWALK REMOVAL						
SQ FT	LOCATION					REMARKS
1160.0	19TH ST	205+62	TO	207+07		
TOTAL						

550A0340 STORM SEWERS, CLASS A, TYPE 2 12"						
FOOT	LOCATION					REMARKS
270.0	19TH ST	205+00	TO	209+00		
TOTAL						

550A0360 STORM SEWERS, CLASS A, TYPE 2 15"						
FOOT	LOCATION					REMARKS
130.0	19TH ST	205+00	TO	209+00		
TOTAL						

60605000 COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24						
FOOT	LOCATION					REMARKS
145.0	19TH ST	205+62	TO	207+07		
TOTAL						

63100070 TRAFFIC BARRIER TERMINAL, TYPE 5						
EACH	LOCATION					REMARKS
1.0	RAMP	82+50	TO	92+50		SN 081-0115
2.0	RAMP	87+00	TO	92+50		SN 081-0116
TOTAL						

63100085 TRAFFIC BARRIER TERMINAL, TYPE 6						
EACH	LOCATION					REMARKS
2.0	RAMP	82+50	TO	92+50		SN 081-0115
1.0	RAMP	87+00	TO	92+50		SN 081-0116
TOTAL						

63200310 GUARDRAIL REMOVAL						
FOOT	LOCATION					REMARKS
102.0	RAMP	82+50	TO	92+50		SN 081-0115
73.0	RAMP	87+00	TO	92+50		SN 081-0116
TOTAL						

63500105 DELINEATORS						
EACH	LOCATION					REMARKS
6.0	RAMPS	82+75	TO	92+00		SN 081-0115
6.0	RAMPS	87+50	TO	93+80		SN 081-0116
TOTAL						

70300220 TEMPORARY PAVEMENT MARKING - LINE 4"						
FOOT	LOCATION					REMARKS
1144.0	7TH AVE	98+60	TO	112+25		WHITE EDGE EB
213.0	7TH AVE	98+60	TO	112+25		YELLOW EDGE EB
370.0	7TH AVE	115+05	TO	118+75		YELLOW EDGE WB
600.0	RAMPS					WHITE EDGE 081-0116
TOTAL						

70301000 WORK ZONE PAVEMENT MARKING REMOVAL						
SO FT	LOCATION					REMARKS
452.0	7TH AVE	98+60	TO	112+25		WHITE EDGE EB
71.0	7TH AVE	107+36	TO	109+49		YELLOW EDGE EB
67.0	7TH AVE	115+05	TO	117+05		WHITE EDGE WB
200.0	RAMP					WHITE EDGE 081-0116
TOTAL						

70400100 TEMPORARY CONCRETE BARRIER						
FOOT	LOCATION					REMARKS
300	RAMP	91+90	TO	94+90		SN 081-0116
TOTAL						

78200410 GUARDRAIL MARKERS, TYPE A						
EACH	LOCATION					REMARKS
5.0	RAMP	82+50	TO	92+50		SN 081-0115
5.0	RAMP	87+00	TO	92+50		SN 081-0116
TOTAL						

78200520 BARRIER WALL MARKERS, TYPE B						
EACH	LOCATION					REMARKS
34.0	RAMPS	83+75	TO	91+05		SN 081-0115
26.0	RAMPS	88+00	TO	93+16		SN 081-0116
TOTAL						

78300100 PAVEMENT MARKING REMOVAL						
SQ FT	LOCATION					REMARKS
455.0	RAMP	91+88	TO	95+05		WHITE EDGE 081-0116
113.0	7TH AVE	98+60	TO	112+25		WHITE SKIP-DASH EB
100.0	7TH AVE	115+05	TO	117+05		WHITE LEFT TURN LANE WB
79.0	7TH AVE	107+87	TO	109+45		WHITE RIGHT TURN LANE EB
TOTAL						

81012600 CONDUIT IN TRENCH, 2" DIA., PVC						
FOOT	LOCATION					REMARKS
13.0	RAMP	82+50	TO	92+50		SN 081-0115
95.0	RAMP	87+00	TO	92+50		SN 081-0116
TOTAL						

81022100 CONDUIT ENCASED IN CONCRETE, 2" DIA., PVC						
FOOT	LOCATION					REMARKS
2.0	RAMP	82+50	TO	92+50		SN 081-0115
2.0	RAMP	87+00	TO	92+50		SN 081-0116
TOTAL						

81100600 CONDUIT ATTACHED TO STRUCTURE, 2" DIA., GALVANIZED STEEL						
FOOT	LOCATION					REMARKS
541.0	RAMP	82+50	TO	92+50		SN 081-0115
331.0	RAMP	87+00	TO	92+50		SN 081-0116
TOTAL						

81200230 CONDUIT EMBEDDED IN STRUCTURE, 2" DIA., PVC						
FOOT	LOCATION					REMARKS
520.0	RAMP	82+50	TO	92+50		SN 081-0115
180.0	RAMP	87+00	TO	92+50		SN 081-0116
TOTAL						

81300530 JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 12" X 10" X 6"						
EACH	LOCATION					REMARKS
1.0	RAMP	82+50	TO	92+50		SN 081-0115
1.0	RAMP	87+00	TO	92+50		SN 081-0116
TOTAL						

81702415 ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 3-1/C NO. 6						
FOOT	LOCATION					REMARKS
1,273.0	RAMP	82+50	TO	92+50		SN 081-0115
691.0	RAMP	87+00	TO	92+50		SN 081-0116
TOTAL						

81900200 TRENCH AND BACKFILL FOR ELECTRICAL WORK						
FOOT	LOCATION					REMARKS
13.0	RAMP	82+50	TO	92+50		SN 081-0115
95.0	RAMP	87+00	TO	92+50		SN 081-0116
TOTAL						

82102400 LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT						
FOOT	LOCATION					REMARKS
2.0	RAMP	82+50	TO	92+50		SN 081-0115
1.0	RAMP	87+00	TO	92+50		SN 081-0116
TOTAL						

82107300 UNDERPASS LUMINAIRE, 150 WATT, HIGH PRESSURE SODIUM VAPOR						
EACH	LOCATION					REMARKS
4.0	RAMP	82+50	TO	92+50		SN 081-0115
4.0	RAMP	87+00	TO	92+50		SN 081-0116
TOTAL						

84200500 REMOVAL OF LIGHTING UNIT, SALVAGE						
EACH	LOCATION					REMARKS
6.0	RAMP	82+50	TO	92+50		SN 081-0115
5.0	RAMP	87+00	TO	92+50		SN 081-0116
TOTAL						

X0322011 LIGHT POLE REMOVE AND RE-ERECT						
EACH	LOCATION					REMARKS
2.0	RAMP	82+50	TO	92+50		SN 081-0115
1.0	RAMP	87+00	TO	92+50		SN 081-0116
TOTAL						

X0323160 VIDEO INSPECTION OF STORM SEWER						
FOOT	LOCATION					REMARKS
400.0	19TH ST	205+00	TO	209+00		
TOTAL						

X5537800 STORM SEWERS TO BE CLEANED 12"						
FOOT	LOCATION					REMARKS
270.0	19TH ST	205+00	TO	209+00		
TOTAL						

X5537900 STORM SEWERS TO BE CLEANED 15"						
FOOT	LOCATION					REMARKS
130.0	19TH ST	205+00	TO	209+00		
TOTAL						

X8900610 URETHANE PAVEMENT MARKING - LINE 4"						
FOOT	LOCATION					REMARKS
718.0	RAMP	87+34	TO	95+00		WHITE EDGE 081-0116
406.0	RAMP	87+82	TO	91+88		YELLOW EDGE 081-0116
703.0	RAMP	84+23	TO	91+26		YELLOW EDGE 081-0115
703.0	RAMP	84+23	TO	91+26		WHITE EDGE 081-0115
339.0	7TH AVE	98+60	TO	112+25		WHITE SKIP DASH EB
TOTAL						

X7800630 URETHANE PAVEMENT MARKING - LINE 6"						
FOOT	LOCATION					REMARKS
173.0	RAMP	84+23	TO	91+05		WHITE SKIP-DASH 081-0115
200.0	7TH AVE	115+05	TO	117+05		WHITE LEFT TURN LANE LINE WB
158.0	7TH AVE	107+87	TO	109+45		WHITE RIGHT TURN LANE LINE EB
TOTAL						

X7800640 URETHANE PAVEMENT MARKING - LINE 8"						
FOOT	LOCATION					REMARKS
624.0	RAMP	91+88	TO	95+05		WHITE EDGE 081-0116
TOTAL						

X7800650 URETHANE PAVEMENT MARKING - LINE 12"						
FOOT	LOCATION					REMARKS
125.0	RAMP	91+88	TO	95+05		WHITE DIAGONAL 081-0116
TOTAL						

XZ030260 IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE, NARROW), TEST LEVEL 3						
EACH	LOCATION					REMARKS
1.0	RAMP	92+00	TO	92+25		SN 081-0116
TOTAL						

Z0001495 BRIDGE APPROACH SHOULDER REMOVAL						
SQ YD	LOCATION					REMARKS
41.0	RAMP	82+50	TO	92+50		SN 081-0115
45.0	RAMP					