

GENERAL NOTES

SEEDING SHALL NOT BE PERMITTED AT ANY TIME WHEN THE GROUND IS FROZEN, WET, OR IN AN UNTILLABLE CONDITION. LOCATIONS TO BE SEEDED WILL BE DETERMINED BY THE ENGINEER.

ANY REFERENCE TO A STANDARD IN THESE PLANS SHALL BE INTERPRETED TO MEAN THE EDITION AS INDICATED BY THE SUBNUMBER SHOWN IN THE LIST OF STANDARDS OR THE COPY INCLUDED IN THESE PLANS.

MEMBERS OF JULIE KNOWN TO BE WITHIN THE LIMITS OF THE IMPROVEMENT ARE:

- COMMONWEALTH EDISON
- AT & T
- COMCAST
- NICOR GAS

THE CONTRACTOR SHALL CONTACT JULIE AT LEAST 48 HOURS PRIOR TO EXCAVATION TO DETERMINE WHICH UTILITIES ARE IN THE AREA.

THE CONTRACTOR SHALL BE AWARE THAT A FOREST MITIGATION PROJECT JUST NORTH OF THE PROPERTY AT 17801 RIVER ROAD WILL BE PERFORMED. THIS PROJECT WILL BE ACCESSED FROM RIVER ROAD USING THE PRIVATE ENTRANCE AT THIS PROPERTY. IN THE EVENT BOTH PROJECTS OCCUR AT THE SAME TIME ARTICLE 105.08 OF THE STANDARD SPECIFICATIONS SHALL GOVERN.

SUMMARY OF QUANTITIES			URBAN 100% STATE
			0044
CONSTRUCTION CODE	TYPE:		
CODE NO.	ITEM	UNIT	TOTAL QUANTITY
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	985
25000200	SEEDING, CLASS 2	ACRE	0.2
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	18
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	18
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	18
25100115	MULCH, METHOD 2	ACRE	0.2
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	20
67100100	MOBILIZATION	L SUM	1
Z0007601	BUILDING REMOVAL NO. 1	L SUM	1
Z0007602	BUILDING REMOVAL NO. 2	L SUM	1
* Z0049901	REMOVAL AND DISPOSAL OF NON-FRIABLE ASBESTOS, BUILDING NO. 1	L SUM	1
* Z0049902	REMOVAL AND DISPOSAL OF NON-FRIABLE ASBESTOS, BUILDING NO. 2	L SUM	1

* SPECIALTY ITEMS

TOPSOIL & SEEDING						
BUILDING NUMBER (PARCEL #)	TOPSOIL FURNISH AND PLACE 4"	SEEDING CLASS 2	NITROGEN FERTILIZER NUTRIENT	PHOSPHORUS FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT	MULCH METHOD 2
	SQ YD	ACRE	POUND	POUND	POUND	ACRE
1 (3RJ0024)	625	0.13	12	12	12	0.13
2 (3RJ0027)	360	0.07	7	7	7	0.07
TOTALS	985	0.20	18	18	18	0.20

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION
DISTRICT THREE

PREPARED BY: *Dana Brown*
DISTRICT STUDIES & PLANS ENGINEER

DATE: 10/27/10

EXAMINED BY: *Subir K. Das*
DISTRICT CONSTRUCTION ENGINEER

Ray L. Phillips
DISTRICT MATERIALS ENGINEER

Bruce C. Huber
DISTRICT OPERATIONS ENGINEER