

# SCHEDULES OF QUANTITIES

## POLYUREA PAVEMENT MARKING

| STA.             | TO | STA.       | DIRECTION | LENGTH (FT) | NUMBER OF STRIPES | EDGELINE LENGTH (FT) | SKIP DASH LENGTH (FT) | SKIP DASH NEAREST 10' (FT) | POLYUREA PAVEMENT MARKING, TYPE 2, LINE 4" 78008310 (FT) |
|------------------|----|------------|-----------|-------------|-------------------|----------------------|-----------------------|----------------------------|--|
| 779+38.47        |    | 781+58.39  | WB        | 219.9       | 2                 | 439.8                | 55.0                  | 60                         | 499.8  |
| 779+38.47        |    | 781+58.39  | EB        | 219.9       | 2                 | 439.8                | 55.0                  | 60                         | 499.8  |
| 1037+74.25       |    | 1040+25.75 | WB        | 251.5       | 2                 | 503.0                | 62.9                  | 70                         | 573.0  |
| 1037+74.25       |    | 1040+25.25 | EB        | 251.0       | 2                 | 502.0                | 62.8                  | 70                         | 572.0  |
| 829+11.75        |    | 837+66.33  | WB        | 854.6       | 2                 | 1,709.2              | 213.6                 | 220                        | 1,929.2  |
| <b>TOTAL =</b>   |    |            |           |             |                   |                      |                       |                            | <b>4,073.8</b>   |
| <b>ROUND TO:</b> |    |            |           |             |                   |                      |                       |                            | <b>4,100</b>   |

YELLOW = [4100' - (60' + 60' + 70' + 70' + 220')] / 2 = 1810'  
 WHITE = 4100' - 1810' = 2290'

## PREFORMED PLASTIC PAVEMENT MARKING

| STA.             | TO | TO STA.    | DIRECTION | LENGTH (FT) | SKIP DASH LENGTH (FT) | PREFORMED PLASTIC PAVEMENT MARKING, TYPE B, LINE 4" 78003110 (FT) |
|------------------|----|------------|-----------|-------------|-----------------------|---|
| 737+00           |    | 779+38.47  | WB        | 4,238.5     | 1,059.6               | 1,060   |
| 737+00           |    | 779+38.47  | EB        | 4,238.5     | 1,059.6               | 1,060   |
| 781+58.39        |    | 829+11.75  | WB        | 4,753.4     | 1,188.3               | 1,190   |
| 837+66.33        |    | 1037+74.25 | WB        | 20,007.9    | 5,002.0               | 5,010   |
| 1040+25.25       |    | 1111+00    | EB        | 7,074.8     | 1,768.7               | 1,770   |
| 1040+25.75       |    | 1111+00    | WB        | 7,074.3     | 1,768.6               | 1,770   |
| <b>TOTAL =</b>   |    |            |           |             |                       | <b>11,860</b>   |
| <b>ROUND TO:</b> |    |            |           |             |                       | <b>12,000</b>   |

## THERMOPLASTIC PAVEMENT MARKING, LETTERS & SYMBOLS

| STA.             | LOCATION | TYPE      | AREA EACH (SQ FT) | NUMBER | THERMOPLASTIC PAVEMENT MARKING, LETTERS & SYMBOLS 78000100 (SQ FT) |
|------------------|----------|-----------|-------------------|--------|--|
| 44+70.9          | SB CH 36 | LEFT TURN | 15.6              | 1      | 15.6   |
| 45+33.23         | SB CH 36 | LEFT TURN | 15.6              | 1      | 15.6   |
| 45+95.56         | SB CH 36 | LEFT TURN | 15.6              | 1      | 15.6   |
| 46+57.89         | SB CH 36 | LEFT TURN | 15.6              | 1      | 15.6   |
| 53+35.27         | SB CH 36 | LEFT TURN | 15.6              | 1      | 15.6   |
| 53+97.60         | NB CH 36 | LEFT TURN | 15.6              | 1      | 15.6   |
| 54+59.93         | NB CH 36 | LEFT TURN | 15.6              | 1      | 15.6   |
| 55+22.26         | NB CH 36 | LEFT TURN | 15.6              | 1      | 15.6   |
| <b>TOTAL =</b>   |          |           |                   |        | <b>124.8</b>   |
| <b>ROUND TO:</b> |          |           |                   |        | <b>125</b>   |