## NOTE:

THE EXISTING STRUCTURE AT STATION 789+00 LT. CONSISTS OF A 24" R.C.C.P. WITH A MEDIAN INLET AND A PRECAST DOWNSTREAM END SECTION. THE STRUCTURE IS IN GOOD CONDITION BUT HAS THE FOLLOWING DEFICIENCIES. WHILE THE JOINT BETWEEN THE DOWNSTREAM END SECTION AND THE FIRST SECTION OF PIPE IS INTACT, THE NEXT JOINT UPSTREAM HAS SEPARATED ALLOWING SOIL TO ENTER THE STRUCTURE AND IS CAUSING A SINKHOLE IN THE FORESLOPE. ALSO, THE DOWNSTREAM END SECTION IS BROKEN.

THE PROPOSED SCOPE OF WORK IS TO REPLACE THE DOWNSTREAM END SECTION WITH A NEW PRECAST END SECTION. THE EXISTING SAFETY GRATE SHALL BE REUSED. A CONCRETE COLLAR SHALL BE USED TO CONNECT THE PROPOSED END SECTION TO THE STRUCTURE. ALSO, A CONCRETE COLLAR SHALL BE USED TO SEAL THE SEPARATED JOINT. THE COST OF EXCAVATION NECESSARY TO PERFORM THE REQUIRED WORK IS INCLUDED IN THE VARIOUS PAY ITEMS AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED.


## DRAINAGE STRUCTURE IMPROVEMENT DETAIL LOCATION #1 STA. 789 + 00



## LOC. #1STA.789+00 LT. ITEM# AND DESCRIPTION UNIT QUANTITY 25000210 Seeding, Class 2A ACRE 25000400 Nitrogen Fert. Nutr. POUND 0.81 25000500 Phosphorous Fert. Nutr. POUND 0.81 25000600 Potassium Fert. Nutr. POUND 0.81 25100115 Mulch Method 2 ACRE 0.009 28000250 Temp. Eros. Contr. Seeding POUND 0.9 54213669 Precast Flared End Section 24" EACH 1.0 54248510 Concrete Collar CUYD 0.90

EACH

1.0



¢ F.A.I. 74 1787 1788 1790+00 1790+00 1791

FILE NAME =	USER NAME = hoganbj	DESIGNED	-	ВЈМ	REVISED	-	
c:\pw_work\pwidot\hoganbj\dØ15834Ø\D57Ø	50-sht-sm struct det.dgn	DRAWN	-		REVISED	-	
	PLOT SCALE = 40.0000 '/ IN.	CHECKED	-		REVISED	-	
	PLOT DATE = 10/21/2010	DATE	-	09/23/10	REVISED	-	

STATE OI	ILLINOIS
DEPARTMENT OF	TRANSPORTATION

SCALE: 1" = 20'

					F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
					74	(57-20(1),21,22)RS-3	McLean	150	51	
LOUNTION #1 OIA. 705 T 00								CONTRACT	NO. 7	0550
	SHEET NO.	OF	SHEETS	STA.	TO STA.		TILLINOIS FED. AID PROJECT			