

**SCHEDULE OF QUANTITIES
 TABULATION OF CLASS B PATCH, 13", 15", 17"
 I-74 MAINLINE (EASTBOUND & WESTBOUND)**

STATION	LOCATION	LANE	LENGTH	WIDTH	DEPTH	TYPE II	TYPE III	TYPE IV	DOWEL BARS	SAWCUTS	TIE BARS	PAVEMENT FABRIC	
						13"-44201007		15"-44201037					
			(FT)	(FT)		15"-44201031	15"-44201035	17"-44201053	44201299	44213200	44213204	44213100	
						(SQ. YD.)	(SQ. YD.)	(SQ. YD.)	(EACH)	(FT)	(EACH)	(SQ. YD.)	
1698+69	I-74 MAINLINE	WBDL	6.0	12.0	13"	8.0			20.0	48.0			
1698+69	I-74 MAINLINE	WBPL	6.0	12.0	13"	8.0			20.0	48.0			
1080+03	I-74 MAINLINE	EBDL	12.0	12.0	15"		16.0		20.0	60.0		16.0	
1105+46	I-74 MAINLINE	EBDL	12.0	12.0	15"		16.0		20.0	60.0		16.0	
1242+31	I-74 MAINLINE	EBDL	30.0	12.0	15"			40.0	30.0	96.0	15.0	40.0	
1688+64	I-74 MAINLINE	EBDL	100.0	12.0	15"			133.3	80.0	236.0	50.0	133.3	
1889+20	I-74 MAINLINE	EBDL	30.0	12.0	15"			40.0	20.0	96.0	15.0	40.0	
1106+01	I-74 MAINLINE	WBPL	60.0	12.0	15"			80.0	50.0	156.0	30.0	80.0	
1108+64	I-74 MAINLINE	WBDL	70.0	12.0	15"			93.3	60.0	176.0	35.0	93.3	
1239+53	I-74 MAINLINE	WBDL	12.0	12.0	15"		16.0		20.0	60.0		16.0	
1239+97	I-74 MAINLINE	WBDL	50.0	12.0	15"			66.7	50.0	136.0	25.0	66.7	
1240+34	I-74 MAINLINE	WBDL	12.0	12.0	15"		16.0		20.0	60.0		16.0	
1612+08	I-74 MAINLINE	WBPL	6.0	12.0	15"	8.0			20.0	48.0			
1935+33	I-74 MAINLINE	WBDL	20.0	12.0	17"			26.7	30.0	76.0	10.0	26.7	
CLASS B PATCH TOTALS							24.0	64.0	480.0	460.0	1356.0	180.0	544.0