

PAVING SCHEDULE														
STATION	TO	STATION	RT/LT	PAVEMENT WIDTH	DISTANCE	AREA	40201000 AGGREGATE FOR TEMPORARY ACCESS	40600200 BITUMINOUS MATERIALS (PRIME COAT)	40600300 AGGREGATE (PRIME COAT)	40603310 HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	40800050 INCIDENTAL HOT-MIX ASPHALT SURFACING	42001430 BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	44000198 HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	44000200 DRIVEWAY PAVEMENT REMOVAL
				(FEET)	(FEET)	(SQ YD)	(TON)	(TON)	(TON)	(TON)	(TON)	(SQ YD)	(SQ YD)	(SQ YD)
IL 96 HANCOCK COUNTY														
34+00		34+50		24.6	50.0	137		0.2	0.3	12			137	
34+50		35+89.94		24	139.9	373		0.3	0.8	32			374	
36+17.08		37+36		24	118.9	317		0.3	0.7	27			318	
37+36		37+42		24	6.0							16		
39+17		39+23		24	6.0							16		
39+23		41+90		24	267.0	712		0.6	1.5	60			712	
41+90		42+40		24.9	50.0	138		0.2	0.3	12			139	
ENTRANCES														
35+50			LT			940.6	36	0.20			47			
36+40			RT			88.1	31	0.20			40			60
36+64			LT			60.1	21	0.20			27			41
41+62			RT			106.3	37	0.20			21			26
TOTALS							125	2.4	3.6	143.0	135	32.0	1,680.0	127.0
USE							125	3	4	143	135	32	1,680	127

RIPRAP SCHEDULE						
STATION	TO	STATION	LT/RT	AREA	28100707 STONE DUMPED RIPRAP, CLASS A4	28200200 FILTER FABRIC
				(SQ FT)	(SQ YD)	(SQ YD)
37+00		38+12	LT	3458.2	384.3	384.3
37+74.50		37+95	AR	799.7	88.9	88.9
37+00		37+93	RT	2961.5	329.1	329.1
38+32		39+25	LT	2626.4	291.9	291.9
39+15		40+00	LT	2481.2	275.7	275.7
38+32		38+84.50	AR	2048.5	227.7	227.7
38+32		39+00	RT	3014.6	335.0	335.0
TOTALS					1,932.6	1,932.6
USE					1,933	1,933

DRAINAGE SCHEDULE										
STATION	LT/RT	OFFSET	20800150 TRENCH BACKFILL	44200132 PAVEMENT PATCHING, TYPE II, 11 INCH (SQ YD)	50105220 PIPE CULVERT REMOVAL (FOOT)	542A5479 PIPE CULVERTS T1, RC-E, ERS 24" (FOOT)	54214509 PRC FLARED END SECTIONS, ERS 24" (EACH)	54215547 METAL END SECTIONS 12" (EACH)	60105000 PIPE DRAINS, CS/A ALLOY (FOOT)	60900215 TYPE C INLET BOX, STANDARD 609001 (EACH)
		(FOOT)	(CU YD)	(SQ YD)	(FOOT)	(FOOT)	(EACH)	(EACH)	(FOOT)	(EACH)
35+72.97	RT	22.00								
35+82.45										
35+91.61	LT	22.00								
37+32	LT								12	1
37+32	RT								12	1
37+32	LT	24.00						1		
37+32	RT	24.00						1		
35+82.45			5	18	50	48				
35+91.61	LT	21.75					1			
35+72.97	RT	22.48					1			
TOTALS			5	18	50	48	2	2	24	2

ESTIMATED QUANTITIES	
PAY ITEM	QUANTITY
TREE REMOVAL	1 ACRE
AGGREGATE (EROSION CONTROL)	100 TON
PERIMETER EROSION BARRIER	500 FOOT
GROUT FOR USE WITH RIPRAP	325 CU YD
GRATING AND SHAPING DITCHES	200 FOOT
EARTH EXCAVATION FOR EROSION CONTROL	50 CU YD
ROCK EXCAVATION	100 CU YD