

SUMMARY OF QUANTITIES

CODE NO.	ITEM	SP. PROV.	UNIT	80% FED. 20% STATE TOTAL QUANTITIES	80% FEDERAL 20% STATE CONSTRUCTION TYPE CODE							
					0005 ROADWAY	0011 STRUCTURE						
20100500	TREE REMOVAL, ACRES		ACRE	1.7	1.7							
20200100	EARTH EXCAVATION	•	CU YD	5185	5185							
20200500	EARTH EXCAVATION (WIDENING)	•	CU YD	184	184							
20200600	EXCAVATING AND GRADING EXISTING SHOULDER	•	UNIT	30	30							
20400800	FURNISHED EXCAVATION		CU YD	3410	3410							
25000200	SEEDING, CLASS 2		ACRE	4.00	4.00							
25000400	NITROGEN FERTILIZER NUTRIENT		POUND	360	360							
25000500	PHOSPHORUS FERTILIZER NUTRIENT		POUND	360	360							
25000600	POTASSIUM FERTILIZER NUTRIENT		POUND	360	360							
25000700	AGRICULTURAL GROUND LIMESTONE		TON	8.0	8.0							
25100115	MULCH, METHOD 2		ACRE	4.00	4.00							
25100630	EROSION CONTROL BLANKET		SQ YD	616	616							
28000250	TEMPORARY EROSION CONTROL SEEDING		POUND	800	800							
28000400	PERIMETER EROSION BARRIER		FOOT	500	500							
28000500	INLET AND PIPE PROTECTION		EACH	4	4							
28001000	AGGREGATE (EROSION CONTROL)		TON	100	100							
28100107	STONE RIPRAP, CLASS A4		SQ YD	2234		2234						
28100707	STONE DUMPED RIPRAP, CLASS A4	•	SQ YD	5323	5323							
28200200	FILTER FABRIC		SQ YD	7557	5323	2234						
31100100	SUBBASE GRANULAR MATERIAL, TYPE A		TON	137		137						
31100100	SUBBASE GRANULAR MATERIAL, TYPE A		TON	137		137						
35101400	AGGREGATE BASE COURSE, TYPE B		TON	189	189							
35600716	HOT-MIX ASPHALT BASE COURSE WIDENING, 10"		SQ YD	814	814							
40201000	AGGREGATE FOR TEMPORARY ACCESS		TON	30	30							
40600200	BITUMINOUS MATERIALS (PRIME COAT)		TON	38.5	38.5							
40600300	AGGREGATE (PRIME COAT)		TON	197	197							
40600635	LEVELING BINDER (MACHINE METHOD), N70		TON	2059	2059							
40600895	CONSTRUCTING TEST STRIP		EACH	2	2							
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT		SQ YD	87	87							
40600990	TEMPORARY RAMP	•	SQ YD	100	100							
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70		TON	1475	1475							

Rev.