

SUMMARY OF QUANTITIES

CODE NO.	ITEM	SP. PROV.	UNIT	80% FED. 20% STATE TOTAL QUANTITIES	80% FEDERAL 20% STATE CONSTRUCTION TYPE CODE					
					0005 ROADWAY	0011 STRUCTURE				
70300230	TEMPORARY PAVEMENT MARKING - LINE 5"		FOOT	114300	114300					
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"		FOOT	24	24					
70301000	WORK ZONE PAVEMENT MARKING REMOVAL		SQ FT	25112	25112					
70400100	TEMPORARY CONCRETE BARRIER		FOOT	525	525					
70400200	RELOCATE TEMPORARY CONCRETE BARRIER		FOOT	525	525					
* 78001120	PAINT PAVEMENT MARKING - LINE 5"		FOOT	55420	55420					
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER		EACH	268	268					
* 78200410	GUARDRAIL MARKERS, TYPE A		EACH	76	76					
* 78201000	TERMINAL MARKER - DIRECT APPLIED		EACH	18	18					
78300100	PAVEMENT MARKING REMOVAL		SQ FT	793	793					
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL		EACH	268	268					
Z0001900	ASBESTOS BEARING PAD REMOVAL		EACH	22		22				
Z0013798	CONSTRUCTION LAYOUT		L SUM	1	1					
Z0030260	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3		EACH	2	2					
Z0030330	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 3		EACH	2	2					
Z0046304	PIPE UNDERDRAINS FOR STRUCTURES 4"		FOOT	166		166				
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE		L SUM	1	1					
Z0073002	TEMPORARY SOIL RETENTION SYSTEM		SQ FT	560		560				
X0324744	REMOVAL OF EXISTING PRECAST CONCRETE UNITS		SQ FT	688	688					
X2070304	POROUS GRANULAR EMBANKMENT, SPECIAL		CU YD	170		170				
X4401198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH		SQ YD	42681	42681					
X4811300	AGGREGATE SHOULDERS, TYPE B (SPECIAL)		TON	1040	1040					
X6063000	CONCRETE GUTTER, TYPE B (SPECIAL)		FOOT	20	20					
X7010202	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321 (SPECIAL)		EACH	1	1					
X7050167	TEMPORARY TRAFFIC BARRIER TERMINAL, TYPE 1, SPECIAL (TANGENT)		EACH	2	2					
X7200201	WIDTH RESTRICTION SIGNING		L SUM	1	1					

*Specialty Items

FILE NAME =	USER NAME = laughtlinr1	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
c:\pwwork\pwwork\laughtlinr1\0244977.DWG	2805-shr-Summary.dgn	DRAWN -	REVISED -			685	(117,118)RS-4,119RS-1; 118B-1	HANCOCK	101	6	
	PLOT SCALE = 100.0000' / 1"	CHECKED -	REVISED -			CONTRACT NO. 72B05					
	PLOT DATE = Nov-03-2010 10:19:49AM	DATE -	REVISED -			FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT					
				SCALE: none	SHEET NO. 4 OF 4 SHEETS	STA. TO STA.					