

PAINT PAVEMENT MARKING - LINE 5''

78001120

STATION TO STATION	SIDE	DESCRIPTION	WHITE	YELLOW
			FOOT	
FAP 685 (IL 9)				
1094+97.45	1262+55.89	LT	EDGE LINE	16758.4
1263+31.52	1269+77.10	LT	EDGE LINE	645.6
0+00.00	0+50.00	LT	EDGE LINE	50.0
1094+97.45	1262+55.89	RT	EDGE LINE	16758.4
1263+31.52	1269+77.10	RT	EDGE LINE	645.6
0+00.00	0+50.00	RT	EDGE LINE	50.0
1094+97.45	1173+00.00	CL	SKIP-DASH	1960.0
1205+00.00	1221+50.00	CL	SKIP-DASH	420.0
1249+00.00	1262+55.89	CL	SKIP-DASH	340.0
1263+31.52	1269+77.10	CL	SKIP-DASH	170.0
0+00.00	0+50.00	CL	SKIP-DASH	20.0
1104+50.00	1112+00.00	RT CL	NO-PASSING	750.0
1114+50.00	1122+00.00	LT CL	NO-PASSING	750.0
1163+50.00	1205+00.00	RT CL	NO-PASSING	4150.0
1173+00.00	1217+00.00	LT CL	NO-PASSING	4400.0
1221+50.00	1258+50.00	RT CL	NO-PASSING	3700.0
1221+50.00	1249+00.00	LT CL	NO-PASSING	2750.0
1258+50.00	1262+55.89	LT CL	NO-PASSING	405.9
1263+31.52	1269+77.10	LT CL	NO-PASSING	645.6
0+00.00	0+50.00	LT CL	NO-PASSING	50.0
TOTALS			34908.0	20511.5
USE			55420	

FURNISHING AND ERECTING ROW MARKERS

66600105

STATION	SIDE	OFFSET	EACH
FAP 685 (IL 9)			
1212+50.00	LT	40.00	1
1213+00.00	LT	70.00	1
1219+00.00	LT	100.00	1
1222+00.00	LT	100.00	1
1223+10.10	LT	50.00	1
1224+50.00	LT	40.00	1
1212+50.00	RT	40.00	1
1213+00.00	RT	75.00	1
1218+00.00	RT	100.00	1
1223+10.10	RT	100.00	1
1224+00.00	RT	100.00	1
1224+50.00	RT	70.00	1
TOTAL			12

RAISED REFLECTIVE PAVEMENT MARKERS

78100100

STATION TO STATION	SIDE	MAXIMUM SPACING	2-WAY AMBER	
			EACH	
FAP 685 (IL 9)				
1094+97.45	1107+33.42	CL	80	16
1107+33.42	1114+07.85	CL	40	17
1114+07.85	1171+39.31	CL	80	72
1171+39.31	1201+48.90	CL	40	76
1201+48.90	1262+55.89	CL	80	77
1263+31.52	1269+77.10	CL	80	9
0+00.00	0+50.00	CL	80	1
TOTAL			268	

TEMPORARY CONCRETE BARRIER

70400100

STATION TO STATION	SIDE	FOOT
FAP 685 (IL 9) - STAGE 2		
1216+87.9	1222+12.1	LT & RT
TOTAL		525

RELOCATE TEMPORARY CONCRETE BARRIER

70400200

STATION TO STATION	SIDE	FOOT
FAP 685 (IL 9) - STAGE 3		
1216+87.9	1222+12.1	LT & RT
TOTAL		525

FILE NAME =	USER NAME = laughlinc1	DESIGNED -	REVISED -
ct:\pwork\pwork\laughlinc1\0224497\0672805-sh-t-Schedules.dgn		DRAWN -	REVISED -
	PLOT SCALE = 100.0000' / in.	CHECKED -	REVISED -
	PLOT DATE = Nov-03-2010 11:31:18AM	DATE -	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES			
SCALE: none	SHEET NO. 5 OF 5 SHEETS	STA.	TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
685	(117,118)RS-4,119RS-1; 118B-1	HANCOCK	101	11
CONTRACT NO. 72B05				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				