

LEGEND FOR STORM WATER POLLUTION PREVENTION PLAN

ITEM	SYMBOL
AGGREGATE (EROSION CONTROL) [STONE DUMPED RIPRAP DITCH CHECKS: Height = 0.6m (2')]	—
TEMPORARY DITCH CHECKS	\$-
INLET PIPE PROTECTION (I&PP)	\Leftrightarrow
EROSION CONTROL FENCE	~~~
EARTH EXCAVATION FOR EROSION CONTROL (SEDIMENT BASINS)	0
PRESERVE EXISTING TREES, WOODLANDS, AND UNDERSTORY (OUTSIDE CONSTRUCTION LIMITS)	
ITEM PLACED AT BEGINNING OF CONSTRUCTION (Requirement)	* [ITEM] *
ITEM PLACED AS DIRECTED BY ENGINEER (When required by situation)	ITEM
DIRECTION OF OVERLAND FLOW	

GENERAL NOTES:

All items shall be constructed as shown on this sheet, on Standard 280001, and as directed by the Engineer.

The symbology on the STORM WATER POLLUTION PREVENTION PLAN sheets does not represent the size or quantity of bales, for number of bales refer to details and notes shown on this sheet and/or as directed by the Engineer.

THE CONTRACTOR SHALL INSTALL DITCH CHECKS AS DIRECTED BY THE ENGINEER. IF THE ENGINEER ELECTS TO UTILIZE FLUSH RIPRAP DITCH CHECKS IN LIEU OF TEMPORARY DITCH CHECKS AS SHOWN ON THE FOLLOWING PLAN SHEETS, THE SPACING SHOULD BE DOUBLED.

	FILE NAME =	USER NAME = laughlinrl	DESIGNED -	REVISED -	
c:\pw_work\pwidot\laughlinrl\d0215213\D672B98-sht-eros.dgn		DRAWN -	REVISED -	İ	
		PLOT SCALE = 40.0000 '/ in.	CHECKED -	REVISED -	İ
		PLOT DATE = Oct-14-2010 09:42:55AM	DATE -	REVISED -	

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCALE:

STORM WATER POLLUTION PREVENTION PLAN		SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		107B-1	ADAMS	86	31
			CONTRACT	NO.	72B98
SHEET NO. OF SHEETS STA. TO STA.		ILLINOIS FED. AID PROJECT			