

80% FED.
20% STATE

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE
CODE NO	ITEM	UNIT		0005
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	141	141
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	10385	10385
40600300	AGGREGATE (PRIME COAT)	TON	202	202
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	3779	3779
40600895	CONSTRUCTING TEST STRIP	EACH	1	1
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	268	268
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	137	137
40600990	TEMPORARY RAMP	SQ YD	351	351
40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	3781	3781
40603520	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N90	TON	3319	3319
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	164	164
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	12042	12042
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	204	204
44022029	PARTIAL DEPTH REMOVAL 3"	SQ YD	257	257
44201749	CLASS D PATCHES, TYPE I, 9 INCH	SQ YD	112	112
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	1156	1156
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	88	88
44201789	CLASS D PATCHES, TYPE II, 12 INCH	SQ YD	427	427
44201794	CLASS D PATCHES, TYPE III, 12 INCH	SQ YD	105	105
44201803	CLASS D PATCHES, TYPE II, 13 INCH	SQ YD	330	330
44201807	CLASS D PATCHES, TYPE III, 13 INCH	SQ YD	303	303
44201809	CLASS D PATCHES, TYPE IV, 13 INCH	SQ YD	155	155
44201815	CLASS D PATCHES, TYPE II, 14 INCH	SQ YD	43	43
44201821	CLASS D PATCHES, TYPE IV, 14 INCH	SQ YD	29	29
48101200	AGGREGATE SHOULDERS, TYPE B	TON	1874	1874
48203004	HOT-MIX ASPHALT SHOULDERS, 1 3/4"	SQ YD	15925	15925
48203007	HOT-MIX ASPHALT SHOULDERS, 2 1/2"	SQ YD	3038	3038
60250600	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 3 FRAME AND GRATE	EACH	23	23
60253200	CATCH BASINS TO BE RECONSTRUCTED WITH NEW TYPE 3 FRAME AND GRATE	EACH	2	2

80% FED.
20% STATE

SUMMARY OF QUANTITIES (Cont'd)			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE
CODE NO	ITEM	UNIT		0005
60605100	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6, 24 (ABUTTING EXISTING PAVEMENT)	FOOT	204	204
64200105	SHOULDER RUMBLE STRIPS	FOOT	48619	48619
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	4	4
67100100	MOBILIZATION	L SUM	1	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	1
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	11411	11411
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	31	31
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	62759	62759
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	147	147
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	563	563
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	32911	32911
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	56686	56686
* 78001150	PAINT PAVEMENT MARKING - LINE 12"	FOOT	154	154
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	447	447
X4060995	TEMPORARY RAMP, SPECIAL	SQ YD	657	657
X4401198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	56112	56112
X4421000	PARTIAL DEPTH PATCHING	TON	62	62
* X7800605	URETHANE PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	31	31
* X7800610	URETHANE PAVEMENT MARKING - LINE 4"	FOOT	6073	6073
* X7800630	URETHANE PAVEMENT MARKING - LINE 6"	FOOT	147	147
* X7800650	URETHANE PAVEMENT MARKING - LINE 12"	FOOT	409	409
Z0012500	CONCRETE CURB REPAIR	FOOT	33	33
Z0023602	GRANULAR CULVERT BACKFILL	CU YD	50	50
Z0070100	SURVEY MONUMENT COVER ASSEMBLY	EACH	12	12

*Specialty Items

FILE NAME =	USER NAME = #USER#	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.P. RTE. =	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
#FILEL#		DRAWN -	REVISED -		SCALE: NA	SHEET NO. 1 OF 1 SHEETS	STA.	TO STA.	325	9RS-2, IORS-4	SHELBY	46	3
	PLOT SCALE = #SCALE#	CHECKED -	REVISED -		CONTRACT NO. 74460								
	PLOT DATE = #DATE#	DATE -	REVISED -		ILLINOIS FED. AID PROJECT								