#### If you plan to submit a bid directly to the Department of Transportation

#### **PREQUALIFICATION**

Any contractor who desires to become pre-qualified to bid on work advertised by IDOT must submit the properly completed pre-qualification forms to the Bureau of Construction no later that 4:30 p.m. prevailing time twenty-one days prior to the letting of interest. This pre-qualification requirement applies to first time contractors, contractors renewing expired ratings, contractors maintaining continuous pre-qualification or contractors requesting revised ratings. To be eligible to bid, existing pre-qualification ratings must be effective through the date of letting.

#### **REQUESTS FOR AUTHORIZATION TO BID**

Contractors wanting to bid on items included in a particular letting must submit the properly completed "Request for Authorization to Bid/or Not For Bid Status" (BDE 124INT) and the ORIGINAL "Affidavit of Availability" (BC 57) to the proper office no later than 4:30 p.m. prevailing time, three (3) days prior to the letting date.

#### WHO CAN BID?

Bids will be accepted from only those companies that request and receive written **Authorization to Bid** from IDOT's Central Bureau of Construction.

WHAT CONSTITUTES WRITTEN AUTHORIZATION TO BID?: When a prospective prime bidder submits a "Request for Authorization to Bid/or Not For Bid Status" (BDE 124INT) he/she must indicate at that time which items are being requested For Bidding purposes. Only those items requested For Bidding will be analyzed. After the request has been analyzed, the bidder will be issued an Authorization to Bid or Not for Bid Report, approved by the Central Bureau of Construction that indicates which items have been approved For Bidding. If Authorization to Bid cannot be approved, the Authorization to Bid or Not for Bid Report will indicate the reason for denial.

**ABOUT AUTHORIZATION TO BID:** Firms that have not received an authorization form within a reasonable time of complete and correct original document submittal should contact the department as to status. This is critical in the week before the letting. These documents must be received three days before the letting date. Firms unsure as to authorization status should call the Prequalification Section of the Bureau of Construction at the number listed at the end of these instructions.

**ADDENDA AND REVISIONS:** It is the contractor's responsibility to determine which, if any, addenda or revisions pertain to any project they may be bidding. Failure to incorporate all relevant addenda or revisions may cause the bid to be declared unacceptable.

Each addendum will be placed with the contract number. Addenda and revisions will also be placed on the Addendum/Revision Checklist and each subscription service subscriber will be notified by e-mail of each addendum and revision issued.

The Internet is the Department's primary way of doing business. The subscription server e-mails are an added courtesy the Department provides. It is suggested that bidders check IDOT's website at <a href="http://www.dot.il.gov/desenv/delett.html">http://www.dot.il.gov/desenv/delett.html</a> before submitting final bid information.

#### IDOT IS NOT RESPONSIBLE FOR ANY E-MAIL FAILURES.

Addenda Questions may be directed to the Contracts Office at (217)782-7806 or D&Econtracts@dot.il.gov

Technical Questions about downloading these files may be directed to Tim Garman (217)524-1642 or Timothy.Garman@illinois.gov.

WHAT MUST BE INCLUDED WHEN BIDS ARE SUBMITTED?: Bidders need not return the entire proposal when bids are submitted. That portion of the proposal that must be returned includes the following:

- 1. All documents from the Proposal Cover Sheet through the Proposal Bid Bond
- 2. Other special documentation and/or information that may be required by the contract special provisions

All proposal documents, including Proposal Guaranty Checks or Proposal Bid Bonds, should be stapled together to prevent loss when bids are processed by IDOT personnel.

**ABOUT SUBMITTING BIDS**: It is recommended that bidders deliver bids in person to insure they arrive at the proper location prior to the time specified for the receipt of bids. Any bid received at the place of letting after the time specified will not be accepted.

#### WHO SHOULD BE CALLED IF ASSISTANCE IS NEEDED?

Questions Regarding	Call
Prequalification and/or Authorization to Bid	217/782-3413
Preparation and submittal of bids	217/782-7806
Mailing of plans and proposals	217/782-7806

#### ADDENDUMS AND REVISIONS TO THE PROPOSAL FORMS

Planholders should verify that they have received and incorporated any addendum and/or revision prior to submitting their bid. Failure by the bidder to include and addendum or revision could result in a bid being rejected as irregular.

89

KEI OKK WIIII BIB
Proposal Submitted By
Name
Address
City

## Letting January 21, 2011

#### NOTICE TO PROSPECTIVE BIDDERS

This proposal can be used for bidding purposes by only those companies that request and receive written AUTHORIZATION TO BID from IDOT's Central Bureau of Construction. (SEE INSTRUCTIONS ON THE INSIDE OF COVER)

## Notice to Bidders, Specifications, Proposal, Contract and Contract Bond



Springfield, Illinois 62764

Contract No. 74503 CUMBERLAND-CLARK Counties Section D7 PAVT PRSV 2011-2 District 7 Construction Funds Route FAI 70

PLEASE MARK THE APPROPRIATE BOX BELOW:
☐ A <u>Bid Bond</u> is included.
A Cashier's Check or a Certified Check is included.

Plans Included Herein

Prepared by

S

Checked by
(Printed by authority of the State of Illinois)

BIDDERS NEED NOT RETURN THE ENTIRE PROPOSAL (See instructions inside front cover)

#### **INSTRUCTIONS**

**ABOUT IDOT PROPOSALS**: All proposals issued by IDOT are potential bidding proposals. Each proposal contains all Certifications and Affidavits, a Proposal Signature Sheet and a Proposal Bid Bond required for Prime Contractors to submit a bid after written **Authorization to Bid** has been issued by IDOT's Central Bureau of Construction. In addition, this proposal contains new statutory requirements applicable to the use of subcontractors and, in particular, includes the <u>State Required Ethical Standards Governing Subcontractors</u> to be signed and incorporated into all subcontracts.

WHO CAN BID?: Bids will be accepted from only those companies that request and receive written Authorization to Bid from IDOT's Central Bureau of Construction. To request authorization, a potential bidder <u>must complete and submit Part B of the Request for Authorization to Bid/or Not For Bid Status form (BDE 124 INT) and submit an original Affidavit of Availability (BC 57).</u>

WHAT CONSTITUTES WRITTEN AUTHORIZATION TO BID?: When a prospective prime bidder submits a "Authorization to Bid or Not for Bid" form, he/she must indicate at that time which items are being requested For Bidding purposes. Only those items requested For Bidding will be analyzed. After the request has been analyzed, the bidder will be issued a Authorization to Bid or Not for Bid Report, approved by the Central Bureau of Construction, that indicates which items have been approved For Bidding. If Authorization to Bid cannot be approved, the Authorization to Bid or Not for Bid Report will indicate the reason for denial. If a contractor has requested to bid but has not received a Authorization to Bid or Not for Bid Report, they should contact the Central Bureau of Construction in advance of the letting date.

**WHAT MUST BE INCLUDED WHEN BIDS ARE SUBMITTED**?: Bidders need not return the entire proposal when bids are submitted. That portion of the proposal that must be returned includes the following:

- 1. All documents from the Proposal Cover Sheet through the Proposal Bid Bond
- 2. Other special documentation and/or information that may be required by the contract special provisions

All proposal documents, including Proposal Guaranty Checks or Proposal Bid Bonds, should be stapled together to prevent loss when bids are processed by IDOT personnel.

**ABOUT SUBMITTING BIDS**: It is recommended that bidders deliver bids in person to insure they arrive at the proper location prior to the time specified for the receipt of bids. Any bid received at the place of letting after the time specified will not be accepted.

Call

#### WHO SHOULD BE CALLED IF ASSISTANCE IS NEEDED?

**Questions Regarding** 

Prequalification and/or Authorization to Bid	217/782-3413

Preparation and submittal of bids 217/782-7806



**PROPOSAL** 

1. Proposal of		
1. 1 Toposal of		
Taxpayer Identification Number (Mandate	ory)	a

for the improvement identified and advertised for bids in the Invitation for Bids as:

Contract No. 74503 CUMBERLAND-CLARK Counties Section D7 PAVT PRSV 2011-2 Route FAI 70 District 7 Construction Funds

TO THE DEPARTMENT OF TRANSPORTATION

Microsurfacing of 2 ft. of the existing pavement centerline and replacement of pavement markings along I-70 from the Effingham/Cumberland County line to 0.3 mile west of Martinsville.

2. The undersigned bidder will furnish all labor, material and equipment to complete the above described project in a good and workmanlike manner as provided in the contract documents provided by the Department of Transportation. This proposal will become part of the contract and the terms and conditions contained in the contract documents shall govern performance and payments.

- 3. **ASSURANCE OF EXAMINATION AND INSPECTION/WAIVER.** The undersigned further declares that he/she has carefully examined the proposal, plans, specifications, addenda, form of contract and contract bond, and special provisions, and that he/she has inspected in detail the site of the proposed work, and that he/she has familiarized themselves with all of the local conditions affecting the contract and the detailed requirements of construction, and understands that in making this proposal he/she waives all right to plead any misunderstanding regarding the same.
- 4. **EXECUTION OF CONTRACT AND CONTRACT BOND.** The undersigned further agrees to execute a contract for this work and present the same to the department within fifteen (15) days after the contract has been mailed to him/her. The undersigned further agrees that he/she and his/her surety will execute and present within fifteen (15) days after the contract has been mailed to him/her contract bond satisfactory to and in the form prescribed by the Department of Transportation, in the penal sum of the full amount of the contract, guaranteeing the faithful performance of the work in accordance with the terms of the contract.
- 5. **PROPOSAL GUARANTY.** Accompanying this proposal is either a bid bond on the department form, executed by a corporate surety company satisfactory to the department, or a proposal guaranty check consisting of a bank cashier's check or a properly certified check for not less than 5 per cent of the amount bid or for the amount specified in the following schedule:

<u>A</u>	mount o	of Bid	Proposal <u>Guaranty</u>	<u>An</u>	nount c	of Bid	Proposal <u>Guaranty</u>
Up to		\$5,000	\$150	\$2,000,000	to	\$3,000,000	\$100,000
\$5,000	to	\$10,000	\$300	\$3,000,000	to	\$5,000,000	\$150,000
\$10,000	to	\$50,000	\$1,000	\$5,000,000	to	\$7,500,000	\$250,000
\$50,000	to	\$100,000	\$3,000	\$7,500,000	to	\$10,000,000	\$400,000
\$100,000	to	\$150,000	\$5,000	\$10,000,000	to	\$15,000,000	\$500,000
\$150,000	to	\$250,000	\$7,500	\$15,000,000	to	\$20,000,000	\$600,000
\$250,000	to	\$500,000	\$12,500	\$20,000,000	to	\$25,000,000	\$700,000
\$500,000	to	\$1,000,000	\$25,000	\$25,000,000	to	\$30,000,000	\$800,000
\$1,000,000	to	\$1,500,000	\$50,000	\$30,000,000	to	\$35,000,000	\$900,000
\$1,500,000	to	\$2,000,000	\$75,000	over		\$35,000,000	.\$1,000,000

Bank cashier's checks or properly certified checks accompanying proposals shall be made payable to the Treasurer, State of Illinois, when the state is awarding authority; the county treasurer, when a county is the awarding authority; or the city, village, or town treasurer, when a city, village, or town is the awarding authority.

If a combination bid is submitted, the proposal guaranties which accompany the individual proposals making up the combination will be considered as also covering the combination bid.

The amount of the proposal guaranty check is \_\_\_\_\_\_\_\$( ). If this proposal is accepted and the undersigned shall fail to execute a contract bond as required herein, it is hereby agreed that the amount of the proposal guaranty shall become the property of the State of Illinois, and shall be considered as payment of damages due to delay and other causes suffered by the State because of the failure to execute said contract and contract bond; otherwise, the bid bond shall become void or the proposal guaranty check shall be returned to the undersigned.

#### Attach Cashier's Check or Certified Check Here

In the event that one proposal guaranty check is intended to cover two or more proposals, the amount must be equal to the sum of the proposal guaranties which would be required for each individual proposal. If the guaranty check is placed in another proposal, state below where it may be found.

The proposal guaranty check will be found in the proposal for:	Item
--	------

Section No.

County

Mark the proposal cover sheet as to the type of proposal guaranty submitted.

-3-

con pro	mbination bid sportion to the bi	ne will perform the work in accordance with the require pecified in the schedule below, and that the combinati d submitted for the same. If an error is found to exist in a combination, the combination bid shall be corrected a	on bid shall be prorated against each the gross sum bid for one or more of the	section
		combination bid is submitted, the schedule below muing the combination.	ust be completed in each proposal	
	If alterna	ate bids are submitted for one or more of the sections ation bid must be submitted for each alternate.	s comprising the combination, a	
		Schedule of Combination Bids		
Combii	nation	Sections Included in Combination	Combination Bid Dollars Cer	nte
	y	Cooline meladed in Combination	Donard Gor	
sch all e sch is a con con	nedule of prices extensions and a nedule are appro an error in the ex ntract will be man ntract. The sche	RICES. The undersigned bidder submits herewith, in according to the items of work for which bids are sought. The unit summations have been made. The bidder understands to eximate and are provided for the purpose of obtaining a gottension of the unit prices, the unit prices shall govern. Pade only for actual quantities of work performed and accepteduled quantities of work to be done and materials to be find elsewhere in the contract.	prices bid are in U.S. dollars and cents, a hat the quantities appearing in the bid ross sum for the comparison of bids. If the ayment to the contractor awarded the oted or materials furnished according to the	and nere ne
pro	vides that a pe	OO BUSINESS IN ILLINOIS. Section 20-43 of the Illierson (other than an individual acting as a sole propriete of Illinois prior to submitting the bid.		
. The	e services of a	subcontractor will or may be used.		
		Yes  No		
	For known sub	ocontractors with subcontracts with an annual value of mo	ore than \$25.000. the contract shall includ	ما

# ILLINOIS DEPARTMENT OF TRANSPORTATION SCHEDULE OF PRICES CONTRACT 74503 NUMBER -

State Job # - C-97-014-11

PPS NBR - 7-50381-0000

County Name - CLARK- CUMBERLAND-

Code - 23 - 35 - District - 7 - 7 -

Section Number - D7 PAVT PRSV 2011-2

Project Number	Route
	FAI 70

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
X0326240		EACH	1.000				
X7800610	URETH PAVT MK LINE 4	FOOT	75,334.000				
Z0033650	LONG JOINT REPAIR	TON	47.000				
Z0063805	MICRO-SURF SINGL TYP2	SQ YD	66,964.000				
40600100	BIT MATLS PR CT	GALLON	6,697.000				
67100100	MOBILIZATION	L SUM	1.000				
70100700	TRAF CONT-PROT 701406	L SUM	1.000				
70300100	SHORT TERM PAVT MKING	FOOT	30,134.000				
70301000	WORK ZONE PAVT MK REM	SQ FT	10,045.000				
78100100	RAISED REFL PAVT MKR	EACH	7,534.000				
78300100	PAVT MARKING REMOVAL	SQ FT	25,111.000				
78300200	RAISED REF PVT MK REM	EACH	3,767.000				

CONTRACT NUMBER	74503	
THIS IS THE TOTAL BID		\$

#### NOTES:

- 1. Each PAY ITEM should have a UNIT PRICE and a TOTAL PRICE.
- 2. The UNIT PRICE shall govern if no TOTAL PRICE is shown or if there is a discrepancy between the product of the UNIT PRICE multiplied by the QUANTITY.
- 3. If a UNIT PRICE is omitted, the TOTAL PRICE will be divided by the QUANTITY in order to establish a UNIT PRICE.
- 4. A bid may be declared UNACCEPTABLE if neither a unit price nor a total price is shown.

# STATE REQUIRED ETHICAL STANDARDS GOVERNING CONTRACT PROCUREMENT: ASSURANCES, CERTIFICATIONS AND DISCLOSURES

#### I. GENERAL

- **A.** Article 50 of the Illinois Procurement Code establishes the duty of all State chief procurement officers, State purchasing officers, and their designees to maximize the value of the expenditure of public moneys in procuring goods, services, and contracts for the State of Illinois and to act in a manner that maintains the integrity and public trust of State government. In discharging this duty, they are charged by law to use all available information, reasonable efforts, and reasonable actions to protect, safeguard, and maintain the procurement process of the State of Illinois.
- **B.** In order to comply with the provisions of Article 50 and to carry out the duty established therein, all bidders are to adhere to ethical standards established for the procurement process, and to make such assurances, disclosures and certifications required by law. Except as otherwise required in subsection III, paragraphs J-M, by execution of the Proposal Signature Sheet, the bidder indicates that each of the mandated assurances have been read and understood, that each certification is made and understood, and that each disclosure requirement has been understood and completed.
- **C.** In addition to all other remedies provided by law, failure to comply with any assurance, failure to make any disclosure or the making of a false certification shall be grounds for the chief procurement officer to void the contract, or subcontract, and may result in the suspension or debarment of the bidder or subcontractor.

#### **II. ASSURANCES**

The assurances hereinafter made by the bidder are each a material representation of fact upon which reliance is placed should the Department enter into the contract with the bidder.

#### A. Conflicts of Interest

1. The Illinois Procurement Code provides in pertinent part:

Section 50-13. Conflicts of Interest.

- (a) Prohibition. It is unlawful for any person holding an elective office in this State, holding a seat in the General Assembly, or appointed to or employed in any of the offices or agencies of state government and who receives compensation for such employment in excess of 60% of the salary of the Governor of the State of Illinois, or who is an officer or employee of the Capital Development Board or the Illinois Toll Highway Authority, or who is the spouse or minor child of any such person to have or acquire any contract, or any direct pecuniary interest in any contract therein, whether for stationery, printing, paper, or any services, materials, or supplies, that will be wholly or partially satisfied by the payment of funds appropriated by the General Assembly of the State of Illinois or in any contract of the Capital Development Board or the Illinois Toll Highway authority.
- (b) Interests. It is unlawful for any firm, partnership, association or corporation, in which any person listed in subsection (a) is entitled to receive (i) more than 7 1/2% of the total distributable income or (ii) an amount in excess of the salary of the Governor, to have or acquire any such contract or direct pecuniary interest therein.
- (c) Combined interests. It is unlawful for any firm, partnership, association, or corporation, in which any person listed in subsection (a) together with his or her spouse or minor children is entitled to receive (i) more than 15%, in the aggregate, of the total distributable income or (ii) an amount in excess of 2 times the salary of the Governor, to have or acquire any such contract or direct pecuniary interest therein.
- (d) Securities. Nothing in this Section invalidates the provisions of any bond or other security previously offered or to be offered for sale or sold by or for the State of Illinois.
- (e) Prior interests. This Section does not affect the validity of any contract made between the State and an officer or employee of the State or member of the General Assembly, his or her spouse, minor child or any combination of those persons if that contract was in existence before his or her election or employment as an officer, member, or employee. The contract is voidable, however, if it cannot be completed within 365 days after the officer, member, or employee takes office or is employed.

The current salary of the Governor is \$177,412.00. Sixty percent of the salary is \$106,447.20.

2. The bidder assures the Department that the award and execution of the contract would not cause a violation of Section 50-13, or that an effective exemption has been issued by the Board of Ethics to any individual subject to the Section 50-13 prohibitions pursuant to the provisions of Section 50-20 of the Code and Executive Order Number 3 (1998). Information concerning the exemption process is available from the Department upon request.

#### B. Negotiations

1. The Illinois Procurement Code provides in pertinent part:

Section 50-15. Negotiations.

- (a) It is unlawful for any person employed in or on a continual contractual relationship with any of the offices or agencies of State government to participate in contract negotiations on behalf of that office or agency with any firm, partnership, association, or corporation with whom that person has a contract for future employment or is negotiating concerning possible future employment.
- 2. The bidder assures the Department that the award and execution of the contract would not cause a violation of Section 50-15, and that the bidder has no knowledge of any facts relevant to the kinds of acts prohibited therein.

#### C. Inducements

1. The Illinois Procurement Code provides:

Section 50-25. Inducement. Any person who offers or pays any money or other valuable thing to any person to induce him or her not to bid for a State contract or as recompense for not having bid on a State contract is guilty of a Class 4 felony. Any person who accepts any money or other valuable thing for not bidding for a State contract or who withholds a bid in consideration of the promise for the payment of money or other valuable thing is guilty of a Class 4 felony.

2. The bidder assures the Department that the award and execution of the contract would not cause a violation of Section 50-25, and that the bidder has no knowledge of any facts relevant to the kinds of acts prohibited therein.

#### D. Revolving Door Prohibition

1. The Illinois Procurement Code provides:

Section 50-30. Revolving door prohibition. Chief procurement officers, State purchasing officers, procurement compliance monitors, their designees whose principal duties are directly related to State procurement, and executive officers confirmed by the Senate are expressly prohibited for a period of 2 years after terminating an affected position from engaging in any procurement activity relating to the State agency most recently employing them in an affected position for a period of at least 6 months. The prohibition includes, but is not limited to: lobbying the procurement process; specifying; bidding; proposing bid, proposal, or contract documents; on their own behalf or on behalf of any firm, partnership, association, or corporation. This Section applies only to persons who terminate an affected position on or after January 15, 1999.

2. The bidder assures the Department that the award and execution of the contract would not cause a violation of Section 50-30, and that the bidder has no knowledge of any facts relevant to the kinds of acts prohibited therein.

#### E. Reporting Anticompetitive Practices

1. The Illinois Procurement Code provides:

Section 50-40. Reporting anticompetitive practices. When, for any reason, any vendor, bidder, contractor, chief procurement officer, State purchasing officer, designee, elected official, or State employee suspects collusion or other anticompetitive practice among any bidders, offerors, contractors, proposers, or employees of the State, a notice of the relevant facts shall be transmitted to the Attorney General and the chief procurement officer.

2. The bidder assures the Department that it has not failed to report any relevant facts concerning the practices addressed in Section 50-40 which may involve the contract for which the bid is submitted.

#### F. Confidentiality

1. The Illinois Procurement Code provides:

Section 50-45. Confidentiality. Any chief procurement officer, State purchasing officer, designee, or executive officer who willfully uses or allows the use of specifications, competitive bid documents, proprietary competitive information, proposals, contracts, or selection information to compromise the fairness or integrity of the procurement, bidding, or contract process shall be subject to immediate dismissal, regardless of the Personnel code, any contract, or any collective bargaining agreement, and may in addition be subject to criminal prosecution.

2. The bidder assures the Department that it has no knowledge of any fact relevant to the practices addressed in Section 50-45 which may involve the contract for which the bid is submitted.

#### G. Insider Information

1. The Illinois Procurement Act provides:

Section 50-50. Insider information. It is unlawful for any current or former elected or appointed State official or State employee to knowingly use confidential information available only by virtue of that office or employment for actual or anticipated gain for themselves or another person.

2. The bidder assures the Department that it has no knowledge of any facts relevant to the practices addressed in Section 50-50 which may involve the contract for which the bid is submitted.

#### **III. CERTIFICATIONS**

The certifications hereinafter made by the bidder are each a material representation of fact upon which reliance is placed should the Department enter into the contract with the bidder. Section 50-2 of the Illinois Procurement Code provides that every person that has entered into a multi-year contract and every subcontractor with a multi-year subcontract shall certify, by July 1 of each fiscal year covered by the contract after the initial fiscal year, to the responsible chief procurement officer whether it continues to satisfy the requirements of Article 50 pertaining to the eligibility for a contract award. If a contractor or subcontractor is not able to truthfully certify that it continues to meet all requirements, it shall provide with its certification a detailed explanation of the circumstances leading to the change in certification status. A contractor or subcontractor that makes a false statement material to any given certification required under Article 50 is, in addition to any other penalties or consequences prescribed by law, subject to liability under the Whistleblower Reward and Protection Act for submission of a false claim.

#### A. Bribery

1. The Illinois Procurement Code provides:

Section 50-5. Bribery.

- (a) Prohibition. No person or business shall be awarded a contract or subcontract under this Code who:
  - (1) has been convicted under the laws of Illinois or any other state of bribery or attempting to bribe an officer or employee of the State of Illinois or any other state in that officer's or employee's official capacity; or
  - (2) has made an admission of guilt of that conduct that is a matter of record but has not been prosecuted for that conduct.
- (b) Businesses. No business shall be barred from contracting with any unit of State or local government, or subcontracting under such a contract, as a result of a conviction under this Section of any employee or agent of the business if the employee or agent is no longer employed by the business and:
  - (1) the business has been finally adjudicated not guilty; or
  - (2) the business demonstrates to the governmental entity with which it seeks to contract, or which is signatory to the contract which the subcontract relates, and that entity finds that the commission of the offense was not authorized, requested, commanded, or performed by a director, officer, or high managerial agent on behalf of the business as provided in paragraph (2) of subsection (a) of Section 5-4 of the Criminal Code of 1961.
- (c) Conduct on behalf of business. For purposes of this Section, when an official, agent, or employee of a business committed the bribery or attempted bribery on behalf of the business and in accordance with the direction or authorization of a responsible official of the business, the business shall be chargeable with the conduct.
- (d) Certification. Every bid submitted to and contract executed by the State, and every subcontract subject to Section 20-120 of the Procurement Code shall contain a certification by the contractor or the subcontractor, respectively, that the contractor or subcontractor is not barred from being awarded a contract or subcontract under this Section and acknowledges that the chief procurement officer may declare the related contract void if any certifications required by this Section are false. A contractor who makes a false statement, material to the certification, commits a Class 3 felony.
- 2. The contractor or subcontractor certifies that it is not barred from being awarded a contract under Section 50.5.

#### B. Felons

1. The Illinois Procurement Code provides:

Section 50-10. Felons. Unless otherwise provided, no person or business convicted of a felony shall do business with the State of Illinois or any State agency, or enter into a subcontract, from the date of conviction until 5 years after the date of completion of the sentence for that felony, unless no person held responsible by a prosecutorial office for the facts upon which the conviction was based continues to have any involvement with the business.

2. Certification. Every bid submitted to and contract executed by the State and every subcontract subject to Section 20-120 of the Procurement Code shall contain a certification by the bidder or contractor or subcontractor, respectively, that the bidder, contractor, or subcontractor is not barred from being awarded a contract or subcontract under this Section and acknowledges that the chief procurement officer may declare the related contract void if any of the certifications required by this Section are false.

#### C. <u>Debt Delinquency</u>

1. The Illinois Procurement Code provides:

Section 50-11 and 50-12. Debt Delinquency.

The contractor or bidder or subcontractor, respectively, certifies that it, or any affiliate, is not barred from being awarded a contract or subcontract under the Procurement Code. Section 50-11 prohibits a person from entering into a contract with a State agency, or entering into a subcontract, if it knows or should know that it, or any affiliate, is delinquent in the payment of any debt to the State as defined by the Debt Collection Board. Section 50-12 prohibits a person from entering into a contract with a State agency, or entering into a subcontract, if it, or any affiliate, has failed to collect and remit Illinois Use Tax on all sales of tangible personal property into the State of Illinois in accordance with the provisions of the Illinois Use Tax Act. The bidder or contractor or subcontractor, respectively, further acknowledges that the chief procurement officer may declare the related contract void if this certification is false or if the bidder, contractor, or subcontractor, or any affiliate, is determined to be delinquent in the payment of any debt to the State during the term of the contract.

#### D. Prohibited Bidders, Contractors and Subcontractors

1. The Illinois Procurement Code provides:

Section 50-10.5 and 50-60(c). Prohibited bidders, contractors and subcontractors.

The bidder or contractor or subcontractor, respectively, certifies in accordance with 30 ILCS 500/50-10.5 that no officer, director, partner or other managerial agent of the contracting business has been convicted of a felony under the Sarbanes-Oxley Act of 2002 or a Class 3 or Class 2 felony under the Illinois Securities Law of 1953 or if in violation of Subsection (c) for a period of five years from the date of conviction. Every bid submitted to and contract executed by the State and every subcontract subject to Section 20-120 of the Procurement Code shall contain a certification by the bidder, contractor, or subcontractor, respectively, that the bidder, contractor, or subcontractor is not barred from being awarded a contract or subcontract under this Section and acknowledges that the chief procurement officer shall declare the related contract void if any of the certifications completed pursuant to this Section are false.

#### E. Section 42 of the Environmental Protection Act

The bidder or contractor or subcontractor, respectively, certifies in accordance with 30 ILCS 500/50-12 that the bidder, contractor, or subcontractor, is not barred from being awarded a contract or entering into a subcontract under this Section which prohibits the bidding on or entering into contracts with the State of Illinois or a State agency, or entering into any subcontract, that is subject to the Procurement Code by a person or business found by a court or the Pollution Control Board to have committed a willful or knowing violation of Section 42 of the Environmental Protection Act for a period of five years from the date of the order. The bidder or contractor or subcontractor, respectively, acknowledges that the chief procurement officer may declare the contract void if this certification is false.

#### F. Educational Loan

- 1. Section 3 of the Educational Loan Default Act provides:
- § 3. No State agency shall contract with an individual for goods or services if that individual is in default, as defined in Section 2 of this Act, on an educational loan. Any contract used by any State agency shall include a statement certifying that the individual is not in default on an educational loan as provided in this Section.
- 2. The bidder, if an individual as opposed to a corporation, partnership or other form of business organization, certifies that the bidder is not in default on an educational loan as provided in Section 3 of the Act.

#### G. Bid-Rigging/Bid Rotating

1. Section 33E-11 of the Criminal Code of 1961 provides:

§ 33E-11. (a) Every bid submitted to and public contract executed pursuant to such bid by the State or a unit of local government shall contain a certification by the prime contractor that the prime contractor is not barred from contracting with any unit of State or local government as a result of a violation of either Section 33E-3 or 33E-4 of this Article. The State and units of local government shall provide the appropriate forms for such certification.

(b) A contractor who makes a false statement, material to the certification, commits a Class 3 felony.

A violation of Section 33E-3 would be represented by a conviction of the crime of bid-rigging which, in addition to Class 3 felony sentencing, provides that any person convicted of this offense or any similar offense of any state or the United States which contains the same elements as this offense shall be barred for 5 years from the date of conviction from contracting with any unit of State or local government. No corporation shall be barred from contracting with any unit of State or local government as a result of a conviction under this Section of any employee or agent of such corporation if the employee so convicted is no longer employed by the corporation and: (1) it has been finally adjudicated not guilty or (2) if it demonstrates to the governmental entity with which it seeks to contract and that entity finds that the commission of the offense was neither authorized, requested, commanded, nor performed by a director, officer or a high managerial agent in behalf of the corporation.

A violation of Section 33E-4 would be represented by a conviction of the crime of bid-rotating which, in addition to Class 2 felony sentencing, provides that any person convicted of this offense or any similar offense of any state or the United States which contains the same elements as this offense shall be permanently barred from contracting with any unit of State or local government. No corporation shall be barred from contracting with any unit of State or local government as a result of a conviction under this Section of any employee or agent of such corporation if the employee so convicted is no longer employed by the corporation and: (1) it has been finally adjudicated not guilty or (2) if it demonstrates to the governmental entity with which it seeks to contract and that entity finds that the commission of the offense was neither authorized, requested, commanded, nor performed by a director, officer or a high managerial agent in behalf of the corporation.

2. The bidder certifies that it is not barred from contracting with the Department by reason of a violation of either Section 33E-3 or Section 33F-4

#### H. International Anti-Boycott

- 1. Section 5 of the International Anti-Boycott Certification Act provides:
- § 5. State contracts. Every contract entered into by the State of Illinois for the manufacture, furnishing, or purchasing of supplies, material, or equipment or for the furnishing of work, labor, or services, in an amount exceeding the threshold for small purchases according to the purchasing laws of this State or \$10,000.00, whichever is less, shall contain certification, as a material condition of the contract, by which the contractor agrees that neither the contractor nor any substantially-owned affiliated company is participating or shall participate in an international boycott in violation of the provisions of the U.S. Export Administration Act of 1979 or the regulations of the U.S. Department of Commerce promulgated under that Act.
- 2. The bidder makes the certification set forth in Section 5 of the Act.

#### I. Drug Free Workplace

- 1. The Illinois "Drug Free Workplace Act" applies to this contract and it is necessary to comply with the provisions of the "Act" if the contractor is a corporation, partnership, or other entity (including a sole proprietorship) which has 25 or more employees.
- 2. The bidder certifies that if awarded a contract in excess of \$5,000 it will provide a drug free workplace by:
- (a) Publishing a statement notifying employees that the unlawful manufacture, distribution, dispensation, possession or use of a controlled substance, including cannabis, is prohibited in the contractor's workplace; specifying the actions that will be taken against employees for violations of such prohibition; and notifying the employee that, as a condition of employment on such contract, the employee shall abide by the terms of the statement, and notify the employer of any criminal drug statute conviction for a violation occurring in the workplace no later than five (5) days after such conviction.
- (b) Establishing a drug free awareness program to inform employees about the dangers of drug abuse in the workplace; the contractor's policy of maintaining a drug free workplace; any available drug counseling, rehabilitation, and employee assistance programs; and the penalties that may be imposed upon employees for drug violations.
- (c) Providing a copy of the statement required by subparagraph (1) to each employee engaged in the performance of the contract and to post the statement in a prominent place in the workplace.
- (d) Notifying the Department within ten (10) days after receiving notice from an employee or otherwise receiving actual notice of the conviction of an employee for a violation of any criminal drug statute occurring in the workplace.
- (e) Imposing or requiring, within 30 days after receiving notice from an employee of a conviction or actual notice of such a conviction, an appropriate personnel action, up to and including termination, or the satisfactory participation in a drug abuse assistance or rehabilitation program approved by a federal, state or local health, law enforcement or other appropriate agency.
- (f) Assisting employees in selecting a course of action in the event drug counseling, treatment, and rehabilitation is required and indicating that a trained referral team is in place.
- (g) Making a good faith effort to continue to maintain a drug free workplace through implementation of the actions and efforts stated in this certification.

#### J. <u>Disclosure of Business Operations in Iran</u>

Section 50-36 of the Illinois Procurement Code, 30ILCS 500/50-36 provides that each bid, offer, or proposal submitted for a State contract shall include a disclosure of whether or not the Company acting as the bidder, offeror, or proposing entity, or any of its corporate parents or subsidiaries, within the 24 months before submission of the bid, offer, or proposal had business operations that involved contracts with or provision of supplies or services to the Government of Iran, companies in which the Government of Iran has any direct or indirect equity share, consortiums or projects commissioned by the Government of Iran, or companies involved in consortiums or projects commissioned by the Government of Iran and either of the following conditions apply:

- (1) More than 10% of the Company's revenues produced in or assets located in Iran involve oil-related activities or mineral-extraction activities; less than 75% of the Company's revenues produced in or assets located in Iran involve contracts with or provision of oil-related or mineral-extraction products or services to the Government of Iran or a project or consortium created exclusively by that government; and the Company has failed to take substantial action.
- (2) The Company has, on or after August 5, 1996, made an investment of \$20 million or more, or any combination of investments of at least \$10 million each that in the aggregate equals or exceeds \$20 million in any 12-month period, which directly or significantly contributes to the enhancement of Iran's ability to develop petroleum resources of Iran.

The terms "Business operations", "Company", "Mineral-extraction activities", "Oil-related activities", "Petroleum resources", and "Substantial action" are all defined in the Code.

Failure to make the disclosure required by the Code shall cause the bid, offer or proposal to be considered not responsive. The disclosure will be considered when evaluating the bid, offer, or proposal or awarding the contract. The name of each Company disclosed as doing business or having done business in Iran will be provided to the State Comptroller.

Check the appropriate statement:
// Company has no business operations in Iran to disclose.
// Company has business operations in Iran as disclosed the attached document.

#### K. Apprenticeship and Training Certification (Does not apply to federal aid projects)

In accordance with the provisions of Section 30-22 (6) of the Illinois Procurement Code, the bidder certifies that it is a participant, either as an individual or as part of a group program, in the approved apprenticeship and training programs applicable to each type of work or craft that the bidder will perform with its own forces. The bidder further certifies for work that will be performed by subcontract that each of its subcontractors submitted for approval either (a) is, at the time of such bid, participating in an approved, applicable apprenticeship and training program; or (b) will, prior to commencement of performance of work pursuant to this contract, begin participation in an approved apprenticeship and training program applicable to the work of the subcontract. The Department, at any time before or after award, may require the production of a copy of each applicable Certificate of Registration issued by the United States Department of Labor evidencing such participation by the contractor and any or all of its subcontractors. Applicable apprenticeship and training programs are those that have been approved and registered with the United States Department of Labor. The bidder shall list in the space below, the official name of the program sponsor holding the Certificate of Registration for all of the types of work or crafts in which the bidder is a participant and that will be performed with the bidder's forces. Types of work or craft work that will be subcontracted shall be included and listed as subcontract work. The list shall also indicate any type of work or craft job category that does not have an applicable apprenticeship or training program. The bidder is responsible for making a complete report and shall make certain that each type of work or craft job category that will be utilized on the project as reported on the Construction Employee Workforce Projection (Form BC-1256) and returned with the bid is accounted for and listed.

The requirements of this certification and disclosure are a material part of the contract, and the contractor shall require this certification provision to be included in all approved subcontracts. In order to fulfill this requirement, it shall not be necessary that an applicable program sponsor be currently taking or that it will take applications for apprenticeship, training or employment during the performance of the work of this contract.

#### TO BE RETURNED WITH BID

#### L. Political Contributions and Registration with the State Board of Elections

Sections 20-160 and 50-37 of the Illinois Procurement Code regulate political contributions from business entities and any affiliated entities or affiliated persons bidding on or contracting with the state. Generally under Section 50-37, any business entity, and any affiliated entity or affiliated person of the business entity, whose current year contracts with all state agencies exceed an awarded value of \$50,000, are prohibited from making any contributions to any political committees established to promote the candidacy of the officeholder responsible for the awarding of the contracts or any other declared candidate for that office for the duration of the term of office of the incumbent officeholder or a period 2 years after the termination of the contract, whichever is longer. Any business entity and affiliated entities or affiliated persons whose state contracts in the current year do not exceed an awarded value of \$50,000, but whose aggregate pending bids and proposals on state contracts exceed \$50,000, either alone or in combination with contracts not exceeding \$50,000, are prohibited from making any political contributions to any political committee established to promote the candidacy of the officeholder responsible for awarding the pending contract during the period beginning on the date the invitation for bids or request for proposals is issued and ending on the day after the date of award or selection if the entity was not awarded or selected. Section 20-160 requires certification of registration of affected business entities in accordance with procedures found in Section 9-35 of The Election Code.

By submission of a bid, the contractor business entity acknowledges and agrees that it has read and understands Sections 20-160 and 50-37 of the Illinois Procurement Code, and that it makes the following certification:

The undersigned business entity certifies that it has registered as a business with the State Board of Elections and acknowledges a continuing duty to update the registration in accordance with the above referenced statutes. A copy of the certificate of registration shall be submitted with the bid. The bidder is cautioned that the Department will not award a contract without submission of the certificate of registration.

These requirements and compliance with the above referenced statutory sections are a material part of the contract, and any breach thereof shall be cause to void the contract under Section 50-60 of the Illinois Procurement Code. This provision does not apply to Federal-aid contracts.

#### M. Lobbyist Disclosure

Section 50-38 of the Illinois Procurement Code requires that any bidder or offeror on a State contract that hires a person required to register under the Lobbyist Registration Act to assist in obtaining a contract shall:

- (i) Disclose all costs, fees, compensation, reimbursements, and other remunerations paid or to be paid to the lobbyist related to the contract.
- (ii) Not bill or otherwise cause the State of Illinois to pay for any of the lobbyist's costs, fees, compensation, reimbursements, or other remuneration, and
- (iii) Sign a verification certifying that none of the lobbyist's costs, fees, compensation, reimbursements, or other remuneration were billed to the State.

This information, along with all supporting documents, shall be filed with the agency awarding the contract and with the Secretary of State. The chief procurement officer shall post this information, together with the contract award notice, in the online Procurement Bulletin.

Pursuant to Subsection (c) of this Section, no person or entity shall retain a person or entity to attempt to influence the outcome of a procurement decision made under the Procurement Code for compensation contingent in whole or in part upon the decision or procurement. Any person who violates this subsection is guilty of a business offense and shall be fined not more than \$10,000.

Bidder acknowledges that it is required to disclose the hiring of any person required to register pursuant to the Illinois Lobbyist Registration Act (25 ILCS 170) in connection with this contract.

	Bidder has not hired any person required to register pursuant to the Illinois Lobbyist Registration Act in connection with this contract.
Or	
	Bidder has hired the following persons required to register pursuant to the Illinois Lobbyist Registration Act in connection with the contract:
	address of person:ees, compensation, reimbursements and other remuneration paid to said person:

#### IV. DISCLOSURES

A. The disclosures hereinafter made by the bidder are each a material representation of fact upon which reliance is placed should the Department enter into the contract with the bidder. The bidder further certifies that the Department has received the disclosure forms for each bid.

The chief procurement officer may void the bid, contract, or subcontract, respectively, if it is later determined that the bidder or subcontractor rendered a false or erroneous disclosure. A contractor or subcontractor may be suspended or debarred for violations of the Procurement Code. Furthermore, the chief procurement officer may void the contract and the surety providing the performance bond shall be responsible for completion of the contract.

#### B. Financial Interests and Conflicts of Interest

1. Section 50-35 of the Illinois Procurement Code provides that all bids of more than \$25,000 shall be accompanied by disclosure of the financial interests of the bidder. This disclosed information for the successful bidder, will be maintained as public information subject to release by request pursuant to the Freedom of Information Act, filed with the Procurement Policy Board, and shall be incorporated as a material term of the contract. Furthermore, pursuant to Section 5-5, the Procurement Policy Board may review a proposal, bid, or contract and issue a recommendation to void a contract or reject a proposal or bid based on any violation of the Procurement Code or the existence of a conflict of interest as provided in subsections (b) and (d) of Section 50-35.

The financial interests to be disclosed shall include ownership or distributive income share that is in excess of 5%, or an amount greater than 60% of the annual salary of the Governor, of the bidding entity or its parent entity, whichever is less, unless the contractor or bidder is a publicly traded entity subject to Federal 10K reporting, in which case it may submit its 10K disclosure in place of the prescribed disclosure. If a bidder is a privately held entity that is exempt from Federal 10K reporting, but has more than 400 shareholders, it may submit the information that Federal 10K companies are required to report, and list the names of any person or entity holding any ownership share that is in excess of 5%. The disclosure shall include the names, addresses, and dollar or proportionate share of ownership of each person making the disclosure, their instrument of ownership or beneficial relationship, and notice of any potential conflict of interest resulting from the current ownership or beneficial interest of each person making the disclosure having any of the relationships identified in Section 50-35 and on the disclosure form.

#### The current annual salary of the Governor is \$177,412.00

In addition, all disclosures shall indicate any other current or pending contracts, proposals, leases, or other ongoing procurement relationships the bidding entity has with any other unit of state government and shall clearly identify the unit and the contract, proposal, lease, or other relationship.

2. <u>Disclosure Forms</u>. Disclosure Form A is attached for use concerning the individuals meeting the above ownership or distributive share requirements. Subject individuals should be covered each by one form. In addition, a second form (Disclosure Form B) provides for the disclosure of current or pending procurement relationships with other (non-IDOT) state agencies. **The forms must be included with each bid.** 

#### C. <u>Disclosure Form Instructions</u>

than one question.)

#### Form A Instructions for Financial Information & Potential Conflicts of Interest

If the bidder is a publicly traded entity subject to Federal 10K reporting, the 10K Report may be submitted to meet the requirements of Form A. If a bidder is a privately held entity that is exempt from Federal 10K reporting, but has more than 400 shareholders, it may submit the information that Federal 10K companies are required to report, and list the names of any person or entity holding any ownership share that is in excess of 5%. If a bidder is not subject to Federal 10K reporting, the bidder must determine if any individuals are required by law to complete a financial disclosure form. To do this, the bidder should answer each of the following questions. A "YES" answer indicates Form A must be completed. If the answer to each of the following questions is "NO", then the <u>NOT APPLICABLE STATEMENT</u> on Form A must be signed and dated by a person that is authorized to execute contracts for the bidding company. Note: These questions are for assistance only and are not required to be completed.

1.	Does anyone in your organization have a direct or beneficial ownership share of greater than 5% of the bidding entity or parent entity? YES NO
2.	Does anyone in your organization have a direct or beneficial ownership share of less than 5%, but which has a value greater than 60% of the annual salary of the Governor? YESNO
3.	Does anyone in your organization receive more than 60% of the annual salary of the Governor of the bidding entity's or parent entity's distributive income? YES NO
	(Note: Distributive income is, for these purposes, any type of distribution of profits. An annual salary is not distributive income.)
4.	Does anyone in your organization receive greater than 5% of the bidding entity's or parent entity's total distributive income, but which is less than 60% of the annual salary of the Governor? YES NO

A "YES" answer to any of these questions requires the completion of Form A. The bidder must determine each individual in the bidding entity or the bidding entity's parent company that would cause the questions to be answered "Yes". Each form must be signed and dated by a person that is authorized to execute contracts for your organization. **Photocopied or stamped signatures are not acceptable**. The person signing can be, but does not have to be, the person for which the form is being completed. The bidder is responsible for the accuracy of any information provided.

(Note: Only one set of forms needs to be completed per person per bid even if a specific individual would require a yes answer to more

If the answer to each of the above questions is "NO", then the NOT APPLICABLE STATEMENT of Form A must be signed and dated by a person that is authorized to execute contracts for your company.

#### Form B: Instructions for Identifying Other Contracts & Procurement Related Information

Disclosure Form B must be completed for each bid submitted by the bidding entity. *Note: Checking the <u>NOT APPLICABLE STATEMENT</u> on Form A <u>does not</u> allow the bidder to ignore Form B. Form B must be completed, checked, and dated or the bidder may be considered nonresponsive and the bid will not be accepted.* 

The Bidder shall identify, by checking Yes or No on Form B, whether it has any pending contracts (including leases), bids, proposals, or other ongoing procurement relationship with any other (non-IDOT) State of Illinois agency. If "No" is checked, the bidder only needs to complete the check box on the bottom of Form B. If "Yes" is checked, the bidder must do one of the following:

Option I: If the bidder did not submit an Affidavit of Availability to obtain authorization to bid, the bidder must list all non-IDOT State of Illinois agency pending contracts, leases, bids, proposals, and other ongoing procurement relationships. These items may be listed on Form B or on an attached sheet(s). Do not include IDOT contracts. Contracts with cities, counties, villages, etc. are not considered State of Illinois agency contracts and are not to be included. Contracts with other State of Illinois agencies such as the Department of Natural Resources or the Capital Development Board must be included. Bidders who submit Affidavits of Availability are suggested to use Option II.

Option II: If the bidder is required and has submitted an Affidavit of Availability in order to obtain authorization to bid, the bidder may write or type "See Affidavit of Availability" which indicates that the Affidavit of Availability is incorporated by reference and includes all non-IDOT State of Illinois agency pending contracts, leases, bids, proposals, and other ongoing procurement relationships. For any contracts that are not covered by the Affidavit of Availability, the bidder must identify them on Form B or on an attached sheet(s). These might be such things as leases.

## ILLINOIS DEPARTMENT OF TRANSPORTATION

# Form A Financial Information & Potential Conflicts of Interest Disclosure

Contractor Name		
Legal Address		
City, State, Zip		
Telephone Number	Email Address	Fax Number (if available)
•		

Disclosure of the information contained in this Form is required by the Section 50-35 of the Illinois Procurement Code (30 ILCS 500). Vendors desiring to enter into a contract with the State of Illinois must disclose the financial information and potential conflict of interest information as specified in this Disclosure Form. This information shall become part of the publicly available contract file. This Form A must be completed for bids in excess of \$25,000, and for all openended contracts. A publicly traded company may submit a 10K disclosure (or equivalent if applicable) in satisfaction of the requirements set forth in Form A. See Disclosure Form Instructions.

The current annual salary of the Governor is \$177,412.00.

FOR INDIVIDUAL (type or print information)

#### DISCLOSURE OF FINANCIAL INFORMATION

1. Disclosure of Financial Information. The individual named below has an interest in the BIDDER (or its parent) in terms of ownership or distributive income share in excess of 5%, or an interest which has a value of more than 60% of the annual salary of the Governor. (Make copies of this form as necessary and attach a separate Disclosure Form A for each individual meeting these requirements)

NAME:	
ADDRE	ss
_	
Type of	ownership/distributable income share:
	sole proprietorship Partnership other: (explain on separate sheet):
	of Potential Conflicts of Interest. Check "Yes" or "No" to indicate which, if any, of the following
potential conflic and describe. (a) State e	et of interest relationships apply. If the answer to any question is "Yes", please attach additional pages employment, currently or in the previous 3 years, including contractual employment of services.  YesNo
potential conflic and describe. (a) State e	et of interest relationships apply. If the answer to any question is "Yes", please attach additional pages employment, currently or in the previous 3 years, including contractual employment of services.
potential conflic and describe. (a) State e	et of interest relationships apply. If the answer to any question is "Yes", please attach additional pages employment, currently or in the previous 3 years, including contractual employment of services.  YesNo

4. If you are currently appointed to or employed by any agency of the State of Illinois, and your ann salary exceeds 60% of the annual salary of the Governor, are you and your spouse or minor children entitled to receive (i) more than 15 % in the aggregate of the total distributal income of your firm, partnership, association or corporation, or (ii) an amount in excess of two tithe salary of the Governor?  (b) State employment of spouse, father, mother, son, or daughter, including contractual employment services in the previous 2 years.  If your answer is yes, please answer each of the following questions.  1. Is your spouse or any minor children currently an officer or employee of the Capitol Developmer Board or the Illinois State Toll Highway Authority?  2. Is your spouse or any minor children currently appointed to or employed by any agency of the St of Illinois? If your spouse or minor children is/are currently appointed to or employed by. agency of the State of Illinois, and his/her annual salary exceeds 60% of the annual salary of the Governor, provide the name of your spouse and/or minor children, the name of the State agency for which he/she is employed and his/her annual salary of the Governor, as of 7/1/07) are you entitled to receive (i) more than 71/2% of the total distributable income of y firm, partnership, association or corporation, or (ii) an amount in excess of 100% of the annual salary of the Governor?  4. If your spouse or any minor children are currently appointed to or employed by any agency of State of Illinois, and his/her annual salary exceeds 60% of the annual salary of the Governor, as of 7/1/07) are you entitled to receive (i) more than 71/2% of the total distributable income of y firm, partnership, association or corporation, or (ii) an amount in excess of 100% of the annual salary of the Governor?  4. If your spouse or any minor children are currently appointed to or employed by any agency of State of Illinois, and his/her annual salary exceeds 60% of the annual salary of the Gove		3.	If you are currently appointed to or employed by any agency of the Si salary exceeds 60% of the annual salary of the Governor, are you en (i) more than 7 1/2% of the total distributable income of your firm, corporation, or (ii) an amount in excess of 100% of the annual salary	titled to receive partnership, association or
If your answer is yes, please answer each of the following questions.  1. Is your spouse or any minor children currently an officer or employee of the Capitol Developmer Board or the Illinois State Toll Highway Authority? YesNo  2. Is your spouse or any minor children currently appointed to or employed by any agency of the State of Illinois, and his/her annual salary exceeds 60% of the annual salary of the Governor, provide the name of your spouse and/or minor children, the name of the State of Illinois, and his/her annual salary exceeds 60% of the annual salary of the Governor, provide the name of your spouse and/or minor children, the name of the State of Illinois, and his/her annual salary exceeds 60% of the annual salary of the Governor, as of 7/1/07) are you entitled to receive (i) more than 71/2% of the total distributable income of y firm, partnership, association or corporation, or (ii) an amount in excess of 100% of the annual salary of the Governor?  4. If your spouse or any minor children are currently appointed to or employed by any agency of State of Illinois, and his/her annual salary exceeds 60% of the annual salary of the Governor, are and your spouse or minor children are currently appointed to or employed by any agency of State of Illinois, and his/her annual salary exceeds 60% of the annual salary of the Governor, are and your spouse or minor children entitled to receive (i) more than 15% in the aggregate of the total distributable income of your firm, partnership, association or corporation (ii) an amount in excess of 2 times the salary of the Governor?  (c) Elective status; the holding of elective office of the State of Illinois, the government of the United States, unit of local government authorized by the Constitution of the State of Illinois or the statutes of the State of the State of Illinois, which office entitles the holder to compensation in excess of the expenses incurrence of the discharge of that office currently or in the previous 3 years; spouse, father, moth son, or da		4.	salary exceeds 60% of the annual salary of the Governor, are you an or minor children entitled to receive (i) more than 15 % in the aggreincome of your firm, partnership, association or corporation, or (ii) are	d your spouse egate of the total distributable amount in excess of two times
If your answer is yes, please answer each of the following questions.  1. Is your spouse or any minor children currently an officer or employee of the Capitol Developmer Board or the Illinois State Toll Highway Authority?  2. Is your spouse or any minor children currently appointed to or employed by any agency of the State of Illinois, and his/her annual salary exceeds 60% of the annual salary of the Governor, provide the name of your spouse and/or minor children, the name of the State agency for which he/she is employed and his/her annual salary.  3. If your spouse or any minor children is/are currently appointed to or employed by any agency of State of Illinois, and his/her annual salary exceeds 60% of the annual salary of the Governor, as of 7/1/07) are you entitled to receive (i) more than 71/2% of the total distributable income of y firm, partnership, association or corporation, or (ii) an amount in excess of 100% of the annual salary of the Governor?  4. If your spouse or any minor children are currently appointed to or employed by any agency of State of Illinois, and his/her annual salary exceeds 60% of the annual salary of the Governor, are and your spouse or minor children entitled to receive (i) more than 15% in the aggregate of the total distributable income of your firm, partnership, association or corporation (ii) an amount in excess of 2 times the salary of the Governor?  YesNo  (c) Elective status; the holding of elective office of the State of Illinois, the government of the United States, unit of local government authorized by the Constitution of the State of Illinois or the statutes of the Stat Illinois currently or in the previous 3 years.  YesNo  (d) Relationship to anyone holding elective office currently or in the previous 2 years; spouse, father, mother state of Illinois, which office entitles the holder to compensation in excess of the expenses incurrently discharge of that office currently or in the previous 3 years.  YesNo  (f) Relationship to anyone holding appointive offi	(b)			
2. Is your spouse or any minor children currently appointed to or employed by any agency of the St of Illinois? If your spouse or minor children is/are currently appointed to or employed by agency of the State of Illinois, and his/her annual salary exceeds 60% of the annual salary of the Governor, provide the name of your spouse and/or minor children, the name of the State agency for which he/she is employed and his/her annual salary.  3. If your spouse or any minor children is/are currently appointed to or employed by any agency of State of Illinois, and his/her annual salary exceeds 60% of the annual salary of the Governor, as of 771/07) are you entitled to receive (i) more than 71/2% of the total distributable income of y firm, partnership, association or corporation, or (ii) an amount in excess of 100% of the annual salary of the Governor?  4. If your spouse or any minor children are currently appointed to or employed by any agency of State of Illinois, and his/her annual salary exceeds 60% of the annual salary of the Governor, are and your spouse or minor children entitled to receive (i) more than 15 % in the aggregate of the total distributable income of your firm, partnership, association or corporation (ii) an amount in excess of 2 times the salary of the Governor?  YesNo  (c) Elective status; the holding of elective office of the State of Illinois, the government of the United States, unit of local government authorized by the Constitution of the State of Illinois or the statutes of the State Illinois currently or in the previous 3 years.  YesNo  (d) Relationship to anyone holding elective office currently or in the previous 2 years; spouse, father, mothers of the State of Illinois, which office entitles the holder to compensation in excess of the expenses incurrently discharge of that office currently or in the previous 3 years.  YesNo  (f) Relationship to anyone holding appointive office currently or in the previous 2 years; spouse, father, mothers in the previous 3 years, as or by any		If your ans	wer is yes, please answer each of the following questions.	YesNo
of Illinois? If your spouse or minor children is/are currently appointed to or employed by agency of the State of Illinois, and his/her annual salary exceeds 60% of the annual salary of the Governor, provide the name of your spouse and/or minor children, the name of the State agency for which he/she is employed and his/her annual salary.  3. If your spouse or any minor children is/are currently appointed to or employed by any agency of State of Illinois, and his/her annual salary exceeds 60% of the annual salary of the Governor, as of 7/1/07) are you entitled to receive (i) more than 7/1/2% of the total distributable income of y firm, partnership, association or corporation, or (ii) an amount in excess of 100% of the annual salary of the Governor?  4. If your spouse or any minor children are currently appointed to or employed by any agency of State of Illinois, and his/her annual salary exceeds 60% of the annual salary of the Governor, are and your spouse or minor children entitled to receive (i) more than 15 % in the aggregate of the total distributable income of your firm, partnership, association or corporation (ii) an amount in excess of 2 times the salary of the Governor?  YesNo  (c) Elective status; the holding of elective office of the State of Illinois, the government of the United States, unit of local government authorized by the Constitution of the State of Illinois or the statutes of the Stat Illinois currently or in the previous 3 years.  YesNo  (d) Relationship to anyone holding elective office currently or in the previous 2 years; spouse, father, mother son, or daughter.  YesNo  (f) Relationship to anyone holding appointive office currently or in the previous 2 years; spouse, father, mother son, or daughter.  YesNo  (g) Employment, currently or in the previous 3 years, as or by any registered lobbyist of the State government.		1.		
State of Illinois, and his/her annual salary exceeds 60% of the annual salary of the Governor, as of 7/1/07) are you entitled to receive (i) more than 71/2% of the total distributable income of y firm, partnership, association or corporation, or (ii) an amount in excess of 100% of the annual salary of the Governor?  4. If your spouse or any minor children are currently appointed to or employed by any agency of State of Illinois, and his/her annual salary exceeds 60% of the annual salary of the Governor, are and your spouse or minor children entitled to receive (i) more than 15 % in the aggregate of the total distributable income of your firm, partnership, association or corporation. (ii) an amount in excess of 2 times the salary of the Governor?  YesNo  (c) Elective status; the holding of elective office of the State of Illinois, the government of the United States, unit of local government authorized by the Constitution of the State of Illinois or the statutes of the State Illinois currently or in the previous 3 years.  YesNo  (d) Relationship to anyone holding elective office currently or in the previous 2 years; spouse, father, mothers of the State of Illinois, which office entitles the holder to compensation in excess of the expenses incurrently discharge of that office currently or in the previous 3 years.  YesNo  (f) Relationship to anyone holding appointive office currently or in the previous 2 years; spouse, father, mothersNo  (g) Employment, currently or in the previous 3 years, as or by any registered lobbyist of the State government			of Illinois? If your spouse or minor children is/are currently appared agency of the State of Illinois, and his/her annual salary exceed annual salary of the Governor, provide the name of your spouse and/or	pointed to or employed by any ls 60% of the minor children, the name
State of Illinois, and his/her annual salary exceeds 60% of the annual salary of the Governor, are and your spouse or minor children entitled to receive (i) more than 15 % in the aggregate of the total distributable income of your firm, partnership, association or corporation, (ii) an amount in excess of 2 times the salary of the Governor?  YesNo  (c) Elective status; the holding of elective office of the State of Illinois, the government of the United States, unit of local government authorized by the Constitution of the State of Illinois or the statutes of the Stat Illinois currently or in the previous 3 years.  YesNo  (d) Relationship to anyone holding elective office currently or in the previous 2 years; spouse, father, mothers on, or daughter.  YesNo  (e) Appointive office; the holding of any appointive government office of the State of Illinois, the United State of the State of Illinois, which office entitles the holder to compensation in excess of the expenses incurrently discharge of that office currently or in the previous 3 years.  YesNo  (f) Relationship to anyone holding appointive office currently or in the previous 2 years; spouse, father, mothers on, or daughter.  YesNo  (g) Employment, currently or in the previous 3 years, as or by any registered lobbyist of the State government of the State of Illinois, the United State government of the State of Illinois or the State gov			State of Illinois, and his/her annual salary exceeds 60% of the annual as of 7/1/07) are you entitled to receive (i) more than 71/2% of the tof firm, partnership, association or corporation, or (ii) an amount in	I salary of the Governor, tal distributable income of your excess of 100% of the
(c) Elective status; the holding of elective office of the State of Illinois, the government of the United States, unit of local government authorized by the Constitution of the State of Illinois or the statutes of the State Illinois currently or in the previous 3 years.  (d) Relationship to anyone holding elective office currently or in the previous 2 years; spouse, father, mother son, or daughter.  (e) Appointive office; the holding of any appointive government office of the State of Illinois, the United State America, or any unit of local government authorized by the Constitution of the State of Illinois or the state of the State of Illinois, which office entitles the holder to compensation in excess of the expenses incurrently discharge of that office currently or in the previous 3 years.  (f) Relationship to anyone holding appointive office currently or in the previous 2 years; spouse, father, mother son, or daughter.  (g) Employment, currently or in the previous 3 years, as or by any registered lobbyist of the State government.		4.	State of Illinois, and his/her annual salary exceeds 60% of the annual and your spouse or minor children entitled to receive (i) more than aggregate of the total distributable income of your firm, partnership,	salary of the Governor, are you 15 % in the
unit of local government authorized by the Constitution of the State of Illinois or the statutes of the State Illinois currently or in the previous 3 years.  (d) Relationship to anyone holding elective office currently or in the previous 2 years; spouse, father, mother son, or daughter.  (e) Appointive office; the holding of any appointive government office of the State of Illinois, the United State America, or any unit of local government authorized by the Constitution of the State of Illinois or the state of the State of Illinois, which office entitles the holder to compensation in excess of the expenses incurrently discharge of that office currently or in the previous 3 years.  (f) Relationship to anyone holding appointive office currently or in the previous 2 years; spouse, father, mother son, or daughter.  (g) Employment, currently or in the previous 3 years, as or by any registered lobbyist of the State government.				YesNo
son, or daughter.  YesNo  (e) Appointive office; the holding of any appointive government office of the State of Illinois, the United Stat America, or any unit of local government authorized by the Constitution of the State of Illinois or the stat of the State of Illinois, which office entitles the holder to compensation in excess of the expenses incurred the discharge of that office currently or in the previous 3 years.  YesNo  (f) Relationship to anyone holding appointive office currently or in the previous 2 years; spouse, father, mot son, or daughter.  YesNo  (g) Employment, currently or in the previous 3 years, as or by any registered lobbyist of the State government.		unit of	local government authorized by the Constitution of the State of Illinois	s or the statutes of the State of
America, or any unit of local government authorized by the Constitution of the State of Illinois or the state of the State of Illinois, which office entitles the holder to compensation in excess of the expenses incurrently the discharge of that office currently or in the previous 3 years.  YesNo  (f) Relationship to anyone holding appointive office currently or in the previous 2 years; spouse, father, mot son, or daughter.  YesNo  (g) Employment, currently or in the previous 3 years, as or by any registered lobbyist of the State government.		` '		
son, or daughter.  YesNo  (g) Employment, currently or in the previous 3 years, as or by any registered lobbyist of the State government.		Americ of the	ca, or any unit of local government authorized by the Constitution of the State of Illinois, which office entitles the holder to compensation in except the constitution of the compensation in except the constitution of the constitution of the compensation in except the compensati	ne State of Illinois or the statutes cess of the expenses incurred in
		` '		•
		(g) Emplo	yment, currently or in the previous 3 years, as or by any registered lob	byist of the State government. YesNo

#### **RETURN WITH BID/OFFER**

(h)	son, or daughter.  Relationship to anyone who is or was a registered lobbyist in the previous 2 years; spouse, father, mothers on, or daughter.  YesNo	∍r,
(i)	Compensated employment, currently or in the previous 3 years, by any registered election or reelecticommittee registered with the Secretary of State or any county clerk of the State of Illinois, or any politic action committee registered with either the Secretary of State or the Federal Board of Elections.  Yes No	
(j)	Relationship to anyone; spouse, father, mother, son, or daughter; who was a compensated employee in last 2 years by any registered election or re-election committee registered with the Secretary of State or a county clerk of the State of Illinois, or any political action committee registered with either the Secretary State or the Federal Board of Elections.	any
	Yes No	
2.	Communication Disclosure.	
Se er su	sclose the name and address of each lobbyist and other agent of the bidder or offeror who is not identified ction 2 of this form, who is has communicated, is communicating, or may communicate with any State off aployee concerning the bid or offer. This disclosure is a continuing obligation and must be promptly applemented for accuracy throughout the process and throughout the term of the contract. If no person is antified, enter "None" on the line below:	
	Name and address of person(s):	

**4. Debarment Disclosure.** For each of the persons identified under Sections 2 and 3 of this form, disclose whether any of the following has occurred within the previous 10 years: debarment from contracting with any

governmental entity; professional licensure discipline; bankruptcies; adverse civil judgments and administrative findings; and criminal felony convictions. This disclosure is a continuing obligation and must be promptly supplemented for accuracy throughout the procurement process and term of the contract. If no person is identified, enter "None" on the line below: Name of person(s): Nature of disclosure: **APPLICABLE STATEMENT** This Disclosure Form A is submitted on behalf of the INDIVIDUAL named on previous page. Under penalty of perjury, I certify the contents of this disclosure to be true and accurate to the best of my knowledge. Completed by: Signature of Individual or Authorized Representative Date NOT APPLICABLE STATEMENT Under penalty of perjury, I have determined that no individuals associated with this organization meet the criteria that would require the completion of this Form A. This Disclosure Form A is submitted on behalf of the CONTRACTOR listed on the previous page. Signature of Authorized Representative Date

The bidder has a continuing obligation to supplement these disclosures under Sec. 50-35 of the Procurement Code.

## ILLINOIS DEPARTMENT OF TRANSPORTATION

# Form B Other Contracts & Procurement Related Information Disclosure

Contractor Name		
Legal Address		
City, State, Zip		
Telephone Number	Email Address	Fax Number (if available)
Disclosure of the information contained in the LCS 500). This information shall become poids in excess of \$25,000, and for all open-e	art of the publicly available contract nded contracts.	file. This Form B must be completed fo
DISCLOSURE OF OTHER CO	ONTRACTS AND PROCUREMENT	RELATED INFORMATION
1. Identifying Other Contracts & Procure pending contracts (including leases), bids, Illinois agency: Yes No If "No" is checked, the bidder only needs	proposals, or other ongoing procure	ement relationship with any other State of
<b>2. If "Yes" is checked.</b> Identify each such descriptive information such as bid or proje FORM INSTRUCTIONS:		
THE FOLL	OWING STATEMENT MUST BE C	HECKED
	Signature of Authorized Representative	Date

#### **SPECIAL NOTICE TO CONTRACTORS**

The following requirements of the Illinois Department of Human Rights' Rules and Regulations are applicable to bidders on all construction contracts advertised by the Illinois Department of Transportation:

#### **CONSTRUCTION EMPLOYEE UTILIZATION PROJECTION**

- (a) All bidders on construction contracts shall complete and submit, along with and as part of their bids, a Bidder's Employee Utilization Form (Form BC-1256) setting forth a projection and breakdown of the total workforce intended to be hired and/or allocated to such contract work by the bidder including a projection of minority and female employee utilization in all job classifications on the contract project.
- (b) The Department of Transportation shall review the Employee Utilization Form, and workforce projections contained therein, of the contract awardee to determine if such projections reflect an underutilization of minority persons and/or women in any job classification in accordance with the Equal Employment Opportunity Clause and Section 7.2 of the Illinois Department of Human Rights' Rules and Regulations for Public Contracts adopted as amended on September 17, 1980. If it is determined that the contract awardee's projections reflect an underutilization of minority persons and/or women in any job classification, it shall be advised in writing of the manner in which it is underutilizing and such awardee shall be considered to be in breach of the contract unless, prior to commencement of work on the contract project, it submits revised satisfactory projections or an acceptable written affirmative action plan to correct such underutilization including a specific timetable geared to the completion stages of the contract.
- (c) The Department of Transportation shall provide to the Department of Human Rights a copy of the contract awardee's Employee Utilization Form, a copy of any required written affirmative action plan, and any written correspondence related thereto. The Department of Human Rights may review and revise any action taken by the Department of Transportation with respect to these requirements.



Contract No. 74503 CUMBERLAND-CLARK Counties Section D7 PAVT PRSV 2011-2 Route FAI 70 District 7 Construction Funds

PART I. IDENTIFICA	ATION																	
Dept. Human Rights	s #						_ Dui	ration c	f Proje	ect:								
Name of Bidder:																		
PART II. WORKFO  A. The undersigned which this contract wor projection including a p	bidder hark is to be	as analyz perform	ed mir ed, an	d for the	ne locati	ons fro	m whi	ch the b	idder re	cruits	employe	es, and h	ereb	y subm	its the foll	owir con	ig workfo	n orce
		TOTA	AL Wo	rkforce	Project	tion for	Contra	act						(	CURRENT TO BE			S
				MINI			VEEC			TD/	VINIEEC				TO CO			
JOB CATEGORIES	_	TAL OYEES	BLA	ACK	ORITY E		*OT	HER NOR.	APPI TIC	REN-		HE JOB INEES			OTAL OYEES			ORITY OYEES
	М	F	М	F	М	F	М	F	М	F	М	F		М	F		М	F
OFFICIALS (MANAGERS)																		
SUPERVISORS																		
FOREMEN																		
CLERICAL																		
EQUIPMENT OPERATORS																		
MECHANICS																		
TRUCK DRIVERS																		
IRONWORKERS																		
CARPENTERS																		
CEMENT MASONS																		
ELECTRICIANS																		
PIPEFITTERS, PLUMBERS																		
PAINTERS																		
LABORERS, SEMI-SKILLED																		
LABORERS, UNSKILLED																		
TOTAL																		
		BLE C								Γ		EOD	DEL	) A DTI	/ENT US		MII V	
		aining Pro	ojectio	n for C	ontract		1		4			ruk	DEF	MK IIV	ALINI US	, E (	/INL Ĭ	
EMPLOYEES IN	_	TAL OYEES	DI /	ACK	шер	ANIC	_	THER NOR.										
TRAINING	M	JYEES F	M M	F	M	F	M	F	+									
APPRENTICES	IVI	'	171	'	IVI	<u> </u>	IVI	<u> </u>	1									
ON THE JOB	<del> </del>						+		1									
TRAINEES	<u> </u>			<u> </u>		<u> </u>	<u> </u>			L								
* C	Other minor	ities are det	fined as	Asians	(A) or Na	tive Ame	ricans (	N).										

Note: See instructions on page 2

Please specify race of each employee shown in Other Minorities column.

BC 1256 (Rev. 12/11/07)

Contract No. 74503 CUMBERLAND-CLARK Counties Section D7 PAVT PRSV 2011-2 Route FAI 70 District 7 Construction Funds

#### PART II. WORKFORCE PROJECTION - continued

B.		ded in "Total Employees" under Table A is the total numb t the undersigned bidder is awarded this contract.	per of <b>new hires</b> that wo	ould be employed in the
	The u	undersigned bidder projects that: (number)		new hires would be
	recrui	ited from the area in which the contract project is located	d; and/or (number)	
	office	new hires would be report or base of operation is located.	cruited from the area in	which the bidder's principal
C.		ded in "Total Employees" under Table A is a projection o rsigned bidder as well as a projection of numbers of pers		
	The u	undersigned bidder estimates that (number)		persons will
		rectly employed by the prime contractor and that (number byed by subcontractors.	er)	persons will be
PART	III. AFF	FIRMATIVE ACTION PLAN		
A.	utiliza in any comm (geare utiliza	undersigned bidder understands and agrees that in the ention projection included under <b>PART II</b> is determined to by job category, and in the event that the undersigned bid nencement of work, develop and submit a written Affirmated to the completion stages of the contract) whereby determined are corrected. Such Affirmative Action Plan will be repartment of Human Rights.	be an underutilization o lder is awarded this contative Action Plan including ficiencies in minority and	f minority persons or women tract, he/she will, prior to ng a specific timetable d/or female employee
B.	subm	undersigned bidder understands and agrees that the min itted herein, and the goals and timetable included under part of the contract specifications.		
Comp	any		Telephone Number	
Addre	 :SS			
Г		NOTICE REGARDING S	SIGNATURE	
	The Rid	dder's signature on the Proposal Signature Sheet will constitut		The following signature block
		to be completed if revisions are required.	e the signing of this form.	The following signature block
	Signatu	ure: Title:		Date:
Instruct	ions:	All tables must include subcontractor personnel in addition to prime	contractor personnel.	
Table A	۸ -	Include both the number of employees that would be hired to per (Table B) that will be allocated to contract work, and include all apprendices and include all employees including all minorities, apprentices and	prentices and on-the-job trains	ees. The "Total Employees" column
Table E	3 -	Include all employees currently employed that will be allocated to the currently employed.	ie contract work including any	apprentices and on-the-job trainees
Table 0	<b>)</b> -	Indicate the racial breakdown of the total apprentices and on-the-job	trainees shown in Table A.	
				DO 1070 (D 10/1/07)

BC-1256 (Rev. 12/11/07)

RETURN WITH BID
Contract No. 74503
CUMBERLAND-CLARK Counties
Section D7 PAVT PRSV 2011-2
Route FAI 70
District 7 Construction Funds

#### PROPOSAL SIGNATURE SHEET

The undersigned bidder hereby makes and submits this bid on the subject Proposal, thereby assuring the Department that all requirements of the Invitation for Bids and rules of the Department have been met, that there is no misunderstanding of the requirements of paragraph 3 of this Proposal, and that the contract will be executed in accordance with the rules of the Department if an award is made on this bid.

	Firm Name	
(IF AN INDIVIDUAL)	Signature of Owner	
	Firm Name	
(IF A CO-PARTNERSHIP)		
(11 /1 00 1 / 11 (11 12 13 14 14 14 14 14 14 14 14 14 14 14 14 14	Buomicoo / tudicoo	
		Name and Address of All Members of the Firm:
_		
_		
	Corporate Name	
	2,	Signature of Authorized Representative
		Typed or printed name and title of Authorized Representative
(IF A CORPORATION)		
(IF A JOINT VENTURE, USE THIS SECTION	Attest	Signature
FOR THE MANAGING PARTY AND THE		·
SECOND PARTY SHOULD SIGN BELOW)	Business Address	
	Corporate Name	
	Ву	Signature of Authorized Representative
		3
		Typed or printed name and title of Authorized Representative
(IF A JOINT VENTURE)	Attest	
		Signature
	Business Address	
If more than two parties are in the joint venture	e, please attach an ac	dditional signature sheet.

#### **Return with Bid**



Electronic Bid Bond ID#

## Division of Highways Proposal Bid Bond

Item No.

(Effective November 1, 1992)

			Letting Date
NOW ALL MEN BY THESE PRES	SENTS, That We		
s PRINCIPAL, and			
			as SURETY, ar
Article 102.09 of the "Standard S	specifications for Road and Brid	lge Construction" in effe	of 5 percent of the total bid price, or for the amount specific fect on the date of invitation for bids, whichever is the less ch we bind ourselves, our heirs, executors, administrator
			ne PRINCIPAL has submitted a bid proposal to the ment designated by the Transportation Bulletin Item Numb
nd as specified in the bidding and fter award by the Department, the ncluding evidence of the required erformance of such contract and f f the PRINCIPAL to make the requestrement the difference not to ex-	d contract documents, submit as e PRINCIPAL shall enter into disciplination in the prompt payment of laborated DBE submission or to entered the penalty hereof betweether party to perform the work of the party to perform the performance	a DBE Utilization Plan a contract in accordar roviding such bond as r and material furnishe ater into such contract a een the amount specifie	CIPAL; and if the PRINCIPAL shall, within the time in that is accepted and approved by the Department; and ince with the terms of the bidding and contract documer is specified with good and sufficient surety for the faithed in the prosecution thereof; or if, in the event of the failure and to give the specified bond, the PRINCIPAL pays to the din the bid proposal and such larger amount for which the opposal, then this obligation shall be null and void, otherwise
aragraph, then Surety shall pay the ayment within such period of time expenses, including attorney's fees	ne penal sum to the Departmer e, the Department may bring and s, incurred in any litigation in wh	nt within fifteen (15) day n action to collect the a nich it prevails either in	
neir respective officers this	day of	salu SURETT Have cau	used this instrument to be signed by  A.D.,
RINCIPAL	day of	SURET	<del></del>
(Company	Name)		(Company Name)
			(
y (Signa	ture & Title)	By:	(Signature of Attorney-in-Fact)
	Notony Contifi	action for Dringing and	J. Cromoter
TATE OF ILLINOIS, county of	Notary Certifi	cation for Principal and	a Surety
		, a Notary P	Public in and for said County, do hereby certify that
		and	, ,
	(Insert names of individuals		RINCIPAL & SURETY)
	e this day in person and acknow		cribed to the foregoing instrument on behalf of PRINCIPA that they signed and delivered said instrument as their from
Given under my hand and no	otarial seal this	day of	A.D
My commission expires			
			Notary Public
	Signature and Title line below,	the Principal is ensuring	file an Electronic Bid Bond. By signing the proposal at the identified electronic bid bond has been executed at the bid bond as shown above.

Company / Bidder Name

Signature and Title



#### **DBE Utilization Plan**

#### (1) Policy

It is public policy that disadvantaged businesses as defined in 49 CFR Part 26 and the Special Provision shall have the maximum opportunity to participate in the performance of contracts financed in whole or in part with Federal or State funds. Consequently the requirements of 49 CFR Part 26 apply to this contract.

#### (2) Obligation

Date

The contractor agrees to ensure that disadvantaged businesses as defined in 49 CFR Part 26 and the Special Provision have the maximum opportunity to participate in the performance of contracts or subcontracts financed in whole or in part with Federal or State funds. The contractor shall take all necessary and reasonable steps in accordance with 49 CFR Part 26 and the Special Provision to ensure that said businesses have the maximum opportunity to compete for and perform under this contract. The contractor shall not discriminate on the basis of race, color, national origin or sex in the award and performance of contracts.

(3) Pro	ject and Bid Identification			
Complet	te the following information concerning the project and bid:			
Route		Total Bid		<u> </u>
Section		Contract DBE Goal		
Project			(Percent)	(Dollar Amount)
County				
Letting [	Date			
Contrac	t No.			
Letting I	tem No.			
(4) Ass	surance			
	in my capacity as an officer of the undersigned bidder (or bidder my company: (check one)  Meets or exceeds contract award goals and has provided door Disadvantaged Business Participation percent  Attached are the signed participation statements, forms SBE as use of each business participating in this plan and assuring the work of the contract.  Failed to meet contract award goals and has included good far provided participation as follows:  Disadvantaged Business Participation percent  The contract goals should be accordingly modified or waived, support of this request including good faith effort. Also attached required by the Special Provision evidencing availability and use business will perform a commercially useful function in the wo	eumented participation as for 2025, required by the Speciat each business will perform the effort documentation to not attached is all information and are the signed participation of the contract.	ial Provision eving a commercian meet the goals a required by the ion statements, pating in this plant	idencing availability and lly useful function in the and that my company has Special Provision in forms SBE 2025, an and assuring that each
Bv	Company	The "as read" Low Bidder is re-		•
		Submit only one utilization plar submitted in accordance with t		
Title		Bureau of Small Business Ente 2300 South Dirksen Parkway	erprises	Local Let Projects Submit forms to the

The Department of Transportation is requesting disclosure of information that is necessary to accomplish the purpose as outlined under State and Federal law. Disclosure of this information is **REQUIRED**. Failure to provide any information will result in the contract not being awarded. This form has been approved by the State Forms Manager Center.

Springfield, Illinois 62764

Local Agency

(P)	Illinois Department of Transportation		DI	BE Participation	on Statement
	or Registration		Le	etting	
Participation	on Statement	Item No.			
(1) Instructi	ons	Contract			
be submitted	ust be completed for each disadvantaged busines d in accordance with the special provision and will bace is needed complete an additional form for the	be atta			
(2) Work					
Pay Item No.	Description		Quantity	Unit Price	Total
				Total	
	Payment Items ne above items, specifine above items, specifi	ically de	escribe the wor	k and subcontra	ct dollar
has agreed execute a constatement methat complete	ment gned certify that the information included herein is to perform a commercially useful function in the wontract with the prime contractor. The undersigned hay be made without prior approval from the Departe and accurate information regarding actual work vided to the Department.	ork of tl d furthe rtment's	he contract iten or understand the S Bureau of Sm	n(s) listed above nat no changes t nall Business Ent	and to o this erprises and
	Signature for Prime Contractor		Sign	ature for DBE Firm	
Title		Title			
Date		Date			
Contact		Conta			
Phone		Phone	e		
Firm Name		Firm N	Name		
Address		Addre			

The Department of Transportation is requesting disclosure of information that is necessary to accomplish the statutory purpose as outlined under the state and federal law. Disclosure of this information is **REQUIRED**. Failure to provide any information will result in the contract not being awarded. This form has been approved by the State Forms Management Center.

City/State/Zip

E \_\_\_\_\_

WC \_\_\_\_\_

City/State/Zi

### PROPOSAL ENVELOPE



## **PROPOSALS**

for construction work advertised for bids by the Illinois Department of Transportation

Item No.	Item No.	Item No.

#### Submitted By:

Name:	
Address:	
Phone No.	

Bidders should use an IDOT proposal envelope or affix this form to the front of a 10" x 13" envelope for the submittal of bids. If proposals are mailed, they should be enclosed in a second or outer envelope addressed to:

Engineer of Design and Environment - Room 326 Illinois Department of Transportation 2300 South Dirksen Parkway Springfield, Illinois 62764

#### **NOTICE**

Individual bids, including Bid Bond and/or supplemental information if required, should be securely stapled.

# CONTRACTOR OFFICE COPY OF CONTRACT SPECIFICATIONS

#### NOTICE

None of the following material needs to be returned with the bid package unless the special provisions require documentation and/or other information to be submitted.

Contract No. 74503 CUMBERLAND-CLARK Counties Section D7 PAVT PRSV 2011-2 Route FAI 70 District 7 Construction Funds



### SUBCONTRACTOR DOCUMENTATION

Public Acts 96-0795 and 96-0920, enacted substantial changes to the provisions of the Illinois Procurement Code (30 ILCS 500). Among the changes are provisions affecting subcontractors. The Contractor awarded this contract will be required as a material condition of the contract to implement and enforce the contract requirements applicable to subcontractors approved in accordance with article 108.01 of the Standard Specifications for Road and Bridge Construction.

If the Contractor seeks approval of subcontractors to perform a portion of the work, and approval is granted by the Department, the Contractor shall provide a copy of the subcontract to the Chief Procurement Officer within 20 calendar days after execution of the subcontract.

The subcontract shall contain the certifications required to be made by subcontractors pursuant to Article 50 of the Illinois Procurement Code. This Notice to Bidders includes a document incorporating all required subcontractor certifications and disclosures for use by the Contractor in compliance with this mandate. The document is entitled <u>State Required Ethical Standards Governing Subcontractors</u>.

### STATE ETHICAL STANDARDS GOVERNING SUBCONTRACTORS

Article 50 of the Illinois Procurement Code establishes the duty of all State chief procurement officers, State purchasing officers, and their designees to maximize the value of the expenditure of public moneys in procuring goods, services, and contracts for the State of Illinois and to act in a manner that maintains the integrity and public trust of State government. In discharging this duty, they are charged by law to use all available information, reasonable efforts, and reasonable actions to protect, safeguard, and maintain the procurement process of the State of Illinois.

The certifications hereinafter made by the subcontractor are each a material representation of fact upon which reliance is placed should the Department approve the subcontractor. The chief procurement officer may terminate or void the subcontract approval if it is later determined that the bidder or subcontractor rendered a false or erroneous certification.

Section 50-2 of the Illinois Procurement Code provides that every person that has entered into a multi-year contract and every subcontractor with a multi-year subcontract shall certify, by July 1 of each fiscal year covered by the contract after the initial fiscal year, to the responsible chief procurement officer whether it continues to satisfy the requirements of Article 50 pertaining to the eligibility for a contract award. If a contractor or subcontractor is not able to truthfully certify that it continues to meet all requirements, it shall provide with its certification a detailed explanation of the circumstances leading to the change in certification status. A contractor or subcontractor that makes a false statement material to any given certification required under Article 50 is, in addition to any other penalties or consequences prescribed by law, subject to liability under the Whistleblower Reward and Protection Act for submission of a false claim.

#### A. Bribery

1. The Illinois Procurement Code provides:

Section 50-5. Bribery.

- (a) Prohibition. No person or business shall be awarded a contract or subcontract under this Code who:
  - (1) has been convicted under the laws of Illinois or any other state of bribery or attempting to bribe an officer or employee of the State of Illinois or any other state in that officer's or employee's official capacity; or
  - (2) has made an admission of guilt of that conduct that is a matter of record but has not been prosecuted for that conduct.
- (b) Businesses. No business shall be barred from contracting with any unit of State or local government, or subcontracting under such a contract, as a result of a conviction under this Section of any employee or agent of the business if the employee or agent is no longer employed by the business and:
  - (1) the business has been finally adjudicated not guilty; or
  - (2) the business demonstrates to the governmental entity with which it seeks to contract, or which is signatory to the contract to which the subcontract relates, and that entity finds that the commission of the offense was not authorized, requested, commanded, or performed by a director, officer, or high managerial agent on behalf of the business as provided in paragraph (2) of subsection (a) of Section 5-4 of the Criminal Code of 1961.
- (c) Conduct on behalf of business. For purposes of this Section, when an official, agent, or employee of a business committed the bribery or attempted bribery on behalf of the business and in accordance with the direction or authorization of a responsible official of the business, the business shall be chargeable with the conduct.
- (d) Certification. Every bid submitted to and contract executed by the State, and every subcontract subject to Section 20-120 of the Procurement Code shall contain a certification by the contractor or the subcontractor, respectively, that the contractor or subcontractor is not barred from being awarded a contract or subcontract under this Section and acknowledges that the chief procurement officer may declare the related contract void if any certifications required by this Section are false. A contractor who makes a false statement, material to the certification, commits a Class 3 felony.
- 2. The contractor or subcontractor certifies that it is not barred from being awarded a contract under Section 50.5.

#### B. Felons

1. The Illinois Procurement Code provides:

Section 50-10. Felons. Unless otherwise provided, no person or business convicted of a felony shall do business with the State of Illinois or any State agency, or enter into a subcontract, from the date of conviction until 5 years after the date of completion of the sentence for that felony, unless no person held responsible by a prosecutorial office for the facts upon which the conviction was based continues to have any involvement with the business.

2. Certification. Every bid submitted to and contract executed by the State and every subcontract subject to Section 20-120 of the Procurement Code shall contain a certification by the bidder or contractor or subcontractor, respectively, that the bidder, contractor, or subcontractor is not barred from being awarded a contract or subcontract under this Section and acknowledges that the chief procurement officer may declare the related contract void if any of the certifications required by this Section are false.

#### C. <u>Debt Delinquency</u>

1. The Illinois Procurement Code provides:

Section 50-11 and 50-12. Debt Delinquency.

The contractor or bidder or subcontractor, respectively, certifies that it, or any affiliate, is not barred from being awarded a contract or subcontract under the Procurement Code. Section 50-11 prohibits a person from entering into a contract with a State agency, or entering into a subcontract, if it knows or should know that it, or any affiliate, is delinquent in the payment of any debt to the State as defined by the Debt Collection Board. Section 50-12 prohibits a person from entering into a contract with a State agency, or entering into a subcontract, if it, or any affiliate, has failed to collect and remit Illinois Use Tax on all sales of tangible personal property into the State of Illinois in accordance with the provisions of the Illinois Use Tax Act. The bidder or contractor or subcontractor, respectively, further acknowledges that the chief procurement officer may declare the related contract void if this certification is false or if the bidder, contractor, or subcontractor, or any affiliate, is determined to be delinquent in the payment of any debt to the State during the term of the contract.

#### D. Prohibited Bidders, Contractors and Subcontractors

1. The Illinois Procurement Code provides:

Section 50-10.5 and 50-60(c). Prohibited bidders, contractors and subcontractors.

The bidder or contractor or subcontractor, respectively, certifies in accordance with 30 ILCS 500/50-10.5 that no officer, director, partner or other managerial agent of the contracting business has been convicted of a felony under the Sarbanes-Oxley Act of 2002 or a Class 3 or Class 2 felony under the Illinois Securities Law of 1953 or if in violation of Subsection (c) for a period of five years from the date of conviction.. Every bid submitted to and contract executed by the State and every subcontract subject to Section 20-120 of the Procurement Code shall contain a certification by the bidder, contractor, or subcontractor, respectively, that the bidder, contractor, or subcontractor is not barred from being awarded a contract or subcontract under this Section and acknowledges that the chief procurement officer shall declare the related contract void if any of the certifications completed pursuant to this Section are false.

#### E. Section 42 of the Environmental Protection Act

The bidder or contractor or subcontractor, respectively, certifies in accordance with 30 ILCS 500/50-12 that the bidder, contractor, or subcontractor, is not barred from being awarded a contract or entering into a subcontract under this Section which prohibits the bidding on or entering into contracts with the State of Illinois or a State agency, or entering into any subcontract, that is subject to the Procurement Code by a person or business found by a court or the Pollution Control Board to have committed a willful or knowing violation of Section 42 of the Environmental Protection Act for a period of five years from the date of the order. The bidder or contractor or subcontractor, respectively, acknowledges that the chief procurement officer may declare the contract void if this certification is false.

The undersigned, on behalf of the subcontracting company, has read and understands the above certifications and makes the certifications as required by law.

Name of Subcontracting Company	
Authorized Officer	Date
/ tallonzed Onlock	Zulo

#### **RETURN WITH SUBCONTRACT**

#### SUBCONTRACTOR DISCLOSURES

#### I. DISCLOSURES

A. The disclosures hereinafter made by the subcontractor are each a material representation of fact upon which reliance is placed. The subcontractor further certifies that the Department has received the disclosure forms for each subcontract.

The chief procurement officer may void the bid, contract, or subcontract, respectively, if it is later determined that the bidder or subcontractor rendered a false or erroneous disclosure. A contractor or subcontractor may be suspended or debarred for violations of the Procurement Code. Furthermore, the chief procurement officer may void the contract or subcontract.

#### B. Financial Interests and Conflicts of Interest

1. Section 50-35 of the Illinois Procurement Code provides that all subcontracts with a total value of \$25,000 or more from subcontractors identified in Section 20-120 of the Illinois Procurement Code, shall be accompanied by disclosure of the financial interests of the subcontractor. This disclosed information for the subcontractor, will be maintained as public information subject to release by request pursuant to the Freedom of Information Act, filed with the Procurement Policy Board, and shall be incorporated as a material term of the Prime Contractor's contract. Furthermore, pursuant to this Section, the Procurement Policy Board may recommend to allow or void a contract or subcontract based on a potential conflict of interest.

The financial interests to be disclosed shall include ownership or distributive income share that is in excess of 5%, or an amount greater than 60% of the annual salary of the Governor, of the subcontracting entity or its parent entity, whichever is less, unless the subcontractor is a publicly traded entity subject to Federal 10K reporting, in which case it may submit its 10K disclosure in place of the prescribed disclosure. If a subcontractor is a privately held entity that is exempt from Federal 10K reporting, but has more than 400 shareholders, it may submit the information that Federal 10K companies are required to report, and list the names of any person or entity holding any ownership share that is in excess of 5%. The disclosure shall include the names, addresses, and dollar or proportionate share of ownership of each person making the disclosure, their instrument of ownership or beneficial relationship, and notice of any potential conflict of interest resulting from the current ownership or beneficial interest of each person making the disclosure having any of the relationships identified in Section 50-35 and on the disclosure form.

The current annual salary of the Governor is \$177,412.00.

In addition, all disclosures shall indicate any other current or pending contracts, subcontracts, proposals, leases, or other ongoing procurement relationships the subcontracting entity has with any other unit of state government and shall clearly identify the unit and the contract, subcontract, proposal, lease, or other relationship.

2. <u>Disclosure Forms</u>. Disclosure Form A is attached for use concerning the individuals meeting the above ownership or distributive share requirements. Subject individuals should be covered each by one form. In addition, a second form (Disclosure Form B) provides for the disclosure of current or pending procurement relationships with other (non-IDOT) state agencies.

#### C. Disclosure Form Instructions

#### Form A Instructions for Financial Information & Potential Conflicts of Interest

If the subcontractor is a publicly traded entity subject to Federal 10K reporting, the 10K Report may be submitted to meet the requirements of Form A. If a subcontractor is a privately held entity that is exempt from Federal 10K reporting, but has more than 400 shareholders, it may submit the information that Federal 10K companies are required to report, and list the names of any person or entity holding any ownership share that is in excess of 5%. If a subcontractor is not subject to Federal 10K reporting, the subcontractor must determine if any individuals are required by law to complete a financial disclosure form. To do this, the subcontractor should answer each of the following questions. A "YES" answer indicates Form A must be completed. If the answer to each of the following questions is "NO", then the NOT APPLICABLE STATEMENT on the second page of Form A must be signed and dated by a person that is authorized to execute contracts for the subcontracting company. Note: These questions are for assistance only and are not required to be completed.

1.	Does anyone in your organization have a direct or beneficial ownership share of greater than 5% of the bidding entity or parent entity? YES NO
2.	Does anyone in your organization have a direct or beneficial ownership share of less than 5%, but which has a value greater than 60% of the annual salary of the Governor? YES NO
3.	Does anyone in your organization receive more than 60% of the annual salary of the Governor of the subcontracting entity's or parent entity's distributive income? YES NO
	(Note: Distributive income is, for these purposes, any type of distribution of profits. An annual salary is not distributive income.)
4.	Does anyone in your organization receive greater than 5% of the subcontracting entity's or parent entity's total distributive income, but which is less than 60% of the annual salary of the Governor? YES NO
	(Note: Only one set of forms needs to be completed <u>per person per subcontract</u> even if a specific individual would require a yes answer to more than one question.)
	answer to any of these questions requires the completion of Form A. The subcontractor must determine each individual in the acting entity or the subcontracting entity's parent company that would cause the guestions to be answered "Yes". Each form must be

subcontracting entity or the subcontracting entity's parent company that would cause the questions to be answered "Yes". Each form must be signed and dated by a person that is authorized to execute contracts for your organization. **Photocopied or stamped signatures are not acceptable**. The person signing can be, but does not have to be, the person for which the form is being completed. The subcontractor is responsible for the accuracy of any information provided.

If the answer to each of the above questions is "NO", then the <u>NOT APPLICABLE STATEMENT</u> on page 2 of Form A must be signed and dated by a person that is authorized to execute contracts for your company.

#### Form B: Instructions for Identifying Other Contracts & Procurement Related Information

Disclosure Form B must be completed for each subcontract submitted by the subcontracting entity. Note: Checking the <u>NOT APPLICABLE</u> <u>STATEMENT</u> on Form A <u>does not</u> allow the subcontractor to ignore Form B. Form B must be completed, checked, and dated or the subcontract will not be approved.

The Subcontractor shall identify, by checking Yes or No on Form B, whether it has any pending contracts, subcontracts, leases, bids, proposals, or other ongoing procurement relationship with any other (non-IDOT) State of Illinois agency. If "No" is checked, the subcontractor only needs to complete the check box on the bottom of Form B. If "Yes" is checked, the subcontractor must list all non-IDOT State of Illinois agency pending contracts, subcontracts, leases, bids, proposals, and other ongoing procurement relationships. These items may be listed on Form B or on an attached sheet(s). Contracts with cities, counties, villages, etc. are not considered State of Illinois agency contracts and are not to be included. Contracts or subcontracts with other State of Illinois agencies such as the Department of Natural Resources or the Capital Development Board must be included.

### ILLINOIS DEPARTMENT OF TRANSPORTATION

## Form A Subcontractor: Financial Information & Potential Conflicts of Interest Disclosure

Yes \_\_\_No \_\_

Subcontractor Name		
Substitution radiic		
Legal Address		
3		
City State 7in		
City, State, Zip		
Telephone Number	Email Address	Fax Number (if available)
Tolophone Humber	Email / Idai 655	Tax Hamber (II available)

Disclosure of the information contained in this Form is required by the Section 50-35 of the Illinois Procurement Code (30 ILCS 500). Subcontractors desiring to enter into a subcontract of a State of Illinois contract must disclose the financial information and potential conflict of interest information as specified in this Disclosure Form. This information shall become part of the publicly available contract file. This Form A must be completed for subcontracts with a total value of \$25,000 or more, from subcontractors identified in Section 20-120 of the Illinois Procurement Code, and for all open-ended contracts. A publicly traded company may submit a 10K disclosure (or equivalent if applicable) in satisfaction of the requirements set forth in Form A. See Disclosure Form Instructions.

The current annual salary of the Governor is \$177,412.00.

#### DISCLOSURE OF FINANCIAL INFORMATION

1. Disclosure of Financial Information. The individual named below has an interest in the SUBCONTRACTOR (or its parent) in terms of ownership or distributive income share in excess of 5%, or an interest which has a value of more than 60% of the annual salary of the Governor. (Make copies of this form as necessary and attach a separate Disclosure Form A for each individual meeting these requirements)

FOR INDIVIDUAL (type or print infor	tion)	
NAME:		
ADDRESS		
Type of ownership/distributable in	me share:	
stock sole proprietor % or \$ value of ownership/distributal		other: (explain on separate sheet):

- **2. Disclosure of Potential Conflicts of Interest.** Check "Yes" or "No" to indicate which, if any, of the following potential conflict of interest relationships apply. If the answer to any question is "Yes", please attach additional pages and describe.
- (a) State employment, currently or in the previous 3 years, including contractual employment of services.

If your answer is yes, please answer each of the following questions.

- 2. Are you currently appointed to or employed by any agency of the State of Illinois? If you are currently appointed to or employed by any agency of the State of Illinois, and your annual salary exceeds 60% of the annual salary of the Governor, provide the name the State agency for which you are employed and your annual salary. \_\_\_\_\_\_

\_\_\_\_\_

<ol> <li>If you are currently appointed to or employed by any agency of the salary exceeds 60% of the annual salary of the Governor, are you         <ul> <li>(i) more than 7 1/2% of the total distributable income of your fir corporation, or (ii) an amount in excess of 100% of the annual sala</li> </ul> </li> </ol>	entitled to receive rm, partnership, association or
4. If you are currently appointed to or employed by any agency of the salary exceeds 60% of the annual salary of the Governor, are you or minor children entitled to receive (i) more than 15 % in the ag income of your firm, partnership, association or corporation, or (ii) the salary of the Governor?	and your spouse gregate of the total distributable
(b) State employment of spouse, father, mother, son, or daughter, including in the previous 2 years.	
If your answer is yes, please answer each of the following questions.	YesNo
1. Is your spouse or any minor children currently an officer or employ Board or the Illinois Toll Highway Authority?	ree of the Capitol Development YesNo
2. Is your spouse or any minor children currently appointed to or emportal of Illinois? If your spouse or minor children is/are currently agency of the State of Illinois, and his/her annual salary excession annual salary of the Governor, provide the name of your spouse at of the State agency for which he/she is employed and his/her annual salary.	appointed to or employed by any eds 60% of the nd/or minor children, the name
3. If your spouse or any minor children is/are currently appointed to a State of Illinois, and his/her annual salary exceeds 60% of the annual of 7/1/07) are you entitled to receive (i) more then 7 1/2% of the firm, partnership, association or corporation, or (ii) an amount annual salary of the Governor?	nual salary of the Governor, to total distributable income of your
4. If your spouse or any minor children are currently appointed to or State of Illinois, and his/her annual salary exceeds 60% of the annuare you and your spouse or minor children entitled to receive (i) aggregate of the total distributable income of your firm, partnersh (ii) an amount in excess of two times the annual salary of the Gove	ual salary of the Governor, ) more than 15 % in the ip, association or corporation, or
(c) Elective status; the holding of elective office of the State of Illinois, the government authorized by the Constitution of the State of Illin Illinois currently or in the previous 3 years.	vernment of the United States, any
(d) Relationship to anyone holding elective office currently or in the previous a son, or daughter.	2 years; spouse, father, mother, YesNo
(e) Appointive office; the holding of any appointive government office of the S America, or any unit of local government authorized by the Constitution of of the State of Illinois, which office entitles the holder to compensation in the discharge of that office currently or in the previous 3 years.	the State of Illinois or the statutes
(f) Relationship to anyone holding appointive office currently or in the previou son, or daughter.	s 2 years; spouse, father, mother, YesNo
(g) Employment, currently or in the previous 3 years, as or by any registered	lobbyist of the State government. YesNo

(11)	son, or daughter.  YesNo
(i)	Compensated employment, currently or in the previous 3 years, by any registered election or reelection committee registered with the Secretary of State or any county clerk of the State of Illinois, or any political action committee registered with either the Secretary of State or the Federal Board of Elections.  Yes No
(j)	Relationship to anyone; spouse, father, mother, son, or daughter; who was a compensated employee in the last 2 years by any registered election or re-election committee registered with the Secretary of State or any county clerk of the State of Illinois, or any political action committee registered with either the Secretary of State or the Federal Board of Elections.
	Yes No
3.	Communication Disclosure.
Se en su	close the name and address of each lobbyist and other agent of the bidder or offeror who is not identified in ction 2 of this form, who is has communicated, is communicating, or may communicate with any State officer or ployee concerning the bid or offer. This disclosure is a continuing obligation and must be promptly oplemented for accuracy throughout the process and throughout the term of the contract. If no person is ntified, enter "None" on the line below:
	Name and address of person(s):

**4. Debarment Disclosure.** For each of the persons identified under Sections 2 and 3 of this form, disclose whether any of the following has occurred within the previous 10 years: debarment from contracting with any

governmental entity; professional licensure discipline; bankruptcies; adverse civil judgments and administrative findings; and criminal felony convictions. This disclosure is a continuing obligation and must be promptly supplemented for accuracy throughout the procurement process and term of the contract. If no person is identified, enter "None" on the line below: Name of person(s): Nature of disclosure: **APPLICABLE STATEMENT** This Disclosure Form A is submitted on behalf of the INDIVIDUAL named on previous page. Under penalty of perjury, I certify the contents of this disclosure to be true and accurate to the best of my knowledge. Completed by: Signature of Individual or Authorized Officer Date NOT APPLICABLE STATEMENT Under penalty of perjury, I have determined that no individuals associated with this organization meet the criteria that would require the completion of this Form A. This Disclosure Form A is submitted on behalf of the SUBCONTRACTOR listed on the previous page. Signature of Authorized Officer Date

### ILLINOIS DEPARTMENT OF TRANSPORTATION

# Form B Subcontractor: Other Contracts & Procurement Related Information Disclosure

Subcontractor Name		
Legal Address		
City, State, Zip		
Telephone Number	Email Address	Fax Number (if available)
ILCS 500). This information shall become	part of the publicly available contra	on 50-35 of the Illinois Procurement Act (30 act file. This Form B must be completed for identified in Section 20-120 of the Illinois
DISCLOSURE OF OTHER CONTRA	CTS, SUBCONTRACTS, AND PRO	OCUREMENT RELATED INFORMATION
1. Identifying Other Contracts & Procure any pending contracts, subcontracts, includ any other State of Illinois agency: Ye If "No" is checked, the subcontractor only	ing leases, bids, proposals, or othe s No	r ongoing procurement relationship with
2. If "Yes" is checked. Identify each such information such as bid or project number (a INSTRUCTIONS:		
THE FOLLO	WING STATEMENT MUST BE CH	ECKED
	Signature of Authorized Officer	Date

## Illinois Department of Transportation

#### **NOTICE TO BIDDERS**

- 1. TIME AND PLACE OF OPENING BIDS. Sealed proposals for the improvement described herein will be received by the Department of Transportation at the Harry R. Hanley Building, 2300 South Dirksen Parkway, in Springfield, Illinois until 10:00 o'clock a.m., January 21, 2011. All bids will be gathered, sorted, publicly opened and read in the auditorium at the Department of Transportation's Harry R. Hanley Building shortly after the 10:00 a.m. cut off time.
- 2. **DESCRIPTION OF WORK**. The proposed improvement is identified and advertised for bids in the Invitation for Bids as:

Contract No. 74503 CUMBERLAND-CLARK Counties Section D7 PAVT PRSV 2011-2 Route FAI 70 District 7 Construction Funds

Microsurfacing of 2 ft. of the existing pavement centerline and replacement of pavement markings along I-70 from the Effingham/Cumberland County line to 0.3 mile west of Martinsville.

- 3. INSTRUCTIONS TO BIDDERS. (a) This Notice, the invitation for bids, proposal and letter of award shall, together with all other documents in accordance with Article 101.09 of the Standard Specifications for Road and Bridge Construction, become part of the contract. Bidders are cautioned to read and examine carefully all documents, to make all required inspections, and to inquire or seek explanation of the same prior to submission of a bid.
  - (b) State law, and, if the work is to be paid wholly or in part with Federal-aid funds, Federal law requires the bidder to make various certifications as a part of the proposal and contract. By execution and submission of the proposal, the bidder makes the certification contained therein. A false or fraudulent certification shall, in addition to all other remedies provided by law, be a breach of contract and may result in termination of the contract.
- 4. AWARD CRITERIA AND REJECTION OF BIDS. This contract will be awarded to the lowest responsive and responsible bidder considering conformity with the terms and conditions established by the Department in the rules, Invitation for Bids and contract documents. The issuance of plans and proposal forms for bidding based upon a prequalification rating shall not be the sole determinant of responsibility. The Department reserves the right to determine responsibility at the time of award, to reject any or all proposals, to readvertise the proposed improvement, and to waive technicalities.

By Order of the Illinois Department of Transportation

Gary Hannig, Secretary

### INDEX FOR SUPPLEMENTAL SPECIFICATIONS AND RECURRING SPECIAL PROVISIONS

#### Adopted January 1, 2011

This index contains a listing of SUPPLEMENTAL SPECIFICATIONS and frequently used RECURRING SPECIAL PROVISIONS.

ERRATA Standard Specifications for Road and Bridge Construction (Adopted 1-1-07) (Revised 1-1-11)

#### SUPPLEMENTAL SPECIFICATIONS

Std. Sp	pec. Sec.	<u>age No.</u>
201	Clearing, Tree Removal and Protection	
205	Embankment	
251	Mulch	
253	Planting Woody Plants	4
280	Temporary Erosion Control	6
406	Hot-Mix Asphalt Binder and Surface Course	7
420	Portland Cement Concrete Pavement	
443	Reflective Crack Control Treatment	
501	Removal of Existing Structures	15
502	Excavation for Structures	16
503	Concrete Structures	17
504	Precast Concrete Structures	
505	Steel Structures	19
508	Reinforcement Bars	20
540	Box Culverts	21
581	Waterproofing Membrane System	22
606	Concrete Gutter, Curb, Median, and Paved Ditch	23
630	Steel Plate Beam Guardrail	24
633	Removing and Reerecting Guardrail and Terminals	25
637	Concrete Barrier	26
664	Chain Link Fence	
669	Removal and Disposal of Regulated Substances	28
672	Sealing Abandoned Water Wells	29
701	Work Zone Traffic Control and Protection	30
720	Sign Panels and Appurtenances	32
721	Sign Failets and Appurentatives	33
722	Sign Panel Overlay	34
	Demountable Sign Legend Characters and Arrows	
726	Mile Post Marker Assembly	
733	Overhead Sign Structures	
780	Pavement Striping	
782	Prismatic Reflectors	
783	Pavement Marking and Marker Removal	
801	Electrical Requirements	44
805	Electrical Service Installation – Traffic Signals	
821	Roadway Luminaires	46
836	Pole Foundation	47
838	Breakaway Devices	
843	Removal of Navigational Obstruction Warning Lighting System	
862	Uninterruptable Power Supply	
873	Electric Cable	
878	Traffic Signal Concrete Foundation	54
1003	Fine Aggregates	55
1004	Coarse Aggregates	
1005	Stone and Broken Concrete	
1006	Metals	58
1008	Structural Steel Coatings	60
1010	Finely Divided Materials	65

1020	Portland Cement Concrete	66
1022	Concrete Curing Materials	77
1024	Nonshrink Grout	78
1026	Concrete Sealer	79
1030	Hot-Mix Asphalt	80
1032	Bituminous Materials	87
1042	Precast Concrete Products	90
1062	Reflective Crack Control System	92
1069	Pole and Tower	94
1074	Control Equipment	97
1076	Wire and Cable	102
1077	Post and Foundation	103
1080	Fabric Materials	105
1081	Materials for Planting	106
1083	Elastomeric Bearings	108
1090	Sign Base	109
1091	Sign Face	111
1092	Sign Legend and Supplemental Panels	119
1093	Sign Supports	120
1094	Overhead Sign Structures	122
1095	Pavement Markings	128
1097	Reflectors	136
1101	General Equipment	137
1102	Hot-Mix Asphalt Equipment	138
1103	Portland Cement Concrete Equipment	140
1105	Pavement Marking Equipment	141
1106	Work Zone Traffic Control Devices	143

#### **RECURRING SPECIAL PROVISIONS**

The following RECURRING SPECIAL PROVISIONS indicated by an "X" are applicable to this contract and are included by reference:

<u>CHE</u>	CK :	SHEET#	<u>PAGE NO.</u>
1		Additional State Requirements For Federal-Aid Construction Contracts	
		(Eff. 2-1-69) (Rev. 1-1-10)	
2		Subletting of Contracts (Federal-Aid Contracts) (Eff. 1-1-88) (Rev. 5-1-93)	
3	Χ		149
4	Χ	Specific Equal Employment Opportunity Responsibilities	
		Non Federal-Aid Contracts (Eff. 3-20-69) (Rev. 1-1-94)	
5	Χ	Required Provisions - State Contracts (Eff. 4-1-65) (Rev. 1-1-10)	164
6		Reserved	169
7		Reserved	170
8		Haul Road Stream Crossings, Other Temporary Stream Crossings, and	
		In-Stream Work Pads (Eff. 1-2-92) (Rev. 1-1-98)	171
9		Construction Layout Stakes Except for Bridges (Eff. 1-1-99) (Rev. 1-1-07)	
10		Construction Layout Stakes (Eff. 5-1-93) (Rev. 1-1-07)	175
11		Use of Geotextile Fabric for Railroad Crossing (Eff. 1-1-95) (Rev. 1-1-07)	178
12		Subsealing of Concrete Pavements (Eff. 11-1-84) (Rev. 1-1-07)	
13		Hot-Mix Asphalt Surface Correction (Eff. 11-1-87) (Rev. 1-1-09)	184
14		Pavement and Shoulder Resurfacing (Eff. 2-1-00) (Rev. 1-1-09)	
15		PCC Partial Depth Hot-Mix Asphalt Patching (Eff. 1-1-98) (Rev. 1-1-07)	187
16		Patching with Hot-Mix Asphalt Overlay Removal (Eff. 10-1-95) (Rev. 1-1-07)	189
17		Polymer Concrete (Eff. 8-1-95) (Rev. 1-1-08)	
18		PVC Pipeliner (Eff. 4-1-04) (Rev. 1-1-07)	192
19		Pipe Underdrains (Eff. 9-9-87) (Rev. 1-1-07)	193
20		Guardrail and Barrier Wall Delineation (Eff. 12-15-93) (Rev. 1-1-97)	194
21		Bicycle Racks (Eff. 4-1-94) (Rev. 1-1-07)	
22		Temporary Modular Glare Screen System (Eff. 1-1-00) (Rev. 1-1-07)	200
23		Temporary Portable Bridge Traffic Signals (Eff. 8-1-03) (Rev. 1-1-07)	202
24	Χ		
25		Night Time Inspection of Roadway Lighting (Eff. 5-1-96)	205
26		English Substitution of Metric Bolts (Eff. 7-1-96)	206
27		English Substitution of Metric Reinforcement Bars (Eff. 4-1-96) (Rev. 1-1-03)	207
28		Calcium Chloride Accelerator for Portland Cement Concrete (Eff. 1-1-01)	208
29		Reserved	209
30		Quality Control of Concrete Mixtures at the Plant	
		(Eff. 8-1-00) (Rev. 1-1-11)	210
31		Quality Control/Quality Assurance of Concrete Mixtures	
		(Eff. 4-1-92) (Rev. 1-1-11)	218
32		Asbestos Bearing Pad Removal (Eff. 11-1-03)	230
33		Ashestos Hot-Mix Asphalt Surface Removal (Eff. 6-1-89) (Rev. 1-1-09)	231

#### **TABLE OF CONTENTS**

LOCATION OF PROJECT	1
DESCRIPTION OF PROJECT	1
TRAFFIC CONTROL PLAN	1
BORROW AREAS, USE AREAS, AND/OR WASTE AREAS	2
LONGITUDINAL JOINT REPAIR	2
PREVENTIVE MAINTENANCE - MICRO-SURFACING JOINT REPAIR	6
URETHANE PAVEMENT MARKING	16
APPROVAL OF PROPOSED BORROW AREAS, USE AREAS, AND/OR WASTE AREAS (BD	E)20
CONSTRUCTION AIR QUALITY - DIESEL VEHICLE EMISSIONS CONTROL (BDE)	21
CONSTRUCTION AIR QUALITY - IDLING RESTRICTIONS (BDE)	22
DISADVANTAGED BUSINESS ENTERPRISE PARTICIPATION (BDE)	23
EQUIPMENT RENTAL RATES (BDE)	30
LIQUIDATED DAMAGES (BDE)	31
NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM / EROSION AND	SEDIMENT
CONTROL DEFICIENCY DEDUCTION (BDE)	31
PAYMENTS TO SUBCONTRACTORS (BDE)	
POST MOUNTING OF SIGNS (BDE)	34
RAISED REFLECTIVE PAVEMENT MARKERS (BDE)	34
SELECTION OF LABOR (BDE)	34
SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE)	35
TRUCK MOUNTED/TRAILER MOUNTED ATTENUATORS (BDE)	35
WORKING DAYS (BDE)	35

#### STATE OF ILLINOIS

#### SPECIAL PROVISIONS

The following Special Provisions supplement the "Standard Specifications for Road and Bridge Construction," adopted January 1, 2007, the latest edition of the "Manual on Uniform Traffic Control Devices for Streets and Highways," and the "Manual of Test Procedures for Materials" in effect on the date of invitation for bids, and the Supplemental Specifications and Recurring Special Provisions indicated on the Check Sheet included herein which apply to and govern the construction of FAI Route 70 (I-70), D7 Pavt Prsv 2011-2 in Cumberland and Clark Counties, Contract No. 74503 and in case of conflict with any part or parts of said Specifications, the said Special Provisions shall take precedence and shall govern.

#### **LOCATION OF PROJECT**

The proposed project begins at the Effingham/Cumberland County line and continues along I-70 to 0.3 mile west of Martinsville in Clark County.

#### **DESCRIPTION OF PROJECT**

The work included in this section consists of 57.1 lane miles of micro-surfacing a 2' wide path of existing interstate centerline, replacing all pavement markings and any other work necessary to complete this section.

#### TRAFFIC CONTROL PLAN

Traffic Control shall be in accordance with the applicable sections of the Standard Specifications for Road and Bridge Construction, the applicable guidelines contained in the Illinois Manual on Uniform Traffic Control Devices for Streets and Highways, these Special Provisions, and any special details and Highway Standards contained herein and in the plans.

Special attention is called to Articles 107.09, 107.14 and 107.15 of the Standard Specifications for Road and Bridge Construction, the following Highway Standards and Recurring Special Provisions relating to traffic control:

701101 701400 701406 701426 701901

Standard 701101: This standard shall be used where at any time, any vehicle, equipment, workers or their activities will encroach in the area 15' to 24" from the edge of pavement. A typical application for this standard is sign installation and maintenance.

Standard 701400: This standard shall be used where at any time a lane is closed on a freeway/expressway. A typical application for this standard is micro-surfacing.

Standard 701406: This standard shall be used where at any time, any vehicle, equipment, workers or their activities will encroach on the lane adjacent to the shoulder, or on the shoulder within 24" of the edge of pavement for daylight operation. This standard must always be used in combination with standard 701400.

A typical application for this standard is micro-surfacing, removal of existing pavement markings and application of short-term pavement markings. It is intended for this work to be done by closing the passing lane.

Standard 701426: This standard shall be used where any vehicle, equipment, workers or their activities will require: 1) stationary operations up to 1 hour, or 2) a continuous or intermittent moving operation where the average speed of movement is greater than 1 mph. A typical application for this standard is pavement marking.

#### **BORROW AREAS, USE AREAS, AND/OR WASTE AREAS**

Effective: November, 2009

In addition to the provisions contained in Article 107.22 of the Standard Specifications, any required submittal(s) to the District office shall require four (4) copies sent for processing. All copies of pictures submitted shall be in color.

#### LONGITUDINAL JOINT REPAIR

Effective June 1, 2010

Interstate centerline cracks wider than 1 ½" and/or deeper than 1 ½", including depressions resulting from the removal of existing raised reflective pavement markers, shall be patched with bituminous premix as specified below.

- 1. DESCRIPTION. The patching material shall be composed of a mineral aggregate, plant-mixed with a liquid asphalt and chemical additives from the suppliers of the proprietary mixtures. The bituminous material shall be capable of coating wet aggregates without stripping, and shall be available in various grades so that one such grade will enable a stockpile to remain pliable and workable at a temperature of -26 °C (-15 °F). The patching material shall be capable of maintaining adhesive qualities in patched areas which are damp or wet at time of application, and also after remaining in an uncovered stockpile for up to twelve (12) months.
- 2. MATERIALS. Control of the materials shall be in accordance with the general requirements of Section 106 of the current Standard Specifications for Road and Bridge Construction. If required, a five kilogram (ten-pound) sample of the mineral aggregate and one-liter (one-quart) sample of the liquid asphalt shall be submitted to the Bureau of Materials and Physical Research, 126 East Ash Street, Springfield, Illinois, for performing the tests specified herein.

#### (a) Aggregate

All Coarse Aggregate used in the proprietary mixtures shall consist of crushed stone of Class B quality or better as defined in Article 1004.01(a) & (b) of the above cited Standard Specifications.

#### (b) Bituminous Materials

The bituminous material shall be a formulation of the liquid asphalt blend prepared under the supervision of the proprietary mix supplier. It shall meet the requirements of ASTM D 2026 or ASTM 2027, whichever applies, modified as follows:

ASTM D 2042 Solubility in Trichloroethylene 99.0	ASTM D 113 Ductility 4 °C (39 °F) 1cm/min, cm minimum 85	ASTM D 113 Ductility 21 °C (70 °F) 1cm/min cm minimum	ASTM D 5 Penetration, modified with cone, 25 °C (77 °F) 200 150 g, 5s minimum	25 °C (77 °F)	Residue Tests:  ASTM D 2171 Absolute Viscosity 60 °C(140 °F) Pascal Seconds (Poisses) ASTM D 2 (Department	Residue from distillation to 360 °C (680 °F) 70-94 % Volume by Difference	ASTM D 402 Distillate % by Volume of Original Sample Temperature Distillate to 225 °C (437 °F) Ustillate to 250 °C (500 °F) Ustillate to 315 °C (600 °F) 0-21	ASTM D 95 Water % - maximum 0.2	ASTM D 2170 Kinematic Viscosity 60 °C (140 °F) mm <sup>3</sup> /s (cSt) 350-3000	ASTMD 92 Flash point (COC) °C (°F) - minimum	OPTIMIX
99.0	100	I	ı	200	12.5-42.5 (125-425)	72-95	0 0-5 0-25	0.2	300.4000	94 (200)	QPR-2000
99.0	l	100	180	ı	12.542.5 (125425)	ı	0 0-5 0-25	02	300-4000	94 (200)	SYLCRETE EV
99.0	I	000	180	ı	12.5-42.5 (125-425)	ı	0 0-5 0-25	0.2	300-4000	94 (200)	SYLCRETE VA
99.0	100	ı	180	I	12.5-42.5 (125-425)	73-95	0 0-5 0-18	0.2	400-2500	94 (200)	UPM
99.0	100	100	180	I	12.0-42.5 (120-425)	70-95	0 0-5 8-50	ı	280-400 (cPs)	94 (200)	EZ STREET
99.0	100	ı	1	200	12.5-42.5 (125-425)	72-95	0 0-5 0-25	0.2	300-4000	94 (200)	SMP
99.0	100	I	1	200	12.5-42.5 (125-425)	72-95	0 U-5 0-25	0.2	300-4000	94 (200)	ALL WEATHER
99.9	100	I	I	300	12.5 <b>-4</b> 2.5 (125 <b>-4</b> 25)	80-90	0 U-U 0-55	0.1	400-500	121 (250)	PROLINE

#### (c) Stripping Tests

The combined UPM and liquid asphalt shall meet the following stripping tests:

(1) Stripping Tests: Dry Aggregate. Two-hundred grams of the air-dried aggregate passing the 12.5 mm (½-inch) sieve and retained on the 4.75 mm (No. 4) sieve shall be combined with 6.3 percent, by weight, UPM liquid asphalt and mixed in a hemispherical metal dish with a stiff spatula for three to five minutes or until a uniform coating is obtained. Twenty-five grams of this material shall be immediately place in an oven at 60 °C  $\pm$  3 °C (140 °F  $\pm$  5 °F), for eighteen to twenty-four hours, after which it shall be thoroughly mixed and allowed to cool to room temperature.

The sample shall then be immersed in water at a temperature of 49  $^{\circ}$ C  $\pm$  3  $^{\circ}$ C (120  $^{\circ}$ F  $\pm$  5  $^{\circ}$ F), and maintained at this temperature for twenty-four hours. At the end of this period, the area of the aggregate remaining coated shall be determined visually while the sample is still immersed in water. Surface coating of at least 90 percent must be retained on the aggregate. A test similar to the above using MC-250 shall be made for comparison.

(2) Stripping Test: Wet Aggregate. Two-hundred grams of the aggregate passing the 12.5 mm (½-inch) sieve and retained on the 4.75 mm (No. 4) sieve shall be immersed in water for twenty-four hours and the excess water drained off, leaving the aggregate surface wet. This aggregate shall be combined with 6.3 percent, by weight, UPM liquid asphalt and mixed in a hemispherical metal dish with a stiff liquid spatula for three to five minutes or until a uniform coating is obtained. Twenty-five grams of this material shall be immediately place in an oven at 60 °C  $\pm$  3 °C (140 °F  $\pm$  5 °F), for eighteen to twenty-four hours, after which it shall be thoroughly mixed and allowed to cool to room temperature. The sample shall then be immersed in water at a temperature of 49 °C  $\pm$  3 °C (120 °F  $\pm$  5 °F), and maintained at this temperature for twenty-four hours. At the end of this period, the area of the aggregate remaining coated shall be determined visually while the sample is still immersed in water. Surface coating of at least 90 percent must be retained on the aggregate. A test similar to the above using MC-250 shall be made for comparison. In estimating the percentage of area remaining coated, any thin or translucent area shall not be considered as being coated.

Proprietary mixes, Sylcrete EV, Sylcrete VA, Optimix, QPR-2000, EZ Street, SMP, Sakrete All Weather, and Proline shall meet the following stripping tests.

- (1) Place 50 grams of cold mix into a beaker containing 400 ml of boiling distilled water. Bring back to boiling and boil for 3 minutes with constant stirring at 1 revolution per second. At the end of 3 minutes, remove the beaker from the heat source and immediately decant the water. Empty the wet mix onto a paper towel and examine. The retained coating shall not be less than 95 percent.
  - (2) AASHTO T 182-06 Coating and Stripping of Bitumen-Aggregate Mixtures.
- (3) INSPECTION. The Engineer or his authorized representative shall have access at any time to all parts of the plant in order to verify weights or proportions and quality of materials used in the preparation of the mixture. The manufacturer shall afford such facilities as may be required for making inspection at the plant and for collecting and forwarding samples of the ingredient materials and bituminous mixture to the Department.
- (4) PLANT AND EQUIPMENT. Storage facilities and all equipment used in the preparation of the mixture shall be approved by the Department. An approved drier shall be available for surface drying the aggregate when needed. The materials for individual batches shall be measured accurately, either by volume or weight, by approved methods and equipment. A batch type mixer of approved design and capacity shall be used in mixing the ingredient materials. However, approval for the use of a continuous mixer will be given if it can be shown that satisfactory results will be obtained.
- (5) PREPARATION OF MIXTURE. The aggregate and Optimix, or QPR-2000, or Sylcrete, or UPM, or EZ Street, or SMP liquid asphalt shall be proportioned into the mixer and mixed for at least 30 seconds or until a uniformly coated mixture is obtained. The liquid asphalt shall be heated to a temperature of 93 °C  $\pm$  28 °C (200° F  $\pm$  50° F), at the time of mixing, and in accordance with the instructions of proprietary mix supplier. When necessary to heat the aggregates, the aggregates should not be heated to more than 68 °C (155 °F).

(6) COMPOSITION OF MIXTURE. The ingredients shall be combined to produce a mixture meeting the approval of the Department and conforming to the following composition limits, by weight, as determined by tests of the prepared mixture:

<sup>™</sup>Based on percent of total aggregate weight. <sup>™</sup>Based on percent of total mixture weight.

		250	OI GL	a long	Lyndon	M Aggre	Agre ( /o	Gladanon of Extracted Aggregate (% Fassing)				
SIEVE SIZE		SYLC EV AI	SYLCRETE EV AND VA	QPR- 2000	<u>_</u>	UPM	EZSI	EZSTREET	ls.	SMP	SAKRETE	PROLINE
	OPTIMIX	MIX #1	MIX#2		MIX #1	MIX #2	MIX #1	MIX #2	MIX #1	MIX #2	WEATHER	
12.5 mm (1/2")	100	100	100	100	100	100	100	100	100	100	100	100
9.5 mm (3/8")	90-100	100	90-100	90-100	90-100	100	90-100	95-100	100	90-100	90-100	100
4.75 mm (No. 4)	20-55	85-100	20-55	20-55	15-55	70-100	20-55	80-100	85-100	20-55	20-55	70-100
		;	3	2			2	2	;	3	3	
2.30 HIII ( NO. 0)	0-00	10-40	0-00	0-00			00-00	9-10	04-01	0-00	0-00	20-40
1.18 mm (No. 16)	0-10	0-10	0-10	0-10	0-10	0-10	0-10	0-10	0-10	0-10	0-10	10-30
		:	:									
600 µm (No. 30)		0-/	7-0					0-10				0-25
300 µm (No. 50)	0-5	0-5	0-5	0-5			0-5	0-10	0-5	0-5	0-5	0-20
75 µm (No. 200)	0-2	0-2.5	0-2.5	0-2	0-4	0-4	0-3	1.5-3.5	0-4	0-4	0-2	0-5
Residual Biturnen	3-6.5	3-6.5	3-6.5	3-7.0	3.5-6.5 3.5-6.5	3.5-6.5	3-7	3-7	3.5-7.0	3.5-7.0	3-7.0	4.0-6.0

7. LEGAL RELATIONS AND RESPONSIBILITY TO PUBLIC. The laws to be observed; permits and licenses; patented devices; materials, and processes; and responsibility for damage claims, shall be in accordance with the requirements of Section 107 of the above cited Standard Specifications.

#### **CONSTRUCTION REQUIREMENTS**

These areas shall be cleaned of all loose and unsound material with pneumatic tools, or other approved equipment, and filled with the bituminous mixture specified herein. The mixture shall be hand tamped in place with hand tools and/or wheel-rolled to the satisfaction of the Engineer.

BASIS OF PAYEMENT. This work will be paid for at the contract unit price per ton for LONGITUDINAL JOINT REPAIR.

#### PREVENTIVE MAINTENANCE - MICRO-SURFACING JOINT REPAIR

<u>Description</u>. This work shall consist of micro-surfacing hot-mix asphalt (HMA) surfaces 2 ft (0.6 m) wide to fill areas of raveling and depressions and/or provide a wearing surface 12 in (0.3 m) wide on each side of a longitudinal joint.

Materials. Materials shall be according to the following.

(a) Micro-Surfacing. Materials shall be according to the following Articles/Sections of the Standard Specifications.

Item	Article/Section
(1) Mineral Filler (Note 1)	1001
(2) Water	1002
(3) Fine Aggregate (Note 2)	1003.03
(3) Coarse Aggregate (Note 2)	
(4) Bituminous Material (Prime Coat)	1032.06
(5) Latex-Modified Emulsified Asphalt (Note 3)	
(6) Additives (Note 4)	

Note 1. The mineral filler shall be Type 1 portland cement.

Note 2. The aggregate material shall be 100 percent crushed material and shall be crushed stone, crushed sandstone, crushed steel slag, crushed air-cooled blast furnace slag, or crushed gravel. The quality of the aggregate shall be Class B and the gradation shall be as shown in the table below.

Sieve Size	Type II % Passing	Type III % Passing 1/	
3/8 in. (9.5 mm)	100	100	
#4 (4.75 mm)	$95\pm5$	80 ± 10	
#8 (2.36 mm)	77 ± 13	57 ± 13	
#16 (1.18 mm)	57 ± 13	39 ± 11	
#30 (600 µm)	40 ± 10	26 ± 8	
#50 (330 µm)	$24\pm 6$	18 ± 7	
#100 (150 μm)	15 ± 6	12 ± 6	
#200 (75 μm)	10 ± 5	10 ± 5	

<sup>1/</sup> All surface mixes shall be constructed using a Type II gradation.

To assure the material is totally crushed, 100 percent of the parent aggregate shall be larger than the largest stone in the gradation to be used.

The blending, alternate use, and/or substitutions of aggregates from different sources for use in this work will not be permitted without the approval of the Engineer. Any blending shall be by interlocked mechanical feeders. The blending shall be uniform, compatible with the other components of the mix, and the equipment shall be approved by the Engineer.

If blending aggregates, the blend shall have a washed gradation performed every other day or a minimum of three tests per week. Testing shall be completed before the aggregate receives final acceptance for use in the mix. All gradation tests shall be conducted according to the Aggregate Gradation Control System (AGCS).

Aggregates shall be screened at the stockpile prior to delivery to the paving machine to remove oversized material or contaminants.

Note 3. CSS-1h Latex Modified Emulsified Asphalt. The emulsified asphalt shall be a quick-traffic latex modified asphalt emulsion containing a minimum of 3.0 percent latex solids by weight of asphalt binder. The latex shall be milled or blended into the emulsifier solution prior to the emulsification process. The CSS-1h latex modified emulsified asphalt shall be according to the following.

Test (AASHTO T 59)	Result
Viscosity, Saybolt Furol, 77 °F (25 °C), SFS	20-100
Storage Stability Test, 24 hours, %	1 max.
Particle Charge Test	Positive
Sieve Test, No. 20 (850 µm), retained on sieve, %	0.10 max.
Distillation Test, Residue from distillation test to	62 min.
347 ± 9 F (175 ± 5 C), %	

Tests on residue from distillation	Result
Penetration, 77 °F (25 °C), 100 grams, 5 seconds, (AASHTO T 49), dmm	40-90
Ductility, 77 °F (25 °C), 50 mm/min, (AASHTO T 51), mm	400 min.
Solubility in trichloroethylene, (AASHTO T 44), %	97.5 min.
Softening Point, (AASHTO T 53), °F (°C)	135 (57) min.
Absolute Viscosity, 140 °F (60 °C),	8,000 (800)
(AASHTO T 202), Poises (Pa · sec)	min.

Note 4. Additives may be added to the emulsion mix or any of the component materials to provide the control of the quick-traffic properties. They shall be included as part of the mix design and be compatible with the other components of the mix.

(b) Crack/Joint Sealant. The crack/joint sealant shall be a fiber-modified asphalt binder mixed at the jobsite or premixed.

- (1) Jobsite-Mixed Sealant. The sealant shall consist of an asphalt binder and fibers, and be according to the following.
  - a. Asphalt Binder. The asphalt binder shall be PG 58-28, PG 58-22, or PG 64-22 and meet the requirements of Article 1032.05 of the Standard Specifications.
  - b. Fibers. Fibers shall be short cut polypropylene fibers meeting the properties listed below. The fiber may be accepted on certification from the manufacturer that it meets the specified requirements.

Property	Value	
Length, in. (mm)	0.3 - 0.5 (8 - 12)	
Denier	13 - 16	
Crimps	None	
Tensile Strength, min., psi (kPa)	40,000 (275,000)	
Specific Gravity (typical)	0.91	
Moisture Regain @ 70 °F (21 °C) and 65% RH (typical), %	0.1	

- c. Percent Fibers. The sealant shall contain a minimum of 8.0 percent of fibers by weight (mass).
- d. Sealant Heating. The sealant shall be heated in the kettle at temperatures between 255 and 285 °F (124 and 141 °C).
- (2) Premixed Sealant. The sealant shall be packaged and consist of an asphalt binder, fibers, and other modifiers meeting the following requirements. The sealant and its components may be accepted on certification from the manufacturer that it meets the specified requirements.
  - a. Asphalt Binder. The asphalt binder shall be PG 64-22 and meet the requirements of Article 1032.05 of the Standard Specifications.
  - b. Fibers. Fibers shall be short cut polyester fibers meeting the following.

Property	Value	
Length, in. (mm)	$0.25 \pm 0.02 (6.3 \pm 0.5)$	
Denier	3 - 6	
Crimps	None	
Tensile Strength, minimum, psi (kPa)	70,000 (482,000)	
Specific Gravity (typical)	1.32 - 1.40	
Elongation at Break, %	35 - 38	
Melt Temperature, °F (°C)	475 - 490 (246 - 254)	

c. Percent Fibers. The sealant shall contain  $5.0 \pm 0.5$  percent of fibers by weight (mass).

The sealant, in its final form, shall meet the following requirements when sampled and heated to the manufacturer's recommended maximum heating temperature according to ASTM D 5167.

Test	Value	
Cone Penetration @ 77 °F (25 °C),		
ASTM D 5329	10-35 dmm	
Softening Point, ASTM D 36	175 °F (79 °C) min.	
Maximum Heating Temperature	400°F (204 °C)	
Application Temperature	350°F (177 °C) min.	

Equipment. Equipment shall be according to the following.

- (a) Micro-Surfacing. Equipment shall be according to the following.
  - (1) Micro-Surfacing Mixing Machine. The machine shall be either a continuous (self-loading) machine or a non-continuous (self-contained) machine depending on the size of the project as described below. Both types of machines shall have sufficient storage capacity for aggregate, emulsified asphalt, mineral filler, control additive and water to maintain an adequate supply to the proportioning controls.

Machines that are the continuous (self-loading) type shall be an automatic-sequenced, self-propelled, continuous-flow mixing unit able to accurately deliver and proportion the aggregate, emulsified asphalt, mineral filler, control setting additive, and water to a revolving multi-blade, double-shafted mixer and to discharge the mixed product on a continuous-flow basis. The machine shall be equipped to allow the operator to have full control of the forward and reverse speeds during applications of the material and be equipped with opposite-side driver stations to assist in alignment.

Non-continuous (self-contained) machines will be allowed on projects with a length of 2 lane-miles (3.2 lane-km) or less. For mainline paving, the Contractor shall have at least three self-contained machines in continuous operation to ensure appropriate production rates. Self-contained machines will also be allowed on shoulders, ramps, short applications such as bridge decks, or where the material can be placed in a single loading capacity of the machine.

Each mixing unit to be used in the performance of the work shall be calibrated in the presence of the Engineer prior to construction. Each new or different aggregate requires a new calibration. Previous calibration documentation covering the exact materials to be used may be acceptable, provided that no more than 30 days have lapsed. The documentation shall include an individual calibration of each material at various settings, which can be related to the machine metering devices. Prior to the calibration process, portable scales used to calibrate the mixing machine for emulsion and aggregate shall be checked with 25 lb and 50 lb weights, respectively. Results from the standard weight checks shall be furnished to the Engineer. No machine will be allowed to work on the project until the calibration has been completed and/or accepted.

(2) Micro-Surfacing Spreader. The mixture shall be agitated and spread uniformly in the surfacing box by means of twin shafted paddles or spiral augers fixed in the spreader box. A front seal shall be provided to insure no loss of the mixture at the road contact point. The rear seal shall act as a final strike-off and shall be adjustable.

The spreader box and rear strike-off shall be so designed and operated that a uniform consistency is achieved to produce a free flow of material to the rear strike-off. The spreader box shall have suitable means provided to side shift the box to compensate for variations in the pavement geometry.

A secondary strike-off shall be provided to improve surface texture on the surface course. The secondary strike-off shall have the same adjustments as the spreader box and shall not bounce, wobble, or chatter.

When required on the plans, before the final surface course is placed, preliminary micro-surfacing material may be required to fill areas of raveling and depressions in the existing surface. Those areas that are 1 1/2 in. (38 mm) or greater in depth shall be filled independently with a scratch-coat pass utilizing a spreader box. The scratch-coat pass shall be 2 ft (0.6 m) in width and completed in a manner that will leave only trace material on the surface adjacent to the areas to be filled. All scratch-coat material should cure for a minimum of 2 hours before the final surface course is placed.

- (3) Micro-Surfacing Proportioning Devices. Individual volume or weight controls for proportioning each material to be added to the mix (i.e. aggregate, mineral filler, emulsified asphalt, additive, and water) shall be provided and properly marked. These proportioning devices are used in material calibration and determining the material output at any time. Calibration records, conversion formulas, and daily run sheets including the beginning and final numbers shown on the proportioning devices shall be submitted to the Engineer for approval. During production any deviations from the original mix design shall be approved by the Engineer.
- (b) Crack/Joint Sealing. Equipment shall be according to the following.
  - (1) Air Compressor. The air compressor shall be capable of producing a minimum pressure of 90 psi (620 kPa) at the end of the discharge hose. The air stream shall discharge onto the pavement through an appropriate air lance. The tool lubricator shall be bypassed and a filter installed on the discharge valve to keep water and oil out of the line.
  - (2) Oil Kettle. The crack sealant shall be heated in an oil jacketed double wall kettle equipped with an agitator (reversing rotary auger action) and separate thermometers for the oil bath and mixing chamber. The unit shall also be equipped with a reversible hydraulic 2 in. (50 mm) hot asphalt pump and a recirculating pump to circulate the oil bath.

#### CONSTRUCTION REQUIREMENTS

<u>General</u>. The paving mixture shall be capable of filling up to 1 1/2 in. (38 mm) areas of raveling and depressions in one pass, be capable of field regulation of the setting time, and be suitable for nighttime placement. The compatibility of all ingredients of the mix, including the mix set additive, shall be certified by the emulsified asphalt manufacturer.

Weather Limitations. Placement of the micro-surfacing shall be done between May 1 and October 15, and when the temperature is at least 50 °F (10 °C) and rising and the forecast for the next 24 hours is above 40 °F (5 °C).

<u>Mix Design</u>. A Contractor provided laboratory shall develop the mix design for the microsurfacing mixture, shall verify the functioning of the set regulating additives, and shall present certified test results for the Engineer's approval. This laboratory shall be recognized by the International Slurry Surfacing Association (ISSA) as being capable of performing mix designs. The Engineer will verify the laboratory tests required in ISSA A143 have been conducted.

Proportions for the mix design shall be within the following limits.

Mineral Aggregate, dry weight (mass) lb/sq yd (kg/sq m)	15-50 (8-30)
Latex Emulsified Asphalt Residue, % by wt. of Aggregate	5.5-10.5
Latex Base Modifier	As required with % by weight (mass) of binder, min. of 3.0
Mix Set Additive	As required
Mineral Filler,	0.25 - 3 depending on weather
% by weight (mass) of Aggregate	conditions

The amount of mineral filler needed shall be determined by the laboratory mix design and will be considered as part of the aggregate gradation.

The amount and type of latex shall be determined by the laboratory performing the mix design. The minimum amount required shall be based on asphalt weight content and shall be certified by the emulsion supplier.

Compatibility of the aggregate, latex-modified emulsified asphalt, mineral filler, and other additives shall be verified by the mix design. The materials shall meet the following requirements for ISSA A143.

ISSA Test No.	Description	Specification
ISSA TB-139	Wet Cohesion	
	@ 30 minutes min. (Set)	12 kg-cm min.
	@ 60 minutes min. (Traffic)	20 kg-cm min. or Near Spin
ISSA TB-109	Excess Asphalt by LWT Sand Adhesion	50 gm/sq ft (538 gm/sq m) max.
ISSA TB-114	Wet Stripping	Pass (90% min.)
ISSA TB-100	Wet-Track Abrasion Loss	
	One-hour Soak	50 gm/sq ft (538 gm/sq m) max.
	Six-day Soak	75 gm/sq ft (807 gm/sq m) max.
ISSA TB-147	Lateral Displacement	5% max.
	Specific Gravity after 1,000 Cycles of 25 lb (11.34 kg)	2.10 max.
ISSA TB-144	Classification Compatibility	11 Grade Points min.
		(AAA, BAA)
ISSA TB-113	Mix Time @ 77 °F (25 °C)	Controllable to 120 seconds Min.

The mixing test and set-time test shall be checked at the highest temperatures expected during construction.

The mix design shall report the quantitative effects of moisture content on the unit weight of the aggregate (bulking effect). The report shall clearly show the proportions of aggregate, mineral filler (minimum and maximum), water (minimum and maximum), additive usage, and latex-modified asphalt emulsion based on the dry weight of the aggregate.

For the aggregate blend in the mix design, test results for AASHTO T 176 shall be provided with the mix information to the Engineer. Aggregate test values below 65 shall require review and approval from the Engineer.

A minimum of seven days prior to the work commencing, the Contractor shall submit to the Engineer a complete mix design covering the specific materials to be used on the project. The percentages of each individual material required shall be shown in the laboratory report. The Engineer shall approve the mix design prior to its use. After approval, no substitutions will be permitted, unless approved by the Engineer, and the Contractor shall maintain continuous control of the latex-modified emulsified asphalt to dry aggregate proportioning to conform to the approved mix design within a tolerance of  $\pm 2$  gal/ton ( $\pm 8$  L/metric ton).

<u>Test Strip</u>. A minimum of seven days prior to the work commencing, the Contractor shall designate a mutually agreeable location within the project to apply a test strip. The test strip shall be 1,000 ft (305 m) in length and shall be applied using the approved mix design. The test strip shall be applied a minimum of 24 hours prior to work commencing to allow the Engineer to evaluate the application rate, cure time, and durability.

<u>Surface Preparation</u>. Pavement markings shall be removed according to Article 783.03(a) of the Standard Specifications. Only very small particles of tightly adhering existing markings may remain in place.

When specified in the plans, pavement markers shall be removed according to Article 783.03(b) of the Standard Specifications.

When specified in the plans, Bumps greater than or equal to 1/2 in. (13 mm) shall be removed by grinding. The Contractor shall determine bump grinding locations in the presence of the Engineer by using a 16-ft (5-m) straightedge with the scratcher bolts set to 1/2 in. (13 mm). All locations marked by the scratcher bolts shall be ground using either a grinding machine consisting of multiple saws or a cold-milling machine with a double- or triple-wrap milling head.

When specified in the plans, Joints and cracks 3/16 in. (5 mm) or wider shall be cleaned of loose and unsound material and sealed. The sealant shall be applied only when the joints and cracks are clean and dry, and the ambient temperature is 40-85 °F (4-29 °C). The sealant shall be applied using a pressurized wand delivery system with such devices as necessary to seal the cracks/joints and form a nominal 0.125 in. (3 mm) thick by 3 in. (75 mm) wide overseal band centered so that the center of the 3 in. (75 mm) wide band is within 1 in. (25 mm) of the crack. The sealant shall be allowed to cure before opening to traffic. When approved by the Engineer, the sealant may be dusted with fine sand, portland cement, or mineral filler to prevent tracking.

Micro-Surfacing. The micro-surfacing shall be applied as shown on the plans and the following.

(a) Preparation. Prior to applying the micro-surfacing, the pavement surface, and joints and cracks that were not sealed, shall be cleaned of loose and unsound material with an air compressor. On highly oxidized surfaces, a prime coat shall be applied at a rate of 0.05-0.10 gal/sq yd (0.22-0.45 L/sq m) according to Article 406.05(b) of the Standard Specifications. Manholes, valve boxes, drop inlets, and other service entrances shall be protected from the micro-surfacing by a suitable method. The surface preparation shall be approved by the Engineer prior to the application of the micro-surfacing. No dry aggregate either spilled from the lay-down machine or existing on the road will be permitted.

The Contractor shall apply the micro-surfacing according to the following methods.

- (1) Scratch-Coat Filling. When specified in the plans, this method shall consist of filling areas of raveling and depressions using the specially designed spreaderbox. It shall be the Contractor's responsibility to determine and estimate the quantities of fill mix required for scratch-coat filling. This work is then followed by one pass of microsurfacing as described below.
- (2) Micro-Surfacing, Single Pass. This method shall consist of applying the surface mix 2 ft (0.6 m) wide over the longitudinal joint in one pass using the gradation and application rate shown on the plans.

Determinations of application rates shall be from daily readings taken from the material control devices during the progress of the work.

The pavement surface shall be prewetted by water fogging ahead of the spreader box when road conditions require, as determined by the Engineer. The rate of fogging shall be adjusted during the day based on pavement temperature, surface texture, and dryness.

The paving mixture shall be spread to fill minor cracks and shallow potholes and leave a uniform surface. Care shall be taken to maintain the designed profile of the pavement cross section. A sufficient amount of material shall be carried at all times in all parts of the spreader box to ensure complete coverage. Overloading of the spreader shall be avoided. No lumps or uncoated aggregate will be permitted in the finished surface.

Adjustments to the mix design may be required during construction, based on field conditions. The percent of mineral filler in the mix design may be increased or decreased by less than 0.3 percent when the slurry seal is being placed if it is found to be necessary for better consistency or set times. The Engineer will give final approval for all adjustments.

- (b) Mix Consistency. The finished product shall be uniform in color and composition. No streaks, such as those caused by oversized aggregate, shall be left in the finished surface. If excess streaking develops, the job will be stopped until the Contractor proves to the Engineer that the situation has been corrected. Excessive streaking is defined as more than four drag marks greater than 1/2 in. (13 mm) wide and 4 in. (100 mm) long, or 1 in. (25 mm) wide and 3 in. (75 mm) long, in any 30 sq yd (25 sq m) area. No transverse ripples or longitudinal streaks of 0.25 in. (6 mm) in depth will be permitted, when measured by placing a 10 ft (3 m) straightedge over the surface.
- (c) Mix Stability. The micro-surfacing shall possess sufficient stability so that premature breaking of the material in the spreader box does not occur. The mixture shall be homogeneous during and following mixing and spreading. It shall be free of excess water or emulsified asphalt and free of segregation of the emulsified asphalt and aggregate fines from the coarser aggregate. Under no circumstances shall water be sprayed directly into the lay-down box while placing micro-surfacing material.
- (d) Joints and Edges. Micro-surfacing edges shall be parallel with the existing longitudinal joint. If the existing longitudinal joint cannot be used to give a straight edge, a stringline or other guide will be required.

Edge lines shall not vary by more than  $\pm$  1 in. (25 mm) horizontally in any 100 ft (30 m) of length.

A smooth, neat seam shall be provided where two passes meet. Excess material shall be immediately removed from the ends of each run. Any damage to, or irregularities in, the micro-surfacing shall be repaired, as directed by the Engineer. All repairs shall be made with a spreader box, except areas designated as hand work areas.

(e) Hand Work. Those areas inaccessible to the spreader box and approved by the Engineer shall be designated as hand work areas. Adjustments to the additive will be permitted to provide a slower setting time when hand spreading is needed. If hand spreading is necessary, the mixture shall be poured in a small windrow along one edge of the surface to be covered and then spread uniformly by a hand squeegee or lute. Hand work areas shall have an appearance consistent with that being placed with a spreader box.

<u>Clean-Up</u>. All areas, such as manholes, gutters, and intersections, shall have the microsurfacing mix removed as specified by the Engineer. The Contractor shall, on a daily basis, remove any debris associated with the performance of the work.

<u>Sampling and Testing</u>. The Contractor shall check yield of the application after the first 1000 ft (300 m), and throughout each day's paving, with a minimum of three tests per day. Yield check results shall be furnished to the Engineer daily.

The Contractor shall submit a daily "run sheet" for each day's work as soon as all the data is available. The run sheet shall provide a breakdown of the actual meter numbers and quantities of all materials actually used each day, as well as the respective locations.

Opening to Traffic. The micro-surfacing shall have a minimum one hour cure time before being allowed to be opened to traffic.

<u>Curing</u>. The micro-surfacing shall cure for a minimum of 7 days before placement of the permanent pavement markings.

Method of Measurement. This work will be measured for payment as follows.

- (a) Contract Quantities. The requirements for the use of contract quantities shall conform to Article 202.07(a) of the Standard Specifications.
- (b) Measured Quantities. Crack/Joint sealing will be measured for payment in pounds, based on actual quantities used.

Pavement marking removal will be measured for payment according to Article 783.05 of the Standard Specifications.

The micro-surfacing will be measured according to the following for the method of application provided in the plans.

(1) Micro-surfacing Scratch-Coat Filling. Micro-surfacing scratch-coat filling will be measured for payment in place in feet (meters) along the longitudinal joint.

(2) Micro-surfacing, Single Pass. Micro-surfacing, single pass will be measured for payment in place and the area computed in square yards (square meters). The width for measurement will be the width of the top surface. No additional compensation will be made for micro-surfacing placed wider than 2 ft (0.6 m).

Prime coat, when required, will be measured for payment according to Article 406.13(b) of the Standard Specifications.

<u>Basis of Payment</u>. Crack/joint sealing will be paid for at the contract unit price per pound of FIBER ASPHALT.

Bump removal will be paid for at the contract unit price per each for BUMP REMOVAL.

Pavement marking removal and pavement marker removal will be paid for according to Article 783.06 of the Standard Specifications.

Scratch-coat filling will be paid for at the contract unit price per foot (meter) for MICRO-SURFACING SCRATCH-COAT FILLING.

Micro-surfacing, single pass will be paid for at the contract unit price per square yard (square meter) for MICRO-SURFACING, SINGLE PASS, of the type specified.

Prime coat, when required, will be paid for according to Article 406.14 of the Standard Specifications.

Test strip will be evaluated for payment at the contract unit price each for MICRO-SURFACING TEST STRIP, according to the following:

- (a) If the micro-surfacing placed during the initial test strip is determined to be acceptable, the micro-surfacing and test strip will be paid for at the contract unit prices.
- (b) If the micro-surfacing placed during the initial test strip (1) is determined to be unacceptable to remain in place by the Engineer, and (2) was not produced in accordance with the approved mix design, the initial micro-surfacing and test strip will not be paid for and shall be removed at the Contractor's expense. An additional test strip will be paid for in full, if produced within the approved mix design.
- (c) If the micro-surfacing placed during the initial test strip (1) is determined to be unacceptable to remain in place by the Engineer, and (2) was produced in accordance with the with the approved mix design, the micro-surfacing shall be removed. Removal will be paid for according to Article 109.04 of the Standard Specifications. This initial micro-surfacing and test strip will be paid for at the contract unit prices. The additional micro-surfacing will be paid for at the contract unit price, and any additional test strips will be paid for at one half the unit price of each test strip.
- (d) If the micro-surfacing placed during a test strip is determined to be acceptable to remain in place by the Engineer and the Engineer deems a new start-up is required for any reason, the initial micro-surfacing and test strip will be paid for at the contract unit prices. The additional micro-surfacing will be paid for at the contract unit price and any additional test strips will be paid for at one-half the unit price for each test strip.

(e) If the Contractor requests and is granted approval for a mix design other than the initial approved mix design, he/she shall construct a test strip for the new mix design at no additional cost to the Department.

#### **URETHANE PAVEMENT MARKING**

Effective March 25, 2005

<u>Description:</u> This work shall consist of furnishing and applying a reflectorized modified urethane, plural component, durable liquid pavement marking lines, sizes and colors as shown on the plans.

Materials: All materials shall meet the following specifications:

- (a) Modified Urethane Marking: The modified urethane pavement marking material shall consist of a homogeneous blend of modified urethane resins and pigments designed to provide a simple volumetric mixing ratio of two components (must be two volumes of Part A to one volume of Part B). No volatile solvent or fillers will be allowed.
- (b) Pigmentation: The pigment content by weight of Component A shall be determined by low temperature ashing according to ASTM D 3723. The pigment content shall not vary more than plus or minus two percent from the pigment content of the original qualified paint.

White Pigment shall be Titanium Dioxide meeting ASTM D 476 Type II, Rutile.

Yellow Pigment shall be Organic Yellow and contain no heavy metals.

- (c) Environmental: Upon heating to application temperature, the material shall not exude fumes, which are toxic or injurious to persons or property when handled according to manufacturer specifications. The modified urethane pavement marking material compositions shall not contain free isocyanate functionality.
- (d) Daylight Reflectance: The daylight directional reflectance of the cured modified urethane material (without reflective media) shall be a minimum of 80 percent (white) and 50 percent (yellow) relative to magnesium oxide when tested using a color spectrophotometer with a 45 degree circumferential / zero degrees geometry, illuminant C, and two degrees observer angle. The color instrument shall measure the visible spectrum from 380 to 720 nm with a wavelength measurement interval and spectral bandpass of 10 nm. In addition, the color of the yellow modified urethane shall visually match Color Number 33538 of Federal Standard 595a with chromaticity limits as follows:

Х	0.490	0.475	0.485	0.539
У	0.470	0.438	0.425	0.456

(e) Weathering Resistance: The modified urethane, when mixed in the proper ratio and applied at 0.35 to 0.41 mm (14 to 16 mils) wet film thickness to an aluminum alloy panel (Federal Test Std. No. 141, Method 2013) and allowed to cure for 72 hours at room temperature, shall be subjected to accelerated weathering for 75 hours. The accelerated weathering shall be completed by using the light and water exposure apparatus (fluorescent UV – condensation type) and tested according to ASTM G 53.

The cycle shall consist of four hours UV exposure at 50 °C (122 °F) and four hours of condensation at 40 °C (104 °F). UVB 313 bulbs shall be used. At the end of the exposure period, the material shall show no substantial change in color or gloss.

- (f) Drying Time: The modified urethane material, when mixed in the proper ratio and applied at 0.35 to 0.41 mm (14 to 16 mils) wet film thickness and with the proper saturation of glass spheres, shall exhibit a no-tracking time of three minutes or less when tested according to ASTM D 711.
- (g) Adhesion: The catalyzed modified urethane pavement marking materials when applied to a 100 x 100 x 50 mm (4 x 4 x2 in) concrete block shall have a degree of adhesion which results in a 100 percent concrete failure in the performance of this test. The concrete block shall be brushed on one side and have a minimum strength of 24,100 kPa (3,500 psi). A 50 mm (2 in) square film of the mixed modified urethane shall be applied to the brushed surface and allowed to cure for 72 hours at room temperature. A 50 mm (2 in) square cube shall be affixed to the surface of the modified urethane by means of an epoxy glue. After the glue has cured for 24 hours, the modified urethane specimen shall be placed on a dynamic testing machine in such a fashion so that the specimen block is in a fixed position and the 50 mm (2 in) cube (glued to the modified urethane surface) is attached to the dynamometer head. Direct upward pressure shall be slowly applied until the modified urethane system fails. The location of the break and the amount of concrete failure shall be recorded.
- (h) Hardness: The modified urethane marking materials, when tested according to ASTM D-2240, shall have a Shore D Hardness greater than 75. Films shall be cast on a rigid substrate at 0.35 to 0.41 mm (14 to 16 mils) in thickness and allowed to cure at room temperature for 72 hours before testing.
- (i) Abrasion: The abrasion resistance shall be evaluated on a Taber Abrader with a 1,000 gram load and CS-17 wheels. The duration of test shall be 1,000 cycles. The wear index shall be calculated based on ASTM test method D-4060 and the wear index for the catalyzed material shall not be more than 80. The tests shall be run on cured samples of modified urethane material which have been applied at a film thickness of 0.35 to 0.41 (14 to 16 mils) to code S-16 stainless steel plates. The films shall be allowed to cure at room temperature for at least 72 hours and not more than 96 hours before testing.
- (j) Tensile: When tested according to ASTM D-638, the modified urethane pavement marking materials shall have an average tensile strength of not less than 6,000 pounds per square inch. The Type IV Specimens shall be pulled at a rate of ½" per minute by a suitable dynamic testing machine. The samples shall be allowed to cure at 75 °F± 2°F for a minimum of 24 hours and a maximum of 72 hours prior to performing the indicated tests.
- (k) Compressive Strength: When tested according to ASTM D-695, the catalyzed modified urethane pavement marking materials shall have a compressive strength of not less than 12,000 pounds per square inch. The cast sample shall be conditioned at 75°F± 2°F for a minimum of 72 hours before performing the indicated tests. The rate of compression of these samples shall be no more than ½"per minute.
- (I) Glass Spheres: The glass spheres shall meet the requirements of Article 1095.04(m) and Article 1095.07 of the Standard Specifications for first drop and second drop glass beads.

- (m) The material shall be shipped to the job site in substantial containers and shall be plainly marked with the manufacturer's name and address, the name and color of the material, date of manufacture and batch number.
- (n) Prior to approval and use of the modified urethane pavement marking materials, the manufacturer shall submit a notarized certification of an independent laboratory, together with the results of all tests, stating these materials meet the requirements as set forth herein. The certification test report shall state the lot tested, manufacturer's name, brand name of modified urethane and date of manufacture. The certification shall be accompanied by one half-liter (one-pint) samples each of Part A and Part B. Samples shall be sent in the appropriate volumes for complete mixing of Part A and Part B.

After approval by the Department, certification by the modified urethane manufacturer shall be submitted for each batch used. New independent laboratory certified test results and samples for testing by the Department shall be submitted any time the manufacturing process or paint formulation is changed. All costs of testing (other than tests conducted by the Department) shall be borne by the manufacturer.

- (o) Acceptance samples shall consist of one half-liter (one-pint) samples of Part A and Part B, of each lot of paint. Samples shall be sent in the appropriate volumes for complete mixing of Part A and Part B. The samples shall be submitted to the Department for testing, together with a manufacturer's certification. The certification shall state the formulation for the lot represented is essentially identical to that used for qualification testing. All, acceptance samples shall be taken by a representative of the Illinois Department of Transportation. The modified urethane pavement marking materials shall not be used until tests are completed and they have met the requirements as set forth herein.
- (p) The manufacturer shall retain the test sample for a minimum of 18 months.

#### APPLICATION EQUIPMENT

The modified urethane pavement marking compounds shall be applied through equipment specifically designed to precisely meter the two components in the ratio of 2:1 and approved by the manufacturer of the material. This equipment shall produce the required amount of heat at the mixing head and gun tip and maintain those temperatures within the tolerances specified. This equipment shall also have as an integral part of the gun carriage, a high pressure air spray capable of cleaning the pavement immediately prior to the marking application.

The equipment shall be capable of spraying both yellow and white urethane, according to the manufacturer's recommended proportions and be mounted on a truck of sufficient size and stability with an adequate power source to produce lines of uniform dimensions and prevent application failure. The truck shall have at least two urethane tanks each of 415 L (110 gal) minimum capacity and shall be equipped with hydraulic systems. It shall be capable of placing stripes on the left and right sides and placing two lines on a three-line system simultaneously with either line in a solid or intermittent pattern, in yellow or white, and applying glass beads by the double drop pressurized bead system. The system shall apply both the first drop glass beads and the second drop glass beads at a rate of 1.2 kg per L (10 lb/gal). The equipment shall be equipped with pressure gauges for each proportioning pump. All guns shall be in full view of operators at all times. The equipment shall have a metering device to register the accumulated installed quantities for each gun, each day.

Each vehicle shall include at least one operator who shall be a technical expert in equipment operations and urethane application techniques. Certification of equipment shall be provided at the preconstruction conference.

#### APPLICATION

The pavement shall be cleaned by a method approved by the Engineer to remove all dirt, grease, glaze or any other material that would reduce the adhesion of the markings with minimum or no damage to the pavement. New PCC pavements shall be blast-cleaned to remove all curing compounds.

Markings shall be applied to the cleaned surfaces on the same calendar day. If this cannot be accomplished, the surface shall be re-cleaned prior to applying the markings. Existing pavement markings shall be at least 90 percent removed. No markings shall be applied until the Engineer approves the cleaning.

Widths, lengths and shapes of the cleaned surface shall be prepared wider then the modified urethane pavement marking material to be applied, such that a prepared area is on all sides of the urethane pavement marking material after application.

New asphalt concrete and seal coated surfaces shall be in place a minimum of two weeks prior to marking applications.

The cleaning operation shall be a continuous moving operation process with minimum interruption to traffic.

The pavement markings shall be applied to the cleaned road surface, during conditions of dry weather and subsequently dry pavement surfaces at a minimum uniform wet thickness of 20 mils in accordance with the manufacturer's installation instructions and at the widths and patterns shown on the contract plans. The application and combination of reflective media (glass beads and/or reflective elements) shall be applied at a rate specified by the manufacturer. At the time of installation the pavement surface temperature shall be 40 ° F and rising and the ambient temperature shall be 35° F and rising. The pavement surface temperature and the ambient temperatures shall be determined and documented before the start of each of marking operation. The pavement markings shall not be applied if the pavement shows any visible signs of moisture or it is anticipated that damage causing moisture, such as rain showers, may occur during the installation and curing periods. The Engineer shall determine the atmospheric conditions and pavement surface conditions that produce satisfactory results.

Unless directed by the Engineer, lines shall not be laid directly over a longitudinal crack or joint. The edge of the center line or lane line shall be offset a minimum distance of 50 mm (2 inches) from a longitudinal crack or joint. Edge lines shall be approximately 50 mm (2 inches) from the edge of pavement. The finished center and lane lines shall be straight, with the lateral deviation of any 3 meter (10-foot) line not to exceed 25 mm (1 inch).

#### **Notification:**

The Contractor shall notify the Engineer 72 hours prior to the placement of the markings in order that an inspector can be present during the operation.

At the time of this notification, the Contractor shall indicate the manufacturer and lot numbers of urethane and reflective media that he intends to use. The Engineer will ensure that the approved lot numbers appear on the material package. Failure to comply with this provision may be cause for rejection.

The Contractor shall provide an accurate temperature-measuring device(s) that shall be capable of measuring the pavement temperature prior to application of the material, the material temperature at the gun tip and the material temperature prior to mixing.

#### Inspection:

The urethane pavement markings will be inspected following installation, but no later than December 15, and inspected following a winter performance period that extends 180 days from December 15 in accordance with the provisions of Article 780.10 of the Standard Specification for Road and Bridge Construction.

#### Method of Measurement:

The lines will be measured for payment in feet of urethane pavement marking lines applied and accepted, measured in place. Double yellow lines will be measured as two separate lines. Words and symbols shall conform to the size and dimensions specified in the Manual on Uniform Traffic Control Devices and Standard 780001 and will be measured based on total areas indicated in table 1 or as specified in the plans.

#### Basis of Payment:

This work will be paid for at the contract unit prices per foot of applied line for URETHANE PAVEMENT MARKING - LINE 4, 5, 6, 8, 12, 24 inches or per square foot URETHANE PAVEMENT MARKING - LETTERS AND SYMBOLS measured as specified herein.

### APPROVAL OF PROPOSED BORROW AREAS, USE AREAS, AND/OR WASTE AREAS (BDE)

Effective: November 1, 2008 Revised: November 1, 2010

Replace the first paragraph of Article 107.22 of the Standard Specifications with the following:

"All proposed borrow areas, including commercial borrow areas; use areas, including, but not limited to temporary access roads, detours, runarounds, plant sites, and staging and storage areas; and/or waste areas are to be designated by the Contractor to the Engineer and approved prior to their use. Such areas outside the State of Illinois shall be evaluated, at no additional cost to the Department, according to the requirements of the state in which the area lies; and approval by the authority within that state having jurisdiction for such areas shall be forwarded to the Engineer. Such areas within Illinois shall be evaluated as described herein.

A location map delineating the proposed borrow area, use area, and/or waste area shall be submitted to the Engineer for approval along with an agreement from the property owner granting the Department permission to enter the property and conduct cultural and biological resource reconnaissance surveys of the site for archaeological resources, threatened or endangered species or their designated essential habitat, wetlands, prairies, and savannahs.

The type of location map submitted shall be a topographic map, a plat map, or a 7.5 minute quadrangle map. Submittals shall include the intended use of the site and provide sufficient detail for the Engineer to determine the extent of impacts to the site. The Engineer will initiate cultural and biological resource reconnaissance surveys of the site, as necessary, at no cost to the Contractor. The Engineer will advise the Contractor of the expected time required to complete all surveys. If the proposed area is within 150 ft (45 m) of the highway right-of-way, a topographic map of the proposed site will be required as specified in Article 204.02."

#### CONSTRUCTION AIR QUALITY - DIESEL VEHICLE EMISSIONS CONTROL (BDE)

Effective: April 1, 2009 Revised: July 1, 2009

<u>Diesel Vehicle Emissions Control</u>. The reduction of construction air emissions shall be accomplished by using cleaner burning diesel fuel. The term "equipment" refers to any and all diesel fuel powered devices rated at 50 hp and above, to be used on the project site in excess of seven calendar days over the course of the construction period on the project site (including any "rental" equipment).

All equipment on the jobsite, with engine ratings of 50 hp and above, shall be required to: use Ultra Low Sulfur Diesel fuel (ULSD) exclusively (15 ppm sulfur content or less).

Diesel powered equipment in non-compliance will not be allowed to be used on the project site, and is also subject to a notice of non-compliance as outlined below.

The Contractor shall submit copies of monthly summary reports and include certified copies of the ULSD diesel fuel delivery slips for diesel fuel delivered to the jobsite for the reporting time period, noting the quantity of diesel fuel used.

If any diesel powered equipment is found to be in non-compliance with any portion of this specification, the Engineer will issue the Contractor a notice of non-compliance and identify an appropriate period of time, as outlined below under environmental deficiency deduction, in which to bring the equipment into compliance or remove it from the project site.

Any costs associated with bringing any diesel powered equipment into compliance with these diesel vehicle emissions controls shall be considered as included in the contract unit prices bid for the various items of work involved and no additional compensation will be allowed. The Contractor's compliance with this notice and any associated regulations shall also not be grounds for a claim.

<u>Environmental Deficiency Deduction</u>. When the Engineer is notified, or determines that an environmental control deficiency exists, he/she will notify the Contractor in writing, and direct the Contractor to correct the deficiency within a specified time period. The specified time-period, which begins upon Contractor notification, will be from 1/2 hour to 24 hours long, based on the urgency of the situation and the nature of the deficiency. The Engineer shall be the sole judge regarding the time period.

The deficiency will be based on lack of repair, maintenance and diesel vehicle emissions control.

If the Contractor fails to correct the deficiency within the specified time frame, a daily monetary deduction will be imposed for each calendar day or fraction thereof the deficiency continues to exist. The calendar day(s) will begin when the time period for correction is exceeded and end with the Engineer's written acceptance of the correction. The daily monetary deduction will be \$1,000.00 for each deficiency identified.

If a Contractor or subcontractor accumulates three environmental deficiency deductions in a contract period, the Contractor will be shutdown until the deficiency is corrected. Such a shutdown will not be grounds for any extension of contract time, waiver of penalties, or be grounds for any claim.

#### **CONSTRUCTION AIR QUALITY - IDLING RESTRICTIONS (BDE)**

Effective: April 1, 2009

Idling Restrictions. The Contractor shall establish truck-staging areas for all diesel powered vehicles that are waiting to load or unload material at the jobsite. Staging areas shall be located where the diesel emissions from the equipment will have a minimum impact on adjacent sensitive receptors. The Department will review the selection of staging areas, whether within or outside the existing highway right-of-way, to avoid locations near sensitive areas or populations to the extent possible. Sensitive receptors include, but are not limited to, hospitals, schools, residences, motels, hotels, daycare facilities, elderly housing and convalescent facilities. Diesel powered engines shall also be located as far away as possible from fresh air intakes, air conditioners, and windows. The Engineer will approve staging areas before implementation.

Diesel powered vehicle operators may not cause or allow the motor vehicle, when it is not in motion, to idle for more than a total of 10 minutes within any 60 minute period, except under any of the following circumstances:

- 1) The motor vehicle has a gross vehicle weight rating of less than 8000 lb (3630 kg).
- 2) The motor vehicle idles while forced to remain motionless because of on-highway traffic, an official traffic control device or signal, or at the direction of a law enforcement official.
- 3) The motor vehicle idles when operating defrosters, heaters, air conditioners, or other equipment solely to prevent a safety or health emergency.
- 4) A police, fire, ambulance, public safety, other emergency or law enforcement motor vehicle, or any motor vehicle used in an emergency capacity, idles while in an emergency or training mode and not for the convenience of the vehicle operator.
- 5) The primary propulsion engine idles for maintenance, servicing, repairing, or diagnostic purposes if idling is necessary for such activity.
- 6) A motor vehicle idles as part of a government inspection to verify that all equipment is in good working order, provided idling is required as part of the inspection.
- 7) When idling of the motor vehicle is required to operate auxiliary equipment to accomplish the intended use of the vehicle (such as loading, unloading, mixing, or processing cargo; controlling cargo temperature; construction operations, lumbering operations; oil or gas well servicing; or farming operations), provided that this exemption does not apply when the vehicle is idling solely for cabin comfort or to operate non-essential equipment such as air conditioning, heating, microwave ovens, or televisions.
- 8) When the motor vehicle idles due to mechanical difficulties over which the operator has no control.
- 9) The outdoor temperature is less than 32 °F (0 °C) or greater than 80 °F (26 °C).

When the outdoor temperature is greater than or equal to 32 °F (0 °C) or less than or equal to 80 °F (26 °C), a person who operates a motor vehicle operating on diesel fuel shall not cause or allow the motor vehicle to idle for a period greater than 30 minutes in any 60 minute period while waiting to weigh, load, or unload cargo or freight, unless the vehicle is in a line of vehicles that regularly and periodically moves forward.

The above requirements do not prohibit the operation of an auxiliary power unit or generator set as an alternative to idling the main engine of a motor vehicle operating on diesel fuel.

<u>Environmental Deficiency Deduction</u>. When the Engineer is notified, or determines that an environmental control deficiency exists based on non-compliance with the idling restrictions, he/she will notify the Contractor, and direct the Contractor to correct the deficiency.

If the Contractor fails to correct the deficiency a monetary deduction will be imposed. The monetary deduction will be \$1,000.00 for each deficiency identified.

#### DISADVANTAGED BUSINESS ENTERPRISE PARTICIPATION (BDE)

Effective: September 1, 2000 Revised: January 1, 2010

<u>FEDERAL OBLIGATION</u>. The Department of Transportation, as a recipient of federal financial assistance, is required to take all necessary and reasonable steps to ensure nondiscrimination in the award and administration of contracts. Consequently, the federal regulatory provisions of 49 CFR part 26 apply to this contract concerning the utilization of disadvantaged business enterprises. For the purposes of this Special Provision, a disadvantaged business enterprise (DBE) means a business certified by the Department in accordance with the requirements of 49 CFR part 26 and listed in the Illinois Unified Certification Program (IL UCP) DBE Directory.

STATE OBLIGATION. This Special Provision will also be used by the Department to satisfy the requirements of the Business Enterprise for Minorities, Females, and Persons with Disabilities Act, 30 ILCS 575. When this Special Provision is used to satisfy state law requirements on 100 percent state-funded contracts, the federal government has no involvement in such contracts (not a federal-aid contract) and no responsibility to oversee the implementation of this Special Provision by the Department on those contracts. DBE participation on 100 percent state-funded contracts will not be credited toward fulfilling the Department's annual overall DBE goal required by the US Department of Transportation to comply with the federal DBE program requirements.

<u>CONTRACTOR ASSURANCE</u>. The Contractor makes the following assurance and agrees to include the assurance in each subcontract that the Contractor signs with a subcontractor:

The Contractor, subrecipient, or subcontractor shall not discriminate on the basis of race, color, national origin, or sex in the performance of this contract. The Contractor shall carry out applicable requirements of 49 CFR part 26 in the award and administration of contracts funded in whole or in part with federal or state funds. Failure by the Contractor to carry out these requirements is a material breach of this contract, which may result in the termination of this contract or such other remedy as the recipient deems appropriate.

OVERALL GOAL SET FOR THE DEPARTMENT. As a requirement of compliance with 49 CFR part 26, the Department has set an overall goal for DBE participation in its federally assisted contracts.

That goal applies to all federal-aid funds the Department will expend in its federally assisted contracts for the subject reporting fiscal year. The Department is required to make a good faith effort to achieve the overall goal. The dollar amount paid to all approved DBE companies performing work called for in this contract is eligible to be credited toward fulfillment of the Department's overall goal.

CONTRACT GOAL TO BE ACHIEVED BY THE CONTRACTOR. This contract includes a specific DBE utilization goal established by the Department. The goal has been included because the Department has determined that the work of this contract has subcontracting opportunities that may be suitable for performance by DBE companies. This determination is based on an assessment of the type of work, the location of the work, and the availability of DBE companies to do a part of the work. The assessment indicates that, in the absence of unlawful discrimination, and in an arena of fair and open competition, DBE companies can be expected to perform 6.00% of the work. This percentage is set as the DBE participation goal for this contract. Consequently, in addition to the other award criteria established for this contract, the Department will only award this contract to a bidder who makes a good faith effort to meet this goal of DBE participation in the performance of the work. A bidder makes a good faith effort for award consideration if either of the following is done in accordance with the procedures set forth in this Special Provision:

- (a) The bidder documents that enough DBE participation has been obtained to meet the goal; or
- (b) The bidder documents that a good faith effort has been made to meet the goal, even though the effort did not succeed in obtaining enough DBE participation to meet the goal.

<u>DBE LOCATOR REFERENCES</u>. Bidders may consult the IL UCP DBE Directory as a reference source for DBE-certified companies. In addition, the Department maintains a letting and item specific DBE locator information system whereby DBE companies can register their interest in providing quotes on particular bid items advertised for letting. Information concerning DBE companies willing to quote work for particular contracts may be obtained by contacting the Department's Bureau of Small Business Enterprises at telephone number (217)785-4611, or by visiting the Department's web site at www.dot.il.gov.

<u>BIDDING PROCEDURES</u>. Compliance with this Special Provision is a material bidding requirement. The failure of the bidder to comply will render the bid not responsive.

- (a) The bidder shall submit a Disadvantaged Business Utilization Plan on Department forms SBE 2025 and 2026 with the bid.
- (b) The Utilization Plan shall indicate that the bidder either has obtained sufficient DBE participation commitments to meet the contract goal or has not obtained enough DBE participation commitments in spite of a good faith effort to meet the goal. The Utilization Plan shall further provide the name, telephone number, and telefax number of a responsible official of the bidder designated for purposes of notification of plan approval or disapproval under the procedures of this Special Provision.
- (c) The Utilization Plan shall include a DBE Participation Commitment Statement, Department form SBE 2025, for each DBE proposed for the performance of work to achieve the contract goal. For bidding purposes, submission of the completed SBE 2025 forms, signed by the DBEs and faxed to the bidder will be acceptable as long as the original is available and provided upon request.

All elements of information indicated on the said form shall be provided, including but not limited to the following:

- (1) The names and addresses of DBE firms that will participate in the contract;
- (2) A description, including pay item numbers, of the work each DBE will perform;
- (3) The dollar amount of the participation of each DBE firm participating. The dollar amount of participation for identified work shall specifically state the quantity, unit price, and total subcontract price for the work to be completed by the DBE. If partial pay items are to be performed by the DBE, indicate the portion of each item, a unit price where appropriate and the subcontract price amount;
- (4) DBE Participation Commitment Statements, form SBE 2025, signed by the bidder and each participating DBE firm documenting the commitment to use the DBE subcontractors whose participation is submitted to meet the contract goal;
- (5) If the bidder is a joint venture comprised of DBE companies and non-DBE companies, the plan must also include a clear identification of the portion of the work to be performed by the DBE partner(s); and,
- (6) If the contract goal is not met, evidence of good faith efforts.

GOOD FAITH EFFORT PROCEDURES. The contract will not be awarded until the Utilization Plan submitted by the apparent successful bidder is approved. All information submitted by the bidder must be complete, accurate and adequately document the good faith efforts of the bidder before the Department will commit to the performance of the contract by the bidder. The Utilization Plan will be approved by the Department if the Utilization Plan commits sufficient commercially useful DBE work performance to meet the contract goal or the bidder submits sufficient documentation of a good faith effort to meet the contract goal pursuant to 49 CFR part 26, Appendix A. The Utilization Plan will not be approved by the Department if the Utilization Plan does not commit sufficient DBE participation to meet the contract goal unless the apparent successful bidder documented in the Utilization Plan that it made a good faith effort to meet the goal. This means that the bidder must show that all necessary and reasonable steps were taken to achieve the contract goal. Necessary and reasonable steps are those which, by their scope, intensity and appropriateness to the objective, could reasonably be expected to obtain sufficient DBE participation, even if they were not successful. The Department will consider the quality, quantity, and intensity of the kinds of efforts that the bidder has made. Mere pro forma efforts, in other words, efforts done as a matter of form, are not good faith efforts; rather, the bidder is expected to have taken genuine efforts that would be reasonably expected of a bidder actively and aggressively trying to obtain DBE participation sufficient to meet the contract goal.

- (a) The following is a list of types of action that the Department will consider as part of the evaluation of the bidder's good faith efforts to obtain participation. These listed factors are not intended to be a mandatory checklist and are not intended to be exhaustive. Other factors or efforts brought to the attention of the Department may be relevant in appropriate cases, and will be considered by the Department.
- (1) Soliciting through all reasonable and available means (e.g. attendance at pre-bid meetings, advertising and/or written notices) the interest of all certified DBE companies that have the capability to perform the work of the contract.

The bidder must solicit this interest within sufficient time to allow the DBE companies to respond to the solicitation. The bidder must determine with certainty if the DBE companies are interested by taking appropriate steps to follow up initial solicitations.

- (2) Selecting portions of the work to be performed by DBE companies in order to increase the likelihood that the DBE goals will be achieved. This includes, where appropriate, breaking out contract work items into economically feasible units to facilitate DBE participation, even when the prime Contractor might otherwise prefer to perform these work items with its own forces.
- (3) Providing interested DBE companies with adequate information about the plans, specifications, and requirements of the contract in a timely manner to assist them in responding to a solicitation.
- (4) a. Negotiating in good faith with interested DBE companies. It is the bidder's responsibility to make a portion of the work available to DBE subcontractors and suppliers and to select those portions of the work or material needs consistent with the available DBE subcontractors and suppliers, so as to facilitate DBE participation. Evidence of such negotiation includes the names, addresses, and telephone numbers of DBE companies that were considered; a description of the information provided regarding the plans and specifications for the work selected for subcontracting; and evidence as to why additional agreements could not be reached for DBE companies to perform the work.
- b. A bidder using good business judgment would consider a number of factors in negotiating with subcontractors, including DBE subcontractors, and would take a firm's price and capabilities as well as contract goals into consideration. However, the fact that there may be some additional costs involved in finding and using DBE companies is not in itself sufficient reason for a bidder's failure to meet the contract DBE goal, as long as such costs are reasonable. Also, the ability or desire of a bidder to perform the work of a contract with its own organization does not relieve the bidder of the responsibility to make good faith efforts. Bidders are not, however, required to accept higher quotes from DBE companies if the price difference is excessive or unreasonable.
- (5) Not rejecting DBE companies as being unqualified without sound reasons based on a thorough investigation of their capabilities. The bidder's standing within its industry, membership in specific groups, organizations, or associations and political or social affiliations (for example union vs. non-union employee status) are not legitimate causes for the rejection or non-solicitation of bids in the bidder's efforts to meet the project goal.
- (6) Making efforts to assist interested DBE companies in obtaining bonding, lines of credit, or insurance as required by the recipient or Contractor.
- (7) Making efforts to assist interested DBE companies in obtaining necessary equipment, supplies, materials, or related assistance or services.
- (8) Effectively using the services of available minority/women community organizations; minority/women contractors' groups; local, state, and federal minority/women business assistance offices; and other organizations as allowed on a case-by-case basis to provide assistance in the recruitment and placement of DBE companies.

- (b) If the Department determines that the apparent successful bidder has made a good faith effort to secure the work commitment of DBE companies to meet the contract goal, the Department will award the contract provided that it is otherwise eligible for award. If the Department determines that the bidder has failed to meet the requirements of this Special Provision and that a good faith effort has not been made, the Department will notify the responsible company official designated in the Utilization Plan that the bid is not responsive. The notification shall include a statement of reasons why good faith efforts have not been found.
- (c) The bidder may request administrative reconsideration of a determination adverse to the bidder within the five working days after receipt of the notification date of the determination by delivering the request to the Department of Transportation, Bureau of Small Business Enterprises, Contract Compliance Section, 2300 South Dirksen Parkway, Room 319, Springfield, Illinois 62764 (Telefax: (217)785-1524). Deposit of the request in the United States mail on or before the fifth business day shall not be deemed delivery. The determination shall become final if a request is not made and delivered. A request may provide additional written documentation and/or argument concerning the issue of whether an adequate good faith effort was made to meet the contract goal. The request will be forwarded to the Department's Reconsideration Officer. The Reconsideration Officer will extend an opportunity to the bidder to meet in person in order to consider all issues of whether the bidder made a good faith effort to meet the goal. After the review by the Reconsideration Officer, the bidder will be sent a written decision within ten working days after receipt of the request for reconsideration, explaining the basis for finding that the bidder did or did not meet the goal or make adequate good faith efforts to do so. A final decision by the Reconsideration Officer that a good faith effort was made shall approve the Utilization Plan submitted by the bidder and shall clear the contract for award. A final decision that a good faith effort was not made shall render the bid not responsive.

<u>CALCULATING DBE PARTICIPATION</u>. The Utilization Plan values represent work anticipated to be performed and paid for upon satisfactory completion. The Department is only able to count toward the achievement of the overall goal and the contract goal the value of payments made for the work actually performed by DBE companies. In addition, a DBE must perform a commercially useful function on the contract to be counted. A commercially useful function is generally performed when the DBE is responsible for the work and is carrying out its responsibilities by actually performing, managing, and supervising the work involved. The Department and Contractor are governed by the provisions of 49 CFR part 26.55(c) on questions of commercially useful functions as it affects the work. Specific counting guidelines are provided in 49 CFR part 26.55, the provisions of which govern over the summary contained herein.

- (a) DBE as the Contractor: 100 percent goal credit for that portion of the work performed by the DBE's own forces, including the cost of materials and supplies. Work that a DBE subcontracts to a non-DBE does not count toward the DBE goals.
- (b) DBE as a joint venture Contractor: 100 percent goal credit for that portion of the total dollar value of the contract equal to the distinct, clearly defined portion of the work performed by the DBE's own forces.
- (c) DBE as a subcontractor: 100 percent goal credit for the work of the subcontract performed by the DBE's own forces, including the cost of materials and supplies, excluding the purchase of materials and supplies or the lease of equipment by the DBE subcontractor from the prime Contractor or its affiliates. Work that a DBE subcontractor in turn subcontracts to a non-DBE does not count toward the DBE goal.

- (d) DBE as a trucker: 100 percent goal credit for trucking participation provided the DBE is responsible for the management and supervision of the entire trucking operation for which it is responsible. At least one truck owned, operated, licensed, and insured by the DBE must be used on the contact. Credit will be given for the following:
- (1) The DBE may lease trucks from another DBE firm, including an owner-operator who is certified as a DBE. The DBE who leases trucks from another DBE receives credit for the total value of the transportation services the lessee DBE provides on the contract.
- (2) The DBE may also lease trucks from a non-DBE firm, including from an owner-operator. The DBE who leases trucks from a non-DBE is entitled to credit only for the fee or commission it receives as a result of the lease arrangement.
- (e) DBE as a material supplier:
- (1) 60 percent goal credit for the cost of the materials or supplies purchased from a DBE regular dealer.
- (2) 100 percent goal credit for the cost of materials or supplies obtained from a DBE manufacturer.
- (3) 100 percent credit for the value of reasonable fees and commissions for the procurement of materials and supplies if not a regular dealer or manufacturer.

CONTRACT COMPLIANCE. Compliance with this Special Provision is an essential part of the contract. The Department is prohibited by federal regulations from crediting the participation of a DBE included in the Utilization Plan toward either the contract goal or the Department's overall goal until the amount to be applied toward the goals has been paid to the DBE. The following administrative procedures and remedies govern the compliance by the Contractor with the contractual obligations established by the Utilization Plan. After approval of the Utilization Plan and award of the contract, the Utilization Plan and individual DBE Participation Statements become part of the contract. If the Contractor did not succeed in obtaining enough DBE participation to achieve the advertised contract goal, and the Utilization Plan was approved and contract awarded based upon a determination of good faith, the total dollar value of DBE work calculated in the approved Utilization Plan as a percentage of the awarded contract value shall become the amended contract goal.

- (a) No amendment to the Utilization Plan may be made without prior written approval from the Department's Bureau of Small Business Enterprises. All requests for amendment to the Utilization Plan shall be submitted to the Department of Transportation, Bureau of Small Business Enterprises, Contract Compliance Section, 2300 South Dirksen Parkway, Room 319, Springfield, Illinois 62764. Telephone number (217) 785-4611. Telefax number (217) 785-1524.
- (b) The Contractor must notify and obtain written approval from the Department's Bureau of Small Business Enterprises prior to replacing a DBE or making any change in the participation of a DBE. Approval for replacement will be granted only if it is demonstrated that the DBE is unable or unwilling to perform. The Contractor must make every good faith effort to find another certified DBE subcontractor to substitute for the original DBE. The good faith efforts shall be directed at finding another DBE to perform at least the same amount of work under the contract as the original DBE, to the extent needed to meet the contract goal.

- (c) Any deviation from the DBE condition-of-award or contract specifications must be approved, in writing, by the Department. The Contractor shall notify affected DBEs in writing of any changes in the scope of work which result in a reduction in the dollar amount condition-of-award to the contract.
- (d) In addition to the above requirements for reductions in the condition of award, additional requirements apply to the two cases of Contractor-initiated work substitution proposals. Where the contract allows alternate work methods which serve to delete or create underruns in condition of award DBE work, and the Contractor selects that alternate method or, where the Contractor proposes a substitute work method or material that serves to diminish or delete work committed to a DBE and replace it with other work, then the Contractor must demonstrate one of the following:
- (1) That the replacement work will be performed by the same DBE (as long as the DBE is certified in the respective item of work) in a modification of the condition of award; or
- That the DBE is aware that its work will be deleted or will experience underruns and has agreed in writing to the change. If this occurs, the Contractor shall substitute other work of equivalent value to a certified DBE or provide documentation of good faith efforts to do so; or
- (3) That the DBE is not capable of performing the replacement work or has declined to perform the work at a reasonably competitive price. If this occurs, the Contractor shall substitute other work of equivalent value to a certified DBE or provide documentation of good faith efforts to do so.
- (e) Where the revision includes work committed to a new DBE subcontractor, not previously involved in the project, then a Request for Approval of Subcontractor, Department form BC 260A, must be signed and submitted.
- (f) If the commitment of work is in the form of additional tasks assigned to an existing subcontract, than a new Request for Approval of Subcontractor shall not be required. However, the Contractor must document efforts to assure that the existing DBE subcontractor is capable of performing the additional work and has agreed in writing to the change.
- (g) All work indicated for performance by an approved DBE shall be performed, managed, and supervised by the DBE executing the Participation Statement. The Contractor shall not terminate for convenience a DBE listed in the Utilization Plan and then perform the work of the terminated DBE with its own forces, those of an affiliate or those of another subcontractor, whether DBE or not, without first obtaining the written consent of the Bureau of Small Business Enterprises to amend the Utilization Plan. The Contractor shall notify the Bureau of Small Business Enterprises of any termination for reasons other than convenience, and shall obtain approval for inclusion of the substitute DBE in the Utilization Plan. If good faith efforts following a termination of a DBE for cause are not successful, the Contractor shall contact the Bureau of Small Business Enterprises and provide a full accounting of the efforts undertaken to obtain substitute DBE participation. The Bureau of Small Business Enterprises will evaluate the good faith efforts in light of all circumstances surrounding the performance status of the contract, and determine whether the contract goal should be amended.
- (h) The Contractor shall maintain a record of payments for work performed to the DBE participants. The records shall be made available to the Department for inspection upon request.

After the performance of the final item of work or delivery of material by a DBE and final payment therefore to the DBE by the Contractor, but not later than thirty calendar days after payment has been made by the Department to the Contractor for such work or material, the Contractor shall submit a DBE Payment Agreement on Department form SBE 2115 to the Regional Engineer. If full and final payment has not been made to the DBE, the DBE Payment Agreement shall indicate whether a disagreement as to the payment required exists between the Contractor and the DBE or if the Contractor believes that the work has not been satisfactorily completed. If the Contractor does not have the full amount of work indicated in the Utilization Plan performed by the DBE companies indicated in the Utilization Plan and after good faith efforts are reviewed, the Department may deduct from contract payments to the Contractor the amount of the goal not achieved as liquidated and ascertained damages. The Contractor may request an administrative reconsideration of any amount deducted as damages pursuant to subsection (j) of this part.

- (i) The Department reserves the right to withhold payment to the Contractor to enforce the provisions of this Special Provision. Final payment shall not be made on the contract until such time as the Contractor submits sufficient documentation demonstrating achievement of the goal in accordance with this Special Provision or after liquidated damages have been determined and collected.
- (j) Notwithstanding any other provision of the contract, including but not limited to Article 109.09 of the Standard Specifications, the Contractor may request administrative reconsideration of a decision to deduct the amount of the goal not achieved as liquidated damages. A request to reconsider shall be delivered to the Contract Compliance Section and shall be handled and considered in the same manner as set forth in paragraph (c) of "Good Faith Effort Procedures" of this Special Provision, except a final decision that a good faith effort was not made during contract performance to achieve the goal agreed to in the Utilization Plan shall be the final administrative decision of the Department.

### **EQUIPMENT RENTAL RATES (BDE)**

Effective: August 2, 2007 Revised: January 2, 2008

Replace the second and third paragraphs of Article 105.07(b)(4)a. of the Standard Specifications with the following:

"Equipment idled which cannot be used on other work, and which is authorized to standby on the project site by the Engineer, will be paid for according to Article 109.04(b)(4)."

Replace Article 109.04(b)(4) of the Standard Specifications with the following:

- "(4) Equipment. Equipment used for extra work shall be authorized by the Engineer. The equipment shall be specifically described, be of suitable size and capacity for the work to be performed, and be in good operating condition. For such equipment, the Contractor will be paid as follows.
  - a. Contractor Owned Equipment. Contractor owned equipment will be paid for by the hour using the applicable FHWA hourly rate from the "Equipment Watch Rental Rate Blue Book" (Blue Book) in effect when the force account work begins. The FHWA hourly rate is calculated as follows.

FHWA hourly rate = (monthly rate/176) x (model year adj.) x (Illinois adj.) + EOC

Where: EOC = Estimated Operating Costs per hour (from the Blue Book)

The time allowed will be the actual time the equipment is operating on the extra work. For the time required to move the equipment to and from the site of the extra work and any authorized idle (standby) time, payment will be made at the following hourly rate: 0.5 x (FHWA hourly rate - EOC).

All time allowed shall fall within the working hours authorized for the extra work.

The rates above include the cost of fuel, oil, lubrication, supplies, small tools, necessary attachments, repairs, overhaul and maintenance of any kind, depreciation, storage, overhead, profits, insurance, and all incidentals. The rates do not include labor.

The Contractor shall submit to the Engineer sufficient information for each piece of equipment and its attachments to enable the Engineer to determine the proper equipment category. If a rate is not established in the Blue Book for a particular piece of equipment, the Engineer will establish a rate for that piece of equipment that is consistent with its cost and use in the industry.

b. Rented Equipment. Whenever it is necessary for the Contractor to rent equipment to perform extra work, the rental and transportation costs of the equipment plus five percent for overhead will be paid. In no case shall the rental rates exceed those of established distributors or equipment rental agencies.

All prices shall be agreed to in writing before the equipment is used."

### LIQUIDATED DAMAGES (BDE)

Effective: April 1, 2009

Revise the table in Article 108.09 of the Standard Specifications to read:

"Schedule of Deductions for Each Day of Overrun in Contract Time												
Original Contra	act Amount	Daily Charges										
From More Than	To and Including	Calendar Day	Work Day									
\$ 0	\$ 100,000	\$ 375	\$ 500									
100,000	500,000	625	875									
500,000	1,000,000	1,025	1,425									
1,000,000	3,000,000	1,125	1,550									
3,000,000	5,000,000	1,425	1,950									
5,000,000	10,000,000	1,700	2,350									
10,000,000	And over	3,325	4,650"									

### NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM / EROSION AND SEDIMENT CONTROL DEFICIENCY DEDUCTION (BDE)

Effective: April 1, 2007 Revised: November 1, 2009

Revise Article 105.03(a) of the Standard Specifications to read:

"(a) National Pollutant Discharge Elimination System (NPDES) / Erosion and Sediment Control Deficiency Deduction When the Engineer is notified or determines an erosion and/or sediment control deficiency(s) exists, or the Contractor's activities represents a violation of the Department's NPDES permits, the Engineer will notify and direct the Contractor to correct the deficiency within a specified time. The specified time, which begins upon notification to the Contractor, will be from 1/2 hour to 1 week based on the urgency of the situation and the nature of the work effort required. The Engineer will be the sole judge.

A deficiency may be any lack of repair, maintenance, or implementation of erosion and/or sediment control devices included in the contract, or any failure to comply with the conditions of the Department's NPDES permits. A deficiency may also be applied to situations where corrective action is not an option such as the failure to participate in a jobsite inspection of the project, failure to install required measures prior to initiating earth moving operations, disregard of concrete washout requirements, or other disregard of the NPDES permit.

If the Contractor fails to correct a deficiency within the specified time, a daily monetary deduction will be imposed for each calendar day or portion of a calendar day until the deficiency is corrected to the satisfaction of the Engineer. The calendar day(s) will begin with notification to the Contractor and end with the Engineer's acceptance of the correction. The base value of the daily monetary deduction is \$1000.00 and will be applied to each location for which a deficiency exists. The value of the deficiency deduction assessed for each infraction will be determined by multiplying the base value by a Gravity Adjustment Factor provided in Table A. Except for failure to participate in a required jobsite inspection of the project prior to initiating earthmoving operations which will be based on the total acreage of planned disturbance at the following multipliers: <5 Acres: 1; 5-10 Acres: 2; >10-25 Acres: 3; >25 Acres: 5. For those deficiencies where corrective action was not an option, the monetary deduction will be immediate and will be valued at one calendar day multiplied by a Gravity Adjustment Factor.

Tak	ole A												
Deficiency Deduction Gravity Adjustment Factors													
Types of Violations	Soil Disturbed and Not Permanently Stabilized												
	At Time of Violation												
	< 5	5 - 10	>10 - 25	> 25									
	Acres	Acres	Acres	Acres									
Failure to Install or Properly Maintain BMP	0.1 - 0.5	0.2 - 1.0	0.5 - 2.5	1.0 - 5									
Careless Destruction of BMP	0.2 - 1	0.5 - 2.5	1.0 - 5.	1.0 - 5									
Intrusion into Protected Resource	1.0 - 5	1.0 - 5	2.0 - 10	2.0 - 10									
Failure to properly manage Chemicals,	0.2 - 1	0.2 - 1	0.5 - 2.5	1.0 - 5									
Concrete Washouts or Residuals, Litter or													
other Wastes													
Improper Vehicle and Equipment	0.1 - 0.5	0.2 - 1	0.2 - 1	0.5 - 2.5									
Maintenance, Fueling or Cleaning													
Failure to Provide or Update Written or	0.2 - 1	0.5 - 2.5	1.0 - 5	1.0 - 5									
Graphic Plans Required by SWPPP													
Failure to comply with Other Provisions of the	0.1 - 0.5	0.2 - 1	0.2 - 1	0.5 - 2.5"									
NPDES Permit													

### PAYMENTS TO SUBCONTRACTORS (BDE)

Effective: June 1, 2000 Revised: January 1, 2006

Federal regulations found at 49 CFR §26.29 mandate the Department to establish a contract clause to require Contractors to pay subcontractors for satisfactory performance of their subcontracts and to set the time for such payments.

State law also addresses the timing of payments to be made to subcontractors and material suppliers. Section 7 of the Prompt Payment Act, 30 ILCS 540/7, requires that when a Contractor receives any payment from the Department, the Contractor shall make corresponding, proportional payments to each subcontractor and material supplier performing work or supplying material within 15 calendar days after receipt of the Department payment. Section 7 of the Act further provides that interest in the amount of two percent per month, in addition to the payment due, shall be paid to any subcontractor or material supplier by the Contractor if the payment required by the Act is withheld or delayed without reasonable cause. The Act also provides that the time for payment required and the calculation of any interest due applies to transactions between subcontractors and lower-tier subcontractors and material suppliers throughout the contracting chain.

This Special Provision establishes the required federal contract clause, and adopts the 15 calendar day requirement of the State Prompt Payment Act for purposes of compliance with the federal regulation regarding payments to subcontractors. This contract is subject to the following payment obligations.

When progress payments are made to the Contractor according to Article 109.07 of the Standard Specifications, the Contractor shall make a corresponding payment to each subcontractor and material supplier in proportion to the work satisfactorily completed by each subcontractor and for the material supplied to perform any work of the contract. The proportionate amount of partial payment due to each subcontractor and material supplier throughout the contracting chain shall be determined by the quantities measured or otherwise determined as eligible for payment by the Department and included in the progress payment to the Contractor. Subcontractors and material suppliers shall be paid by the Contractor within 15 calendar days after the receipt of payment from the Department. The Contractor shall not hold retainage from the subcontractors. These obligations shall also apply to any payments made by subcontractors and material suppliers to their subcontractors and material suppliers; and to all payments made to lower tier subcontractors and material suppliers throughout the contracting chain. Any payment or portion of a payment subject to this provision may only be withheld from the subcontractor or material supplier to whom it is due for reasonable cause.

This Special Provision does not create any rights in favor of any subcontractor or material supplier against the State or authorize any cause of action against the State on account of any payment, nonpayment, delayed payment, or interest claimed by application of the State Prompt Payment Act. The Department will not approve any delay or postponement of the 15 day requirement except for reasonable cause shown after notice and hearing pursuant to Section 7(b) of the State Prompt Payment Act. State law creates other and additional remedies available to any subcontractor or material supplier, regardless of tier, who has not been paid for work properly performed or material furnished. These remedies are a lien against public funds set forth in Section 23(c) of the Mechanics Lien Act, 770 ILCS 60/23(c), and a recovery on the Contractor's payment bond according to the Public Construction Bond Act, 30 ILCS 550.

### POST MOUNTING OF SIGNS (BDE)

Effective: January 1, 2011

Revise the second paragraph of Article 701.14 of the Standard Specifications to read:

"Post mounted signs shall be a breakaway design. The sign shall be within five degrees of vertical. Two posts shall be used for signs greater than 16 sq ft (1.5 sq m) in area or where the height between the sign and the ground exceeds 7 ft (2.1 m)."

### RAISED REFLECTIVE PAVEMENT MARKERS (BDE)

Effective: November 1, 2009 Revised: April 1, 2010

Revise the first sentence of the second paragraph of Article 781.03(a) of the Standard Specifications to read:

"The pavement shall be cut to match the bottom contour of the marker using a concrete saw fitted with 18 and 20 in. (450 and 500 mm) diameter blades."

### **SELECTION OF LABOR (BDE)**

Effective: July 2, 2010

Revise Section I of Check Sheet #5 of the Recurring Special Provisions to read:

### "I. SELECTION OF LABOR

The Contractor shall comply with all Illinois statutes pertaining to the selection of labor.

### EMPLOYMENT OF ILLINOIS WORKERS DURING PERIODS OF EXCESSIVE UNEMPLOYMENT

Whenever there is a period of excessive unemployment in Illinois, which is defined herein as any month immediately following two consecutive calendar months during which the level of unemployment in the State of Illinois has exceeded five percent as measured by the United States Bureau of Labor Statistics in its monthly publication of employment and unemployment figures, the Contractor shall employ at least 90 percent Illinois laborers. "Illinois laborer" means any person who has resided in Illinois for at least 30 days and intends to become or remain an Illinois resident.

Other laborers may be used when Illinois laborers as defined herein are not available, or are incapable of performing the particular type of work involved, if so certified by the Contractor and approved by the Engineer. The Contractor may place no more than three of his/her regularly employed non-resident executive and technical experts, who do not qualify as Illinois laborers, to do work encompassed by this contract during period of excessive unemployment.

This provision applies to all labor, whether skilled, semi-skilled, or unskilled, whether manual or non-manual."

### SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE)

Effective: April 2, 2005

To account for the preparatory work and operations necessary for the movement of subcontractor personnel, equipment, supplies, and incidentals to the project site and for all other work or operations that must be performed or costs incurred when beginning work approved for subcontracting in accordance with Article 108.01 of the Standard Specifications, the Contractor shall make a mobilization payment to each subcontractor.

This mobilization payment shall be made at least 14 days prior to the subcontractor starting work. The amount paid shall be equal to 3 percent of the amount of the subcontract reported on form BC 260A submitted for the approval of the subcontractor's work.

This provision shall be incorporated directly or by reference into each subcontract approved by the Department.

### TRUCK MOUNTED/TRAILER MOUNTED ATTENUATORS (BDE)

Effective: January 1, 2010

Revise Article 701.03(k) of the Standard Specifications to read:

"(k) Truck Mounted/Trailer Mounted Attenuators .......1106.02"

Revise Article 701.15(h) of the Standard Specifications to read:

"(h) Truck Mounted/Trailer Mounted Attenuators (TMA). TMA units shall have a roll ahead distance in the event of an impact. The TMA shall be between 100 and 200 ft (30 and 60 m) behind the vehicle ahead or the workers. This distance may be extended by the Engineer.

TMA host vehicles shall have the parking brake engaged when stationary.

The driver and passengers of the TMA host vehicle should exit the vehicle if the TMA is to remain stationary for 15 minutes or more in duration."

Revise Article 1106.02(g) of the Standard Specifications to read:

"(g) Truck Mounted/Trailer Mounted Attenuators. The attenuator shall be a NCHRP 350 approved unit for Test Level 3. Test Level 2 may be used as directed by the Engineer for normal posted speeds less than or equal to 45 mph."

### **WORKING DAYS (BDE)**


Effective: January 1, 2002

The Contractor shall complete the work within **25** working days.

D-97-003-11 SHEET 1 OF 5

# STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION

FAI 70 (I70)
D7 PAVT PRSV 2011-2
CUMBERLAND & CLARK COUNTIES



FAI 70 (I 70) D7 PAVT PRSV 2011-2 CUMBERLAND & CLARK COUNTIES SHEET 2 OF 5 CONTRACT 74503

### INDEX OF SHEETS

SHEET NO.	TITLE
1	COVER SHEET
2	INDEX OF SHEETS, LIST OF STANDARDS
3	GENERAL NOTES
4	SUMMARY OF QUANTITIES
5	SCHEDULE OF QUANTITIES

THE FOLLOWING STANDARDS ARE A PART OF THESE PLANS AND ARE INCLUDED FOLLOWING THE LAST NUMBERED SHEET OF THE PLANS.


STD. NO.	DESCRIPTION
000001-06 001006	STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS DECIMAL OF AN INCH AND OF A FOOT
701101-02	OFF-RD OPERATIONS, MULTILANE, 15' TO 24" FROM PAVEMENT EDGE
701400-05	APPROACH TO LANE CLOSURE, FREEWAY/EXPRESSWAY
701406-06	LANE CLOSURE, FREEWAY/EXPRESSWAY, DAY OPERATIONS ONLY
701426-04	LANE CLOSURE, MULTILANE, INTERMITTENT OR MOVING OPER., FOR SPEEDS >= 45 MPH
780001-02	TYPICAL PAVEMENT MARKINGS
781001-03	TYPICAL APPLICATIONS RAISED REFLECTIVE PAVEMENT MARKERS
701901-01	TRAFFIC CONTROL DEVICES

FAI 70 (I 70) D7 PAVT PRSV 2011-2 CUMBERLAND & CLARK COUNTIES SHEET 3 OF 5 CONTRACT 74503

### **GENERAL NOTES**

THERE WILL BE NO CRACK/JOINT SEALING, BUMP REMOVAL OR SCRATCH-COAT FILLING ON THIS PROJECT.

ALL SHORT-TERM PAVEMENT MARKING SHALL BE TAPE. THE TAPE SHALL BE PLACED BEYOND THE LIMITS OF THE MICRO-SURFACING ON THE PASSING LANE SIDE.



FAI 70 (1 70)
D7 PAVT PRSV 2011-2
CUMBERLAND & CLARK COUNTIES
SHEET 4 OF 5
CONTRACT 74503

			CONSTRUCTION TYPE CODE	TYPE CODE
	SUMMARY OF QUANTITIES	TOTAL	100% STATE	100% STATE
(		QUANTITIES	CUMBERLAND CO	CLARK CO
CODE NO	ITEM		0005	0005
40600100	BITUMINOUS MATERIALS (PRIME COAT) GALLON	Z699 N	5049	1648
67100100	MOBILIZATION	₩.	0.75	7075
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	<b>н</b>	0.75	0.25
70300100	SHORT TERM PAVEMENT MARKING FOOT	30134	01.766	2.2.0
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	1000	CT /77	7415
78100100		C#00T	/5/3	2472
762662	RAISEU REFLECTIVE PAVEIMEN I-MARKER	7534	5680	1854
/8300100	PAVEMENT MARKING REMOVAL SQ FT	25111	18937	6170
78300200	MARKER REMOVAL	3767	2840	277
X0326240	MICRO-SURFACING TEST STRIP	,	2010	/76
XXXOUG10		-1	0.75	0.25
	CALTIFIANE PAVEINIENT IVIARRING - LINE 4" FOOT	75334	26797	18537
70033650	LONGITUDINAL JOINT REPAIR TON	47	35	1,
Z0063805	MICRO-SURFACING, SINGLE PASS, TYPE II	ŭ	1000	77
		-	5048/	16477

\*Specially Items

FAI 70 (I 70)

D7 PAVT PRSV 2011-2

CUMBERLAND & CLARK COUNTIES

SHEET 5 OF 5

CONTRACT 74503

CONTRACT 74503	ficro-surfacing, single ASS, Type II		10453.1	1000	373.5		4283.6	4	05727	33/3./	2 - 200	1807.6		889.3		473.1	1 4430 0	14430.5	0,00	8.34.2	5048/	15224.0		1253.0	66964	
	AISED REFLECTIVE PAVEMENT	F A	588.0	8	21.0	42	241.0	44	530 E	2000	10,50	<u>`</u>	45	0.05	,	26.6	040	017.6	707	400.3	2840	856.3	107	5.07	3767	
	AVEMENT MARKING REMOVAL	SOFT	L	SN 018-00	140.1	SN 018-00	1606.4	SN 018-00	3500 1	10000	0 77.2	67/10	00-8TO NC	333.5 CN 010 00	On-orto vic	1//.4 SNI 019 00	5414 A	CN 010 00	07-070 NC	30/2.0	10332	5/09.0 8	00-270 NG	6170	25111	
	NARKER NARKER	19	1176.0	FBOUND	42.0	EASTBOUND SN 018-0043, WESTBOUND SN 018-0042	481.9	ROUND	1077.0		702 4	100		O.OO.	ברים ברים ברים	23.2 GM 108	1624 3	POLINIA PROLINIA	92.6	261.0	2000			1854	7534	
	NETHANE PAVEMENT NETHANE PAVEMENT	FOOT	11759.7	SN 018-0040, WESTBOUND SN 018-0040	420.2	3043, WEST	4819.1	EASTBOUND SN 018-0054, WESTBOUND SN 018-0044	1436.1 10770.4	STATION FOUATION	2033 6	STBOLIND SN 018-0046 WESTBOLIND SN 028 028	122 4 1 1000 4	EASTBOUND SN 018-0048 WESTBOLIND SN 018-0048	, , , ,	EASTBOUND SN 018-0050 WESTBOUND SN 018 0040	2165 8 16243 3	EASTBOUND SN 018-0052 WESTBOUND SN 049 OPE1	9218 5	20232	16100	EASTBOUND SN 012-0050 WESTBOUND	1400 5	18537	75334	
	NORK ZONE PAVEMENT NARKING REMOVAL	1	1568.0	SN 018-(	56.0	SN 018-(	642.5	SN 018-(	1436.1	ATION E	7711	SN 018-	122 4	SN 018-C	71.0	SN 018-0	2165 R	SN 018-C	1229 1	7572	20000	SN 012-0	188.0	2472	10045	
NTITIES	ЗНОКТ-ТЕRМ 5НОКТ-ТЕRМ	. =	4703.9	EASTBOUND	168.1	STBOUND	1927.6	STBOUND	4308.2	ST	813.4	STROUND	400.2	STBOUND	2120	STBOUND	6497.3	STBOUND	3687.4	27710	SEC D	STROUND	562.0	7415	30134	
SCHEDULE OF QUANTITIES	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	1045.3	EA	37.4	EĀ	428.4	ΕÅ	957.4		180.8	7<	88.0	s I	47.3	EA	1443.9	EA	819.4	5049	1522 4	EA	1753	1648	2699	
SCHEDUL	WIDTH	(FT)	2		2		2		7		2		^		2	1	2		2		,		2			
	LENGTH	(FT)	23519.38	100.9	840,42	196.6	9638.2	177	21540.88		4067.16	156	2000.84	207.6	1064.4	670	32486.65	134.7	18436.95		34253.95	335.5	2819.25			
	N TO STATION	STATION	250+60.38	251+61.28	260+01.70	261+98.30	358+36.50	360+13.50	- 1	TA 80+00.00 AH	120+67.16	122+23.16	142+24.00	144+31.60	154+96.00	161+66.00	486+52.65	487+87.35	672+24.30	ERLAND CO. TOTALS	1014+78,25	1018+13.75	1046+33.00	CLARK CO. TOTALS:	ROJECT TOTALS:	
		2	2		2	2	2	9	힏	BK = S	TO	TO	ũ	오	2	2	5	To	TO	CUMBE	2	인	TO	리	E.	
	STATION TO SI	STATION	15+41.00	250+60.38	251+61.28	260+01.70	261+98.30	358+36.50	360+13.50	STA 575+54.38 BK = ST	80+00.00	120+67.16	122+23.16	142+24.00	144+31.60	154+96.00	161+66.00	486+52.65	487+87.35		672+24,30	1014+78.25	1018+13.75			

### ILLINOIS DEPARTMENT OF LABOR

## PREVAILING WAGES FOR CLARK & CUMBERLAND COUNTIES EFFECTIVE DECEMBER 2010

The Prevailing rates of wages are included in the Contract proposals which are subject to Check Sheet #5 of the Supplemental Specifications and Recurring Special Provisions. The rates have been ascertained and certified by the Illinois Department of Labor for the locality in which the work is to be performed and for each craft or type of work or mechanic needed to execute the work of the Contract. As required by Prevailing Wage Act (820 ILCS 130/0.01, et seq.) and Check Sheet #5 of the Contract, not less than the rates of wages ascertained by the Illinois Department of Labor and as revised during the performance of a Contract shall be paid to all laborers, workers and mechanics performing work under the Contract. Post the scale of wages in a prominent and easily accessible place at the site of work.

If the Illinois Department of Labor revises the prevailing rates of wages to be paid as listed in the specification of rates, the contractor shall post the revised rates of wages and shall pay not less than the revised rates of wages. Current wage rate information shall be obtained by visiting the Illinois Department of Labor web site at <a href="http://www.state.il.us/agency/idol/">http://www.state.il.us/agency/idol/</a> or by calling 312-793-2814. It is the responsibility of the contractor to review the rates applicable to the work of the contract at regular intervals in order to insure the timely payment of current rates. Provision of this information to the contractor by means of the Illinois Department of Labor web site satisfies the notification of revisions by the Department to the contractor pursuant to the Act, and the contractor agrees that no additional notice is required. The contractor shall notify each of its subcontractors of the revised rates of wages.

### **Clark County Prevailing Wage for December 2010**

Trade Name	RG	TYP	С	Base	FRMAN					Pensn	Vac	Trng
=======================================	==		=		=====							
ASBESTOS ABT-GEN		BLD			29.190					8.790		
ASBESTOS ABT-MEC		BLD		20.190	0.000					3.400		
BOILERMAKER		BLD			34.000					11.43		
BRICK MASON		BLD			29.510					7.830		
CARPENTER		BLD			31.250					10.30		
CARPENTER		HWY			30.630					10.30		
CEMENT MASON		BLD			30.980					7.880		
CEMENT MASON		HWY			30.400					7.900		
CERAMIC TILE FNSHER		BLD		28.100	0.000					7.430		
COMM SYSTEMS TECH		BLD			25.700					4.310		
ELECTRICIAN		BLD			35.350					7.270		
ELEVATOR CONSTRUCTOR		BLD			42.580					9.460		
GLAZIER		BLD			28.080					5.050		
HT/FROST INSULATOR		BLD		28.470	0.000					5.800		
IRON WORKER		ALL			30.250					10.70		
LABORER		BLD			27.190					8.790		
LABORER		HWY			28.350					8.790		
LATHER		BLD			31.250					10.30		
MACHINIST		BLD			45.160					8.700		
MARBLE FINISHERS		BLD		28.100	0.000					7.430		
MARBLE MASON		BLD		29.600	0.000					7.430		
MILLWRIGHT		BLD			31.270					10.74		
MILLWRIGHT		HWY			32.080					11.19		
OPERATING ENGINEER				33.350	0.000					7.500		
OPERATING ENGINEER			2	21.800	0.000					7.500		
PAINTER		ALL			27.500					8.230		
PILEDRIVER		BLD			31.750					10.30		
PILEDRIVER		HWY			31.630					10.30		
PIPEFITTER		ALL			36.450					5.690		
PLASTERER		BLD			31.470					8.500		
PLUMBER		ALL			36.450					5.690		
ROOFER		BLD			29.010					7.800		
SHEETMETAL WORKER		BLD			31.130					6.500		
SPRINKLER FITTER		BLD			38.890					6.550		
STONE MASON		BLD			29.510					7.830		
TERRAZZO FINISHER		BLD		28.100	0.000					7.430		
TERRAZZO MASON		BLD		29.600	0.000					7.430		
TILE LAYER		BLD			29.150							
TILE MASON		BLD	_	29.600	0.000					7.430		
TRUCK DRIVER				28.955	0.000					2.900		
TRUCK DRIVER				29.355	0.000					2.900		
TRUCK DRIVER				29.555	0.000					2.900		
TRUCK DRIVER				29.805	0.000					2.900		
TRUCK DRIVER				30.555	0.000					2.900		
TRUCK DRIVER				23.160	0.000					2.900		
TRUCK DRIVER				23.480	0.000					2.900		
TRUCK DRIVER				23.640	0.000					2.900		
TRUCK DRIVER				23.840	0.000					2.900		
TRUCK DRIVER			5	24.440	0.000					2.900		
TUCKPOINTER		BLD		28.010	29.510	2.0	2.0	2.0	5.900	7.830	0.000	0.630

Legend:

M-F>8 (Overtime is required for any hour greater than 8 worked each day, Monday through Friday.

OSH (Overtime is required for every hour worked on Sunday and Holidays)

H/W (Health & Welfare Insurance)

Pensn (Pension)

Vac (Vacation)

Trng (Training)

### **Explanations**

CLARK COUNTY

The following list is considered as those days for which holiday rates of wages for work performed apply: New Years Day, Memorial Day, Fourth of July, Labor Day, Thanksgiving Day, Christmas Day and Veterans Day in some classifications/counties. Generally, any of these holidays which fall on a Sunday is celebrated on the following Monday. This then makes work performed on that Monday payable at the appropriate overtime rate for holiday pay. Common practice in a given local may alter certain days of celebration. If in doubt, please check with IDOL.

Oil and chip resealing (O&C) means the application of road oils and liquid asphalt to coat an existing road surface, followed by application of aggregate chips or gravel to coated surface, and subsequent rolling of material to seal the surface.

#### EXPLANATION OF CLASSES

ASBESTOS - GENERAL - removal of asbestos material/mold and hazardous materials from any place in a building, including mechanical systems where those mechanical systems are to be removed. This includes the removal of asbestos materials/mold and hazardous materials from ductwork or pipes in a building when the building is to be demolished at the time or at some close future date.

ASBESTOS - MECHANICAL - removal of asbestos material from mechanical systems, such as pipes, ducts, and boilers, where the mechanical systems are to remain.

CERAMIC TILE FINISHER, MARBLE FINISHER, TERRAZZO FINISHER

Assisting, helping or supporting the tile, marble and terrazzo mechanic by performing their historic and traditional work assignments required to complete the proper installation of the work covered by said crafts. The term "Ceramic" is used for naming the classification only and is in no way a limitation of the product handled. Ceramic takes into consideration most hard tiles.

### COMMUNICATION SYSTEMS TECHNICIAN

Installation, operation, inspection, maintenance, repair, and service of radio, television, recording, voice sound and vision production and reproduction apparatus, equipment and appliances used for domestic, commercial, education, entertainment and private telephone systems.

TRUCK DRIVER - BUILDING, HEAVY AND HIGHWAY CONSTRUCTION

- Class 1. Drivers on 2 axle trucks hauling less than 9 ton. Air compressor and welding machines and brooms, including those pulled by separate units, truck driver helpers, warehouse employees, mechanic helpers, greasers and tiremen, pickup trucks when hauling materials, tools, or workers to and from and on-the-job site, and fork lifts up to 6,000 lb. capacity.
- Class 2. Two or three axle trucks hauling more than 9 ton but hauling less than 16 ton. A-frame winch trucks, hydrolift trucks, vactor trucks or similar equipment when used for transportation purposes. Fork lifts over 6,000 lb. capacity, winch trucks, four axle combination units, and ticket writers.
- Class 3. Two, three or four axle trucks hauling 16 ton or more. Drivers on water pulls, articulated dump trucks, mechanics and working forepersons, and dispatchers. Five axle or more combination units.
- Class 4. Low Boy and Oil Distributors.
- Class 5. Drivers who require special protective clothing while employed on hazardous waste work.

TRUCK DRIVER - OIL AND CHIP RESEALING ONLY.

This shall encompass laborers, workers and mechanics who drive contractor or subcontractor owned, leased, or hired pickup, dump, service, or oil distributor trucks. The work includes transporting materials and equipment (including but not limited to, oils, aggregate supplies, parts, machinery and tools) to or from the job site; distributing oil or liquid asphalt and aggregate; stock piling material when in connection with the actual oil and chip contract. The Truck Driver (Oil & Chip Resealing) wage classification does not include supplier delivered materials.

### OPERATING ENGINEERS - BUILDING, HEAVY AND HIGHWAY CONSTRUCTION

Class 1. Power Cranes, Draglines, Derricks, Shovels, Gradalls, Mechanics, Tractor Highlift, Tournadozer, Concrete Mixers with Skip, Tournamixer, Two Drum Machine, One Drum Hoist with Tower or Boom, Cableways, Tower Machines, Motor Patrol, Boom Tractor, Boom or Winch Truck, Winch or Hydraulic Boom Truck, Truck Crane, Tournapull, Tractor Operating Scoops, Bulldozer, Push Tractor, Asphalt Planer, Finishing Machine on Asphalt, Large Rollers on Earth, Rollers on Asphalt Mix, Ross Carrier or similar Machine, Gravel Processing Machine, Asphalt Plant Engineer, Paver Operator, Dredging Equipment, or Dredge Engineer, or Dredge Operator, Central Mix Plant Engineer, CMI or similar type machine, Concrete Pump, Truck or Skid Mounted, Tower Crane, Engineer or Rock Crusher Plant, Concrete Plant Engineer, Ditching Machine with dual attachment, Tractor Mounted Loaders, Cherry Picker, Hydro Crane, Standard or Dinkey Locomotives, Scoopmobiles, Euclid Loader, Soil Cement Machine, Back Filler, Elevating Machine, Power Blade, Drilling Machine, including Well Testing, Caissons, Shaft or any similar type drilling machines, Motor Driven Paint Machine, Pipe Cleaning Machine, Pipe Wrapping Machine, Pipe Bending Machine, Apsco Paver, Boring Machine, (Head Equipment Greaser), Barber-Greene Loaders, Formless Paver, (Well Point System), Concrete Spreader, Hydra Ax, Span Saw, Marine Scoops, Brush Mulcher, Brush Burner, Mesh Placer, Tree Mover, Helicopter Crew (3), Piledriver-Skid or Crawler, Stump Remover, Root Rake, Tug Boat Operator, Refrigerating Machine, Freezing Operator, Chair Cart-Self-Propelled, Hydra Seeder, Straw Blower, Power Sub Grader, Bull Float, Finishing Machine, Self-Propelled Pavement Breaker, Lull (or similar type Machine), Two Air Compressors, Compressors hooked in

Manifold, Overhead Crane, Chip Spreader, Mud Cat, Sull-Air, Fork Lifts (except when used for landscaping work), Soil Stabilizer (Seaman Tiller, Bo Mag, Rago Gator, and similar types of equipment), Tube Float, Spray Machine, Curing Machine, Concrete or Asphalt Milling Machine, Snooper Truck-Operator, Backhoe, Farm Tractors (with attachments), 4 Point Lift System (Power Lift or similar type), Skid-Steer (Bob Cat or similar type), Wrecking Shears, Water Blaster.

Class 2. Concrete Mixers without Skips, Rock Crusher, Ditching Machine under 6', Curbing Machine, One Drum Machines without Tower or Boom, Air Tugger, Self-Propelled Concrete Saw, Machine Mounted Post Hole Digger, two to four Generators, Water Pumps or Welding Machines, within 400 feet, Air Compressor 600 cu. ft. and under, Rollers on Aggregate and Seal Coat Surfaces, Fork Lift (when used for landscaping work), Concrete and Blacktop Curb Machine, One Water Pump, Oilers, Air Valves or Steam Valves, One Welding Machine, Truck Jack, Mud Jack, Gunnite Machine, House Elevators when used for hoisting material, Engine Tenders, Fireman, Wagon Drill, Flex Plane, Conveyor, Siphons and Pulsometer, Switchman, Fireman on Paint Pots, Fireman on Asphalt Plants, Distributor Operator on Trucks, Tampers, Self-Propelled Power Broom, Striping Machine (motor driven), Form Tamper, Bulk Cement Plant, Equipment Greaser, Deck Hands, Truck Crane Oiler-Driver, Cement Blimps, Form Grader, Temporary Heat, Throttle Valve, Super Sucker (and similar type of equipment).

#### Other Classifications of Work:

For definitions of classifications not otherwise set out, the Department generally has on file such definitions which are available. If a task to be performed is not subject to one of the classifications of pay set out, the Department will upon being contacted state which neighboring county has such a classification and provide such rate, such rate being deemed to exist by reference in this document. If no neighboring county rate applies to the task, the Department shall undertake a special determination, such special determination being then deemed to have existed under this determination. If a project requires these, or any classification not listed, please contact IDOL at 217-782-1710 for wage rates or clarifications.

#### LANDSCAPING

Landscaping work falls under the existing classifications for laborer, operating engineer and truck driver. The work performed by landscape plantsman and landscape laborer is covered by the existing classification of laborer. The work performed by landscape operators (regardless of equipment used or its size) is covered by the classifications of operating engineer. The work performed by landscape truck drivers (regardless of size of truck driven) is covered by the classifications of truck driver.

### **Cumberland County Prevailing Wage for December 2010**

Trade Name	TYP C			FRMAN *					Pensn	Vac	Trng
ASBESTOS ABT-GEN	BLD		27.940	29.190	1.5	1.5	2.0	5.050	8.790	0.000	0.800
ASBESTOS ABT-MEC	BLD		20.800	0.000	2.0	2.0	2.0	5.500	4.200	0.000	0.000
BOILERMAKER	BLD		31.500	34.000	1.5	1.5	2.0	6.820	11.43	1.500	0.350
BRICK MASON	BLD		28.010	29.510	2.0				7.830		
CARPENTER	BLD		29.000	31.250	1.5	1.5	2.0	7.250	10.30	0.000	0.320
CARPENTER	HWY		28.880	30.630	1.5	1.5	2.0	7.250	10.30	0.000	0.320
CEMENT MASON	BLD		29.480	30.980	1.5	1.5	2.0	5.900	7.880	0.000	0.500
CEMENT MASON	HWY		28.900	30.400	1.5	1.5	2.0	5.900	7.900	0.000	0.500
CERAMIC TILE FNSHER	BLD		28.100	0.000	1.5	1.5	2.0	5.900	7.430	0.000	0.000
ELECTRICIAN	BLD		33.220	36.540	1.5	1.5			6.540		
ELECTRONIC SYS TECH	BLD		30.630	32.380	1.5	1.5	2.0	5.250	5.240	0.000	0.250
ELEVATOR CONSTRUCTOR	BLD			42.580		2.0			9.460		
GLAZIER	BLD			32.780		2.0			7.650		
HT/FROST INSULATOR	BLD			29.920		1.5			8.160		
IRON WORKER	ALL			30.250		1.5			10.70		
LABORER	BLD			27.190					8.790		
LABORER	HWY			28.350					8.790		
LATHER	BLD			31.250		1.5			10.30		
MACHINIST	BLD			45.160		1.5			8.700		
MARBLE FINISHERS	BLD		28.100	0.000		1.5			7.430		
MARBLE MASON	BLD		29.600	0.000					7.430		
MILLWRIGHT	BLD			31.270					10.74		
MILLWRIGHT	HWY			32.080					11.19		
OPERATING ENGINEER			33.350	0.000		1.5			7.500		
OPERATING ENGINEER PAINTER		<u>.</u>	21.800	0.000 35.060					7.500 4.060		
PAINTER SIGNS	ALL ALL			35.060		1.5			4.060		
PILEDRIVER	BLD			31.750		1.5			10.30		
PILEDRIVER	HWY			31.630		1.5			10.30		
PIPEFITTER	BLD			39.360					8.770		
PLASTERER	BLD			31.470					8.500		
PLUMBER	BLD			39.360					8.770		
ROOFER	BLD			29.010					7.800		
SHEETMETAL WORKER	BLD			34.500					9.170		
SPRINKLER FITTER	BLD		36.140	38.890	1.5		2.0	8.200	6.550	0.000	0.250
STONE MASON	BLD		28.010	29.510	2.0	2.0	2.0	5.900	7.830	0.000	0.630
TERRAZZO FINISHER	BLD		28.100	0.000	1.5	1.5	2.0	5.900	7.430	0.000	0.000
TERRAZZO MASON	BLD		29.600	0.000	1.5	1.5	2.0	5.900	7.430	0.000	0.000
TILE LAYER	BLD		27.150	29.150	1.5	1.5	2.0	6.750	6.800	0.000	0.320
TILE MASON	BLD		29.600	0.000	1.5	1.5	2.0	5.900	7.430	0.000	0.000
TRUCK DRIVER	ALL 1		29.480	0.000	1.5	1.5	2.0	9.050	4.347	0.000	0.250
TRUCK DRIVER	ALL 2	)	29.900	0.000	1.5	1.5	2.0	9.050	4.347	0.000	0.250
TRUCK DRIVER	ALL 3	3	30.110	0.000	1.5	1.5	2.0	9.050	4.347	0.000	0.250
TRUCK DRIVER	ALL 4	Ŀ	30.370	0.000	1.5	1.5	2.0	9.050	4.347	0.000	0.250
TRUCK DRIVER			31.160	0.000					4.347		
TRUCK DRIVER			23.580	0.000					4.347		
TRUCK DRIVER			23.920	0.000					4.347		
TRUCK DRIVER			24.090	0.000					4.347		
TRUCK DRIVER			24.300	0.000					4.347		
TRUCK DRIVER		)	24.930	0.000					4.347		
TUCKPOINTER	BLD		28.010	29.510	2.0	2.0	2.0	5.900	7.830	0.000	U.630

Legend:

M-F>8 (Overtime is required for any hour greater than 8 worked each day, Monday through Friday.

OSH (Overtime is required for every hour worked on Sunday and Holidays)

H/W (Health & Welfare Insurance)

Pensn (Pension)

Vac (Vacation)

Trng (Training)

### **Explanations**

#### CUMBERLAND COUNTY

The following list is considered as those days for which holiday rates of wages for work performed apply: New Years Day, Memorial Day, Fourth of July, Labor Day, Thanksgiving Day, Christmas Day and Veterans Day in some classifications/counties. Generally, any of these holidays which fall on a Sunday is celebrated on the following Monday. This then makes work performed on that Monday payable at the appropriate overtime rate for holiday pay. Common practice in a given local may alter certain days of celebration. If in doubt, please check with IDOL.

Oil and chip resealing (O&C) means the application of road oils and liquid asphalt to coat an existing road surface, followed by application of aggregate chips or gravel to coated surface, and subsequent rolling of material to seal the surface.

#### EXPLANATION OF CLASSES

ASBESTOS - GENERAL - removal of asbestos material/mold and hazardous materials from any place in a building, including mechanical systems where those mechanical systems are to be removed. This includes the removal of asbestos materials/mold and hazardous materials from ductwork or pipes in a building when the building is to be demolished at the time or at some close future date.

ASBESTOS - MECHANICAL - removal of asbestos material from mechanical systems, such as pipes, ducts, and boilers, where the mechanical systems are to remain.

CERAMIC TILE FINISHER, MARBLE FINISHER, TERRAZZO FINISHER

Assisting, helping or supporting the tile, marble and terrazzo mechanic by performing their historic and traditional work assignments required to complete the proper installation of the work covered by said crafts. The term "Ceramic" is used for naming the classification only and is in no way a limitation of the product handled. Ceramic takes into consideration most hard tiles.

### ELECTRONIC SYSTEMS TECHNICIAN

Installation, service and maintenance of low-voltage systems which utilizes the transmission and/or transference of voice, sound, vision, or digital for commercial, education, security and entertainment purposes for the following: TV monitoring and surveillance, background/foreground music, intercom and telephone interconnect, field programming, inventory control systems, microwave transmission,

multi-media, multiplex, radio page, school, intercom and sound burglar alarms and low voltage master clock systems.

Excluded from this classification are energy management systems, life safety systems, supervisory controls and data acquisition systems not intrinsic with the above listed systems, fire alarm systems, nurse call systems and raceways exceeding fifteen feet in length.

TRUCK DRIVER - BUILDING, HEAVY AND HIGHWAY CONSTRUCTION Class 1. Drivers on 2 axle trucks hauling less than 9 ton. Air compressor and welding machines and brooms, including those pulled by separate units, truck driver helpers, warehouse employees, mechanic helpers, greasers and tiremen, pickup trucks when hauling materials, tools, or workers to and from and on-the-job site, and fork lifts up to 6,000 lb. capacity.

- Class 2. Two or three axle trucks hauling more than 9 ton but hauling less than 16 ton. A-frame winch trucks, hydrolift trucks, vactor trucks or similar equipment when used for transportation purposes. Fork lifts over 6,000 lb. capacity, winch trucks, four axle combination units, and ticket writers.
- Class 3. Two, three or four axle trucks hauling 16 ton or more. Drivers on water pulls, articulated dump trucks, mechanics and working forepersons, and dispatchers. Five axle or more combination units.
- Class 4. Low Boy and Oil Distributors.
- Class 5. Drivers who require special protective clothing while employed on hazardous waste work.

TRUCK DRIVER - OIL AND CHIP RESEALING ONLY.

This shall encompass laborers, workers and mechanics who drive contractor or subcontractor owned, leased, or hired pickup, dump, service, or oil distributor trucks. The work includes transporting materials and equipment (including but not limited to, oils, aggregate supplies, parts, machinery and tools) to or from the job site; distributing oil or liquid asphalt and aggregate; stock piling material when in connection with the actual oil and chip contract. The Truck Driver (Oil & Chip Resealing) wage classification does not include supplier delivered materials.

### OPERATING ENGINEERS - BUILDING, HEAVY AND HIGHWAY CONSTRUCTION

Class 1. Power Cranes, Draglines, Derricks, Shovels, Gradalls, Mechanics, Tractor Highlift, Tournadozer, Concrete Mixers with Skip, Tournamixer, Two Drum Machine, One Drum Hoist with Tower or Boom, Cableways, Tower Machines, Motor Patrol, Boom Tractor, Boom or Winch Truck, Winch or Hydraulic Boom Truck, Truck Crane, Tournapull, Tractor Operating Scoops, Bulldozer, Push Tractor, Asphalt Planer, Finishing Machine on Asphalt, Large Rollers on Earth, Rollers on Asphalt Mix, Ross Carrier or similar Machine, Gravel Processing Machine, Asphalt Plant Engineer, Paver Operator, Dredging Equipment, or Dredge Engineer, or Dredge Operator, Central Mix Plant Engineer, CMI or similar type machine, Concrete Pump, Truck or Skid Mounted, Tower Crane, Engineer or Rock Crusher Plant, Concrete Plant Engineer, Ditching Machine with dual attachment, Tractor Mounted Loaders, Cherry Picker, Hydro Crane, Standard or Dinkey Locomotives, Scoopmobiles, Euclid Loader, Soil Cement Machine, Back Filler, Elevating Machine, Power Blade, Drilling Machine, including Well Testing, Caissons, Shaft or any similar type drilling machines, Motor Driven Paint Machine, Pipe Cleaning Machine, Pipe Wrapping Machine, Pipe Bending Machine, Apsco Paver, Boring Machine, (Head Equipment Greaser), Barber-Greene Loaders, Formless Paver, (Well Point System), Concrete Spreader, Hydra Ax, Span Saw, Marine Scoops, Brush Mulcher, Brush Burner, Mesh Placer, Tree Mover, Helicopter Crew (3), Piledriver-Skid or Crawler, Stump Remover, Root Rake, Tug Boat Operator, Refrigerating Machine, Freezing Operator, Chair Cart-Self-Propelled, Hydra Seeder, Straw Blower, Power Sub Grader, Bull Float, Finishing Machine, Self-Propelled Pavement Breaker, Lull (or similar type Machine), Two Air Compressors, Compressors hooked in Manifold, Overhead Crane, Chip Spreader, Mud Cat, Sull-Air, Fork Lifts (except when used for landscaping work), Soil Stabilizer (Seaman Tiller, Bo Mag, Rago Gator, and similar types of equipment), Tube Float, Spray Machine, Curing Machine, Concrete or Asphalt Milling Machine, Snooper Truck-Operator, Backhoe, Farm Tractors (with attachments), 4 Point Lift System (Power Lift or similar type), Skid-Steer (Bob Cat or similar type), Wrecking Shears, Water Blaster.

Class 2. Concrete Mixers without Skips, Rock Crusher, Ditching Machine under 6', Curbing Machine, One Drum Machines without Tower or Boom, Air Tugger, Self-Propelled Concrete Saw, Machine Mounted Post Hole Digger, two to four Generators, Water Pumps or Welding Machines, within 400 feet, Air Compressor 600 cu. ft. and under, Rollers on Aggregate and Seal Coat Surfaces, Fork Lift (when used for landscaping work), Concrete and Blacktop Curb Machine, One Water Pump, Oilers, Air Valves or Steam Valves, One Welding Machine, Truck Jack, Mud Jack, Gunnite Machine, House Elevators when used for hoisting material, Engine Tenders, Fireman, Wagon Drill, Flex Plane, Conveyor, Siphons and Pulsometer, Switchman, Fireman on Paint Pots, Fireman on Asphalt Plants, Distributor Operator on Trucks, Tampers, Self-Propelled Power Broom, Striping Machine (motor driven), Form Tamper, Bulk Cement Plant, Equipment Greaser, Deck Hands, Truck Crane Oiler-Driver, Cement Blimps, Form Grader, Temporary Heat, Throttle Valve, Super Sucker (and similar type of equipment).

### Other Classifications of Work:

For definitions of classifications not otherwise set out, the Department generally has on file such definitions which are available. If a task to be performed is not subject to one of the classifications of pay set out, the Department will upon being contacted state which neighboring county has such a classification and provide such rate, such rate being deemed to exist by reference in this document. If no neighboring county rate applies to the task, the Department shall undertake a special determination, such special determination being then deemed to have existed under this determination. If a project requires these, or any classification not listed, please contact IDOL at 217-782-1710 for wage rates or clarifications.

### LANDSCAPING

Landscaping work falls under the existing classifications for laborer, operating engineer and truck driver. The work performed by landscape plantsman and landscape laborer is covered by the existing classification of laborer. The work performed by landscape operators (regardless of equipment used or its size) is covered by the classifications of operating engineer. The work performed by landscape truck drivers (regardless of size of truck driven) is covered by the classifications of truck driver.