

BM# 2 - ELEV. 589.808'
 STA. 44+84 (IL 159)
 OFFSET - 59' RT.

CUT "□" ON WEST SIDE OF MAST ARM
 SIGNAL FOUNDATION @ SE CORNER OF IL 159
 & SALEM PLACE.

BM# 105 - ELEV. 574.833'
 STA. 525+46 (I-64)
 OFFSET - 108' RT.

CUT "X" ON THE NORTHEAST ANCHOR BOLT
 FOR STREET LIGHT POLE #1B-5 ON THE SOUTH
 SIDE OF I-64 AT THE BEGINNING OF THE
 SOUTHWEST I-64 EXIT RAMP TO IL 159.

BM# 100 - ELEV. 592.270'
 STA. 39+35 (IL 159)
 OFFSET - 52' LT.

CUT "□" ON SOUTH CORNER OF CONCRETE
 FOUNDATION FOR TRAFFIC SIGNAL CONTROL
 BOX ON THE SW CORNER OF IL 159 & RAMPS
 ON THE NORTH SIDE OF I-64.

BM# 134 - ELEV. 572.046'
 STA. 528+05 (I-64)
 OFFSET - 148' LT.

CUT "X" ON THE SOUTHEAST ANCHOR BOLT
 FOR STREET LIGHT POLE #34 ON THE NORTH
 SIDE OF I-64 AT THE END OF THE NORTHWEST
 ENTRANCE RAMP FROM IL 159 JUST EAST OF
 THE ST. CLAIR 10 CINE.

BM# 64 - ELEV. 578.948'
 STA. 536+89 (I-64)
 OFFSET - 2' RT.

CUT "□" ON THE I-64 CENTER MEDIAN
 BARRIER WALL ON THE SOUTH SIDE OF THE
 WEST PIER FOR IL 159 OVERPASS, BELOW
 STRUCTURE PLACE INSCRIBED "STA. 537+26.79"
 & "FAI RT. 64 - SEC. 82-5HB-3."

BM# 125 - ELEV. 573.314
 STA. 550+79 (I-64)
 OFFSET - 93' RT.

CUT "X" ON THE NORTHWEST ANCHOR BOLT FOR
 STREET LIGHT POLE #1C-25 ON THE SOUTH SIDE
 OF I-64 AT THE END OF THE SOUTHEAST I-64
 ENTRANCE RAMP IL 159.

BM# 119 - ELEV. 572.889'
 STA. 550+06 (I-64)
 OFFSET - 102' LT.

CUT "X" ON THE SOUTHWEST ANCHOR BOLT FOR
 STREET LIGHT POLE #1A-19 ON THE NORTH SIDE
 OF I-64 AT THE BEGINNING OF THE NORTHEAST
 EXIT RAMP TO IL 159.

BM# 102 - ELEV. 581.745'
 STA. 20+32 (IL-159)
 OFFSET - 88' LT.

RAILROAD SPIKE DRIVEN IN THE EAST SIDE OF
 POWER POLE ON THE WEST SIDE OF IL 159
 NORTHEAST OF RUBY TUESDAY RESTAURANT AND
 SOUTHEAST OF TACO BELL RESTAURANT.

FILE NAME =	USER NAME = burnsideem	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	ALIGNMENT, TIES AND BENCHMARK SHEET	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pwork\pwork\burnsideem\d0166363\d0166363.dgn	75d59-ATB.dgn	DRAWN -	REVISED -			64	82-5K-2	ST. CLAIR	162	25
PLOT SCALE = 50.0000' / IN.		CHECKED -	REVISED -			CONTRACT NO. 76D59				
PLOT DATE = 9/12/2010		DATE -	REVISED -			FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				
SCALE: _____ SHEET NO. ___ OF ___ SHEETS STA. _____ TO STA. _____										