SUMMARY OF QUANTITIES

CODE NO.	ITEM DESCRIPTION: ITEM	UNIT	HBP FUNDS 80% FED 20% STATE BRIDGE 0011 RURAL
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	4
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1
70106700	TEMPORARY RUMBLE STRIPS	EACH	6
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	96
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	2369
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	863
70400100	TEMPORARY CONCRETE BARRIER	FOOT	475
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	425
78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	2369
78200410	GUARDRAIL MARKERS, TYPE A	EACH	16
78200510	BARRIER WALL MARKERS, TYPE A	EACH	14
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4
78300100	PAVEMENT MARKING REMOVAL	SQ FT	629
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	6
X2070304	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	86
X5080600	MECHANICAL SPLICERS	EACH	156
Z0004552	APPROACH SLAB REMOVAL	SQ YD	116
Z0018002	DRAINAGE SCUPPERS, DS-11	EACH	2
Z0026407	TEMPORARY SHEET PILING	SQ FT	1102
Z0073002	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	467
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2
Z0046304	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	130

FINAL SURVEY	BY	DATE
SURVEYED		
PLOTTED		
TEMPLATE		
AREAS		
AREAS CHECKED		
NOTE BOOK		
NO.		

ORIGINAL SURVEY	BY	DATE
SURVEYED		
PLOTTED		
TEMPLATE		
AREAS		
AREAS CHECKED		
NOTE BOOK		
NO.		

© Copyright Hanson Professional Services Inc. 2010

HANSON

FILE NAME = c:\working\cox01283\dms23631\D978141-sht-SQQ.dgn	USER NAME = Cox01283	DESIGNED - JDW	REVISED -
		DRAWN - BKC	REVISED -
	PLOT SCALE = 2.0000 ' / in.	CHECKED - MH	REVISED -
	PLOT DATE = 10\01\2010	DATE - 06-30-2010	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

IL-146 (OVER SIMMONS CREEK) SUMMARY OF QUANTITIES

SCALE: NTS | SHEET NO. OF SHEETS | STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
885	6B-2	POPE	48	4

CONTRACT NO. 78141

FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT