

DATE	
BY	
FINAL SURVEY	
SURVEYED	
PLOTTED	
TEMPLATE	
AREAS	
AREAS CHECKED	
NO.	



DATE	
BY	
ORIGINAL SURVEY	
SURVEYED	
PLOTTED	
TEMPLATE	
AREAS	
AREAS CHECKED	
NO.	

SEEDING SCHEDULE										
LOCATION			25000200	25000350	25000400	25000500	25000600	25000700	25100115	28000250
			SEEDING, CLASS 2	SEEDING, CLASS 7	NITROGEN FERTILIZER NUTRIENT	PHOSPHORUS FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT	AGRICULTURAL GROUND LIMESTONE	MULCH, METHOD 2	TEMPORARY EROSION CONTROL SEEDING
BEGIN STATION	END STATION	OFFSET	ACRES	ACRES	POUNDS	POUNDS	POUNDS	TONS	ACRES	POUND
1435+69.50	1438+51.00	LT/RT	0.10	0.10	13	9	9	0.2	0.10	10
1439+93.50	1442+75.00	LT/RT	0.25	0.25	33	23	23	0.5	0.25	25
<b>TOTAL</b>			<b>0.35</b>	<b>0.35</b>	<b>46</b>	<b>32</b>	<b>32</b>	<b>0.7</b>	<b>0.35</b>	<b>35</b>

PAVEMENT MARKING SCHEDULE								
LOCATION			78001110	78200410	78200510	78201000	78300200	NOTE
			PAINT PAVEMENT MARKING - LINE 4"	GUARDRAIL MARKERS, TYPE A	BARRIER WALL MARKERS, TYPE A	TERMINAL MARKER DIRECT APPLIED	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	
BEGIN STATION	END STATION	OFFSET	FOOT	EACH	EACH	EACH	EACH	
1435+69.50	1438+42.00	CENTERLINE					3	
1435+69.50	1442+75.00	LT & RT	1411					WHITE SOLID
1435+69.50	1440+20.00	CENTERLINE	113					YELLOW/SKIP DASH RT
1435+69.50	1441+20.00	CENTERLINE	551					YELLOW/SOLID LT
1435+90.36	1438+36.00	RT		4				
1435+90.36	-	RT				1		
1436+77.87	1438+36.00	LT		4				
1436+77.87	-	LT				1		
1438+36.00	1440+08.00				7			STG 2 - NEW BRIDGE NEXT TO TRAFFIC
1438+36.00	1440+08.00				7			STG 2 - NEW BRIDGE UNDER CONST.
1440+08.00	1442+54.00	RT		4				
1440+08.00	1442+54.14	LT		4				
1440+14.00	1442+75.00	CENTERLINE					3	
1440+20.00	1442+75.00	CENTERLINE	255					YELLOW/SOLID RT
1441+20.00	1442+75.00	CENTERLINE	39					YELLOW/SKIP DASH LT
1441+66.63	-	RT				1		
1442+54.14	-	LT				1		
<b>TOTAL</b>			<b>2369</b>	<b>16</b>	<b>14</b>	<b>4</b>	<b>6</b>	

FILE NAME =	USER NAME = Cov01283	DESIGNED - JDW	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>IL-146 (OVER SIMMONS CREEK) SCHEDULE OF QUANTITIES</b>	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
ct\working\cov01283\dms23631\0978141-sht	schedule.dgn	DRAWN - BKC	REVISED -			885	6B-2	POPE	48	7	
	PLOT SCALE = 2,000' / in.	CHECKED - MH	REVISED -			SCALE: NTS		SHEET NO. OF SHEETS		STA.	TO STA.
	PLOT DATE = 10/01/2010	DATE - 06-30-2010	REVISED -					FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT	
						CONTRACT NO. 78141					